

## ***K Remediation, Decommissioning, Restoration, and Aftercare***

### Restoration

- Site filling is nearing its completion and appreciable stone is picked out by hand. Topsoil is recovered and relayed on the surface to a depth of approximately 225 mm. Topsoil is then raked and grass seed is planted at a rate of 40 g/m<sup>2</sup>. Grass seed planting is only done during the grass growing season.

### Decommissioning

- On completion remove gateway and complete fence back on original line. Fill in the channels of the wheel wash. Leave wheel wash slab in place. Remove signage as required. Remove ESB overhead barriers.

### Note: Item (r) in the Checklist

- The waste placed is inert with exception of the topsoil. Consequently financial security for maintenance and after care is not offered. The land will be used agriculturally.

For inspection purposes only.  
Consent of copyright owner required for any other use.