

ATTACHMENTS TABLE OF CONTENTS

SECTION B GENERAL

Attachment B1: Drawing 1 – Agglomeration Plan

Attachment B2: Drawing 2 – Site Plan & Site Boundary

Attachment B3: Drawing 3 – Location of Primary Discharge

Drawing 4 – Monitoring and Sampling Locations Associated with Primary Discharge Point

Attachment B6: Part 8 Document

Attachment B8: Drawing 5 – Location of Site Notice
Site and Newspaper Notice

SECTION C INFRASTRUCTURE & OPERATION

Attachment C1: Drawing 6 – Pumping Station Locations

Drawing 7 – General Arrangement of Water Treatment Plant

Drawing 8 – Schematic Flow Diagram of Plant

Attachment C2: Discharge Point Details

SECTION D DISCHARGES TO THE AQUATIC ENVIRONMENT

Attachment D1: Table D.1 (i) (a) Emissions to Surface Water (Primary Discharge Point)

Table D.1 (i) (b) Emissions to Surface Water – Characteristics of the Emission
(Primary Discharge Point)

Table D.1 (i) (c) Dangerous Substance to Surface Water – Characteristics of the
Emission (Primary Discharge Point)

Table D.1 (iv) Influent Monitoring Data

Attachment D2: Tabular Data on Discharge Point

SECTION E MONITORING

Attachment E.1: Waste Water Frequency and Quantity of Discharge

Attachment E.2: Accreditation Certificate – Euro Environmental Services Ltd.

Attachment E.3: Tabular Data on Monitoring and Sampling Points

Attachment E.4: Sampling Data

SECTION F EXISTING ENVIRONMENT & IMPACT OF THE DISCHARGE(S)

Attachment F.1: Table F.1 (i)(a) Surface Water Monitoring (Primary Discharge Point –
Downstream

Table F.1 (i)(b) Surface Water Monitoring (Dangerous Substances- Primary
Discharge Point) – Downstream

Table F.1 (i)(a) Surface Water Monitoring (Primary Discharge Point – Upstream

Table F.1 (i)(b) Surface Water Monitoring (Dangerous Substances- Primary
Discharge Point) – Upstream

Attachment F.2: Drawing 9 – Emy Lough Water Abstraction


SECTION G PROGRAMME OF IMPROVEMENTS

Attachment G.2: Draft River Basin Management Plan for the Neagh Bann International River
Basin District

Monaghan County Councils Phosphate Implementation Report 2006

Attachment B.1

*For inspection purposes only.
Consent of copyright owner required for any other use.*



LEGEND:
 LICENCE APPLICATION AREA



REV	DESCRIPTION	BY	CHK	APP	DATE

Monaghan County Council
 Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHERKINMAN, DUBLIN 14
 TEL: +353 (0) 1291 4800
 FAX: +353 (0) 1298 9521
 e-mail: info@pimcc.com




Project:
EMYVALE
 DISCHARGE LICENCE APPLICATION

Drawing Title:
WASTE WATER TREATMENT WORKS
 AGGLOMERATION PLAN

Scale @	Drawn	Date	Checked	Date	Approved	Date
1:10,000	HS	20/03/09	CS	20/03/09	SD	20/03/09
Project No.	Office	Type	Drawing No.	Revision		
C007400			DRAWING 1			

Attachment B.2

For inspection purposes only.
Consent of copyright owner required for any other use.



REV	DESCRIPTION	BY	CHK/APP	DATE

Monaghan County Council
 Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHFARNHAM, DUBLIN 14
 TEL: +353 (0) 1291 4800
 FAX: +353 (0) 1298 9521
 e-mail: info@pimcc.com




Project: EMYVALE
 DISCHARGE LICENCE APPLICATION

Drawing Title: WASTE WATER TREATMENT PLANT
 SITE PLAN

Scale @	A3	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	CS	20.03.09	SD	20.03.09	
Project No.		Office	Type	Drawing No.		Revision	
C007400				DRAWING 2			

Attachment B.3

*For inspection purposes only.
Consent of copyright owner required for any other use.*



REV	DESCRIPTION	BY	CHK	APP	DATE

Monaghan County Council
 Comhairle Contae Mhúineacháin




PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHERRINKIN, DUBLIN 14



Project:
EMYVALE DISCHARGE LICENCE APPLICATION

Drawing Title:
PLAN AT DISCHARGE POINT

Scale @	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	CS	20.03.09	SD	20.03.09
Project No.	Office	Type	Drawing No.	Revision		
C007400			DRAWING 3			



- LEGEND:**
- SAMPLING POINT
 - MONITORING LOCATION
 - DISCHARGE POINT

REV	DESCRIPTION	BY	CHK/APP	DATE

Monaghan County Council
Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
NUTSGROVE OFFICE PARK
NUTSGROVE AVENUE
RATHERSHAMNAN, DUBLIN 14



EMYVALE
DISCHARGE LICENCE APPLICATION

PRIMARY DISCHARGE, SAMPLING & MONITORING LOCATIONS
KEY PLAN

Scale @	A3	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	CS	20.03.09	SD	20.03.09	
Project No.		Office	Type	Drawing No.		Revision	
C007400				DRAWING 4			

Attachment B.6

For inspection purposes only.
Consent of copyright owner required for any other use.



**DESCRIPTION DOCUMENT
OF
PROPOSED DEVELOPMENT
AT
EMYVALE WASTEWATER TREATMENT PLANT**

**Under Part 8 of the Planning and Development
Regulations 2001 (S.I. no 600 of 2001)**

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Water Services Department
Monaghan County Council
The Glen
Monaghan

August 2006

Description of Proposed Development

1 Introduction

In accordance with the provision of Part 8 of the Planning and Development Regulations 2001 this document describes the proposed development at Emyvale Wastewater Treatment Plant. It is proposed to upgrade the existing treatment plant to cater for a population equivalent of 2000. The upgraded plant will produce a treated effluent quality of 25 mg/l BOD and 35 mg/l SS.

2 Location Details

County	Monaghan
DED	Emyvale DED
Parish	Donagh
Townland	Derrygasson Upper
Os Sheet Number	873d, VI 4
NG Co ordinates	267,343

A site location map and layout plan are attached.

3 General Information

The existing treatment plant at Derrygasson Upper, Emyvale, County Monaghan is design to cater for a PE of 825. Due to additional houses being built in the village and to allow for future development it is necessary to up grade the plant.

The existing works comprises of the following units which physically and biologically treats the incoming wastewater

- Hand raked screen
- Storm overflow
- Primary settlement tank
- Pump chamber
- 2 Biological filters
- Humus tank
- v-notch weir outlet chamber

4 Design Demand

A design PE of 2000 and 6 DWF will be used to allow for current demand and future development in the village.

Accurate inflow data for the plant is not available. The influent entering the plant has been estimated based on a house count of 1045 PE at a DWF of 180l/h/day. The following table summarises current and design influent characteristics.

PE	No.	DWF m ³ /day	6 DWF m ³ /day	6 DWF l/sec	BOD ₅ Kg/Day	SS Kg/Day
Current PE	1045	171.9	1031.4	11.99	57.3	71.6
Design PE	2000	360.0	2160	25	120.0	150.0

5 Extent of Development

The up grading works proposed are as follows:

1. Installation of inlet screening unit
2. Construction of a 2 no below ground primary settlement tank for a design PE of 2000. The tank is to have a concrete lid with lockable hatches
3. Installation of 2 no RBC treatment units
4. Construction of a final settlement tank for design loading of 1500
5. Site works comprising of paving, kerbing, landscaping and entrance gate within the confines of the site as per drawing Emyvale 2005 – 03.
6. Construction of a storage bund and install a GRP tank and for ferric sulphur dosing system.

Layout plans, elevations and section drawings are attached.

6 Main Features of Development

Inlet Screen

The existing hand raked screen is allowing a large volume of inorganic material enter the treatment process and causing operational problems downstream. It is proposed to install a Haigh Ace 290 inlet screener unit, a brochure and drawings are attached for information. The macerator pump and Lipactor unit ensures that screenings are disposed of in a safe and regular manner, mechanically. Therefore there is no manual handling by the plant operator of organic waste. The Existing chamber can be utilised for the new mechanical screen. A concrete plinth will be required to facilitate the Lipactor unit.

Primary Settlement Tank

The existing settlement tank is designed for a population equivalent of 730, however this does not include any capacity for sludge storage. The tank has a surface area of 18m² and a volume of 49m³. Based on a sludge production rate of 10l/h/week, for a population equivalent of 730, the volume of sludge produced over a 6 week period would be 43.8m³. Therefore the volume of the tank available for settlement reduces from 49m³ to 5.2m³, or a PE of 52.

The Sludge Report prepared for Monaghan County Council estimated the 20 year sludge production of the plant to be 240.9 m³/year for a PE of 440. This figure is expected to be exceeded by early in 2006 in light of the number of planning applications received for development in the village. A PE of 2000 would produce a volume of 1040m³/year or 20m³/week.

2 new primary settling tanks are to be constructed for a design PE of 2000 and a retention time of 2 hours. The volume of the 2 tanks will be 259.4m³. The Surface Area will be 129m². This includes an allowance for 8 weeks sludge storage. A drawing of the proposed Primary Settlement Tank (Emyvale 2006-05) is attached for information.

Secondary Treatment Units and Settlement Tank

Biological Filter

There are 2 biological filters working in Emyvale Sewerage treatment works with a capacity to treat a PE of 1215. The capacity in the two biological filters is sufficient for the current PE. However it is expected that additional loadings will be entering the plant by the end of 2006 due to houses currently under construction in the village.

To ensure the plant can cater for future loadings, 2 new RBC unit capable of treating a PE of 500 each, are proposed to be constructed as part of the upgrading works. This would increase the secondary treatment process to a capacity of 2215.

The existing pumps, pumping the flow to the high level splitter chamber, are to be upgraded. 2 new pumps will be required 1 duty and 1 assist (also used as standby). The pump shall be installed in the existing sump chamber.

Humus Tank

The existing Humus tank has a surface area of 21.2m². This relates to a population equivalent of 763 persons. There is limited capacity in the existing humus tank. An additional secondary settlement or humus tank is required to cater for the existing demand and new developments which will be contributing to the inflow volume over the next 18 months and also for the long term development in the area.

A design PE of 1500 has been used to determine the size of new humus tank required. There are a number of companies which supply prefabricated tanks which are transported to site and installed with minimum site works.

A typical tank is as per attached detailed drawing and brochure from John Molloy Engineering

Ferric Sulphur Dosing

In order to reduce the phosphate level in the effluent it is proposed to add ferric sulphur to the effluent in the final settlement tank prior to discharging to the river. A GRP tank will be used to store the chemical which will be placed inside a storage bund to ensure any leakage would be contained within the bund and eliminate the risk of any spillage entering the river adjacent to the site. Dosing lines from the tank to the secondary settlement tank will be laid under ground.

Site Works

A new bitmac road and footpaths within the site area are to be constructed as per layout drawing. The area between the treatment units is to have a pea gravel finish. The remainder of the site is to be grass landscaped finish. On completion of the works, the area is to be screened/landscaped using hedging and trees native to the area and similar to existing.

7 Drawing Schedule

Drawing No	Title
Emyvale 2006 – 01	Location Map
Emyvale 2006 – 02	Existing layouts
Emyvale 2006 – 03	Proposed layout of new treatment units fencing and pipe work
Emyvale 2006 – 04	Longitudinal section through site
Emyvale 2006 – 05	Proposed primary settlement tank
Emyvale 2006 – 06	Details of Ferric Sulphur Storage Bund & Pump House
LSS Drawing no 12158/1	Contour survey of Site
HP/122/C/1	Plan of ace 290 inlet screener. As provided by supplier
HP/	Typical Concrete Plinth for Lipactor 304

Brochure and drawings as received from John Molloy Engineering for Secondary Settlement Tank

Brochure “Integrated Systems for biological treatment” for RBC units

For inspection purposes only.
Consent of copyright owner required for any other use.

**MONAGHAN COUNTY COUNCIL
PLANNING & DEVELOPMENT**

This report has been prepared in accordance with Part VIII of the Planning and Development Regulations (S.I. No. 600 of 2001) and is being submitted to the members of Monaghan County Council in the course of compliance with Section 179 of the Planning & Development Act 2000

A. Nature and extent of the proposed development and the principal features thereof:

The development consists of an extension to the Emyvale wastewater treatment plant comprising of new inlet screening unit, 2 no. underground primary settlement tanks, 2 RBC treatment units, 1 secondary settlement tank, ferric sulphur storage bund and tank and all associated site works at Derrygasson Upper, Emyvale.

B. Evaluation of the likely implication of the proposed development with respect to the proper planning and development of the area:

The proposed development is adjoining the existing wastewater treatment operation. Whilst the structure will be visible from the public road, by virtue of the existing landscaping to the rear and side of the site and that it is set within the existing structures on site, the visual impact of the proposal will be limited. The development is considered acceptable in that it will not be detrimental to the visual amenity of the area and allows for the provision of vital infrastructure for the development of the area.

C. List of the persons/bodies who made submissions/observations with respect to the proposed development:

ERFB- no specific objections stated and the upgrading of the wastewater treatment system is acceptable.


No response has been received from the DEHLG, An Taisce, Bord Failte, NEHB.

D. Summary of the issues with respect to the proper planning and development of the area raised by persons/bodies who made submissions/observations and the Council's response thereto:


The existing sewerage treatment system is under severe pressure in terms of the system being over-loaded. The proposed system is to cater for a PE of 2000 persons. The receiving capacity of the Mountain Water River is highlighted as varied due to different flow rates but this sewerage treatment system has additional storage capacity to allow for controlled discharge rates to the watercourse.

E. Conclusions:

Having considered the proper planning and sustainable development of the area I recommend that Monaghan County Council proceed with the development as proposed in accordance with the plans and documents submitted on the 3rd August 2006 and the conditions attached.



Paul Clifford
Director of Services



Date

For inspection purposes only.
Consent of copyright owner required for any other use.

P06/8009 Monaghan County Council, Derrygasson Upper, Emyvale, Co. Monaghan.

1. Appropriate procedures to detect pump failure/blockage etc. and prevent any discharge of polluting matter to surface or groundwaters to be put in place.
2. Spill containment measures for the delivery of bulk chemicals shall be installed prior to commencement of further works on site.
3. Measures to be taken during construction to prevent the discharge of suspended solids or other harmful matter to the watercourse.
4.
 - a. All trees and hedgerows bounding the site to be permanently retained in this development, to be reinforced with additional planting and to be protected from damage at all times, particularly during building operations.
 - b. Planting as required above to be carried out in the first planting season following commencement of building operations and permanently retained thereafter. Any plant which fails in the first planting season to be replaced.
 - c. Any boundary fencing to be of stained wood.
5. Subject to the above conditions, the development to be carried out in strict conformity with the lodged plans and specifications.

THE REASONS FOR THE IMPOSITION OF THE ABOVE CONDITIONS ARE:

- 1,2 In the interest of proper planning and protection of public health.
- 3,4 To protect the amenity of the area.
5. To prevent unauthorised development.




PAUL CLIFFORD
DIRECTOR OF SERVICES

24 Nov 2006
DATE

Attachment B.8

For inspection purposes only.
Consent of copyright owner required for any other use.



LOCATION OF THE
SITE NOTICE

ACCESS ROAD

FENCE
For inspection purposes only.
Consent of copyright owner required for any other use.

REV	DESCRIPTION	BY	CHK	APP	DATE

Monaghan County Council
Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
NUTSGROVE OFFICE PARK
NUTSGROVE AVENUE
RATHERKINHAM, DUBLIN 14
TEL: +353 (0) 1291 4800
FAX: +353 (0) 1298 9521
e-mail: info@pimcc.com



Project:
EMYVALE
DISCHARGE LICENCE APPLICATION

Drawing Title:
WASTE WATER TREATMENT PLANT
LOCATION OF THE SITE NOTICE

Scale @	A3	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	CS	20.03.09	SD	20.03.09	
Project No.	Office	Type	Drawing No.	Revision			
C007400			DRAWING 5				

SITE NOTICE



Monaghan County Council

APPLICATION TO THE ENVIRONMENTAL PROTECTION AGENCY FOR A WASTE WATER DISCHARGE LICENCE

Notice is hereby given that Monaghan County Council of County Offices, The Glen, Monaghan, Co. Monaghan is applying to the Environmental Protection Agency for a Waste Water Discharge Licence for the Emyvale Waste Water Works at Derrygasson Upper, Co. Monaghan in accordance with the Waste Water Discharge (Authorisation) Regulations 2007 (S.I. No. 684 of 2007).

The Waste Water Works comprises a network of gravity sewers, a number of small pumping stations and associated rising main and a Waste Water Treatment Plant serving Emyvale and its environs.

The primary discharge from the Waste Water Treatment Works is directly to the Mountain Water River (at National Grid Reference 267964 E, 343554N) in the townland of Derrygasson Upper, Co. Monaghan. The associated Waste Water Treatment Plant is located at National Grid Reference 267951E, 343612N also in the townland of Derrygasson Upper, Co. Monaghan.

A copy of the waste water discharge licence application shall, as soon as practicable after receipt by the Environmental Protection Agency, be available for inspection or purchase at the

- Environmental Protection Agency, PO Box 3000, Johnstown Castle Estate, Co. Wexford, Lo Call 1980 335599 Telephone: 053-9160600 Fax: 053-9160699 Email: info@epa.ie.

and at

- Monaghan County Council Offices, The Glen, Monaghan, Co Monaghan, Telephone: 047-30500, Fax: 047-82739

Submissions in relation to this application may be made to the Environmental Protection Agency at its headquarters described above.

Signed: David Fallon Director of Services

Date: 26/03/2009

Public Notices • Announcements



Comhairle Contae Mhuineacháin www.monaghan.ie

MONAGHAN COUNTY

APPLICATION TO THE ENVIRONMENTAL PROTECTION AGENCY FOR A WASTE WATER DISCHARGE LICENCE

Notice is hereby given that Monaghan County Council of County Offices, The Glen, Monaghan, Co. Monaghan is applying to the Environmental Protection Agency for a Waste Water Discharge Licence for the Emyvale Waste Water Works at Derrygasson Upper, Co. Monaghan in accordance with the Waste Water Discharge (Authorisation) Regulations 2007 (S.I. No. 684 of 2007).

The Waste Water Works comprises a network of gravity sewers, a number of small pumping stations and associated rising main and a Waste Water Treatment Plant serving Emyvale and its environs.

The primary discharge from the Waste Water Treatment Works is directly to the Mountain Water River (at National Grid Reference 267964 E, 343554N) in the townland of Derrygasson Upper, Co. Monaghan. The associated Waste Water Treatment Plant is located at National Grid Reference 267951E, 343612N also in the townland of Derrygasson Upper, Co. Monaghan.

A copy of the waste water discharge licence application shall, as soon as practicable after receipt by the Environmental Protection Agency, be available for inspection or purchase at the

- Environmental Protection Agency, PO Box 3000, Johnstown Castle Estate, Co. Wexford, Lo Call 1980 335599 Telephone: 053-9160600 Fax: 053-9160699 Email: info@epa.ie.

and at

- Monaghan County Council Offices, the Glen, Monaghan, Co Monaghan, Telephone: 047-30500, Fax: 047-82739

Submissions in relation to this application may be made to the Environmental Protection Agency at its headquarters described above.

Signed: David Fallon Date: 26/03/2009

Director of Services

APPLICATION TO THE ENVIRONMENTAL PROTECTION AGENCY FOR A WASTE WATER DISCHARGE LICENCE

Notice is hereby given that Monaghan County Council of County Offices, The Glen, Monaghan, Co. Monaghan is applying to the Environmental Protection Agency for a Waste Water Discharge Licence for the Inniskeen Waste Water Works at Lacklom, Co. Monaghan in accordance with the Waste Water Discharge (Authorisation) Regulations 2007 (S.I. No. 684 of 2007).

The Waste Water Works comprises a network of gravity sewers, a number of small pumping stations and associated rising main and a Waste Water Treatment Plant serving Inniskeen and its environs.

The primary discharge from the Waste Water Treatment Works is directly to the Fane River (at National Grid Reference 293957E, 306683N) in the townland of Lacklom, Co. Monaghan. The associated Waste Water Treatment Plant is located at National Grid Reference 293924E, 306661N also in the townland of Lacklom, Co. Monaghan.

A copy of the waste water discharge licence application shall, as soon as practicable after receipt by the Environmental Protection Agency, be available for inspection or purchase at the

- Environmental Protection Agency, PO Box 3000, Johnstown Castle Estate, Co. Wexford, Lo Call 1980 335599 Telephone: 053-9160600 Fax: 053-9160699 Email: info@epa.ie.

and at

- Monaghan County Council Offices, The Glen, Monaghan, Co Monaghan, Telephone: 047-30500, Fax: 047-82739

Submissions in relation to this application may be made to the Environmental Protection Agency at its headquarters described above.

Signed: David Fallon Date: 26/03/2009

Director of Services

APPLICATION TO THE ENVIRONMENTAL PROTECTION AGENCY FOR A WASTE WATER DISCHARGE LICENCE

Notice is hereby given that Monaghan County Council of County Offices, The Glen, Monaghan, Co. Monaghan is applying to the Environmental Protection Agency for a Waste Water Discharge Licence for the existing Waste Water Works at Glaslough, Glaslough Village, Co. Monaghan in accordance with the Waste Water Discharge (Authorisation) Regulations 2007 (S.I. No. 684 of 2007).

The Waste Water Works comprises an Integrated Constructed Wetlands for the treatment of municipal sewerage serving Glaslough Village.

The primary discharge from the Waste Water Treatment Works is directly to the Mountain Water River (at National Grid Reference 272194E 342230N) in the townland of Glaslough, Co. Monaghan. The associated Integrated Constructed Wetlands is located at National Grid Reference 272027E 342135N also in the townland of Glaslough, Co. Monaghan.

A copy of the waste water discharge licence application shall, as soon as practicable after receipt by the Environmental Protection Agency, be available for inspection or purchase at the

- Environmental Protection Agency, PO Box 3000, Johnstown Castle Estate, Co. Wexford, Lo Call 1980 335599 Telephone: 053-9160600 Fax: 053-9160699 Email: info@epa.ie.

and at

- Monaghan County Council Offices, The Glen, Monaghan, Co Monaghan, Telephone: 047-30500, Fax: 047-82739

Submissions in relation to this application may be made to the Environmental Protection Agency at its headquarters described above.

Signed: David Fallon Date: 26/03/2009

Monaghan County Council Environment Section

www.monaghan.ie

ENVIRONMENTAL AND RECREATION IMPROVEMENT FUND

Applications are now being sought from Tidy Towns Groups, Resident Associations, Youth Groups and other community based organisations wishing to avail of funding from Monaghan County Council's Environmental and Recreation Improvement Fund 2009.

The aim of this fund is to assist community groups engaged in environmental work in their locality. The type of work would typically include:-

- Maintenance of open spaces
- Tree, shrub, hedge and flower planting
- Litter management
- Painting
- Repair of fences, walls etc.

Application Form and Guidelines are available from the Environment Section. Contact 047 30593 or e-mail jmaguir2@monaghancoco.ie or download from www.monaghan.ie.

Applications will only be accepted from members of the Tidy Towns & Residents Association Network.

Closing date for receipt of completed applications is 24th April 2009.

Roads Act 1993 Tempo


Temporary closing of Roads pursuant to Section 75 of Roads Act 1993 as to public traffic, the road described hereunder from Thursday 9th April 2009.

Road Closed

1. LS06340 & LS06341

Attachment C.1

For inspection purposes only.
Consent of copyright owner required for any other use.



Monaghan County Council
 Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHFRANKLIN, DUBLIN 14

TEL: +353 (0) 1291 4800
 FAX: +353 (0) 1298 9521
 e-mail: info@pimcc.com




Project:
EMYVALE DISCHARGE LICENCE APPLICATION

Drawing Title:
WASTE WATER TREATMENT PLANT PUMPING STATION LOCATIONS

REV	DESCRIPTION	BY	CHK/APP	DATE

Scale @ A3	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20/03/09	CS	20/03/09	SD	20/03/09
Project No.	Office	Type	Drawing No.	Revision		
C007400			DRAWING 6			



REV	DESCRIPTION	BY	CHK/APP	DATE

Monaghan County Council
 Comhairle Contae Mhúineacháin




PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHERSHAMMAN, DUBLIN 14
 TEL: +353 (0) 1291 4800
 FAX: +353 (0) 1298 9521
 e-mail: info@pimcc.com



Project:
 EMYVALE
 DISCHARGE LICENCE APPLICATION

Drawing Title:
 WASTE WATER TREATMENT PLANT
 EXISTING SITE - GENERAL ARRANGEMENTS

Scale @	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	CS	20.03.09	SD	20.03.09
Project No.	Office	Type	Drawing No.	Revision		
C007400			DRAWING 7			



For inspection purposes only.
Consent of copyright owner required for any other use.

REV	DESCRIPTION	BY	CHK/APP	DATE

Monaghan County Council
Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
NUTSGROVE OFFICE PARK
NUTSGROVE AVENUE
RATHERRINKIN, DUBLIN 14



Project: EMYVALE
DISCHARGE LICENCE APPLICATION

Drawing Title:
WASTE WATER TREATMENT PLANT
SCHEMATIC FLOW DIAGRAM

Scale @	A3	Drawn	Date	Checked	Date	Approved	Date
1:500	HS	20.03.09	20.03.09	CS	20.03.09	SD	20.03.09
Project No.	C007400	Office	Type	Drawing No.	DRAWING 8	Revision	

Attachment C.2

For inspection purposes only.
Consent of copyright owner required for any other use.

Discharge Point/Storm Over Flow Code	Name	Easting	Northing	Type	Receiving Waters	Receiving Water System Type
SW1(P)	Emyvale WWTW	267964	343554	Open Pipe Discharge	Mountain Water River	Pipe to Open Channel

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Attachment D.1

For inspection purposes only.
Consent of copyright owner required for any other use.

Table D.1(i)(a): EMISSIONS TO SURFACE/GROUND WATERS (Primary Discharge Point)

Discharge Point Code: SW-1

Local Authority Ref No:	
Source of Emission:	Emyvale Water Treatment Works
Location:	Emyvale, Derrygasson Upper, Co.Monaghan
Grid Ref (12 digits, 6E, 6N)	267964 / 343554
Name of Receiving waters:	Mountain Water River
Water Body:	River Water Body
River Basin District	Neagh Bann IRBD
Designation of Receiving Waters:	Not Applicable
Flow Rate in Receiving Waters:	1.49 m ³ .sec ⁻¹ Dry Weather Flow 0.099 m ³ .sec ⁻¹ 95% Weather Flow
Additional Comments (e.g. commentary on zero flow or other information deemed of value)	

Emission Details:

(i) Volume emitted			
Normal/day	184 m ³	Maximum/day	212 m ³
Maximum rate/hour	8.8 m ³	Period of emission (avg)	60 min/hr 24 hr/day 365 day/yr
Dry Weather Flow	0.0024 m ³ /sec		

For inspection purposes only. Consent of copyright owner required for any other use.

Table D.1(i)(b): EMISSIONS TO SURFACE/GROUND WATERS - Characteristics of The Emission (Primary Discharge Point)

Discharge Point Code: SW-1

Substance	As discharged			
	Unit of Measurement	Sampling Method	Max Daily Avg.	kg/day
pH	pH	24 hr flow proportional	= 7.75	
Temperature	°C	24 hr flow proportional	= 9.3	
Electrical Conductivity (@ 25°C)	µS/cm	24 hr flow proportional	= 964	
Suspended Solids	mg/l	24 hr flow proportional	= 115	21.16
Ammonia (as N)	mg/l	24 hr flow proportional	= 38	6.992
Biochemical Oxygen Demand	mg/l	24 hr flow proportional	= 55	10.12
Chemical Oxygen Demand	mg/l	24 hr flow proportional	= 185	34.04
Total Nitrogen (as N)	mg/l	24 hr flow proportional	= 35.3	6.49
Nitrite (as N)	mg/l	24 hr flow proportional	= 0.139	0.025
Nitrate (as N)	mg/l	24 hr flow proportional	= 41	7.54
Total Phosphorous (as P)	mg/l	24 hr flow proportional	= 8	1.472
OrthoPhosphate (as P)	mg/l	24 hr flow proportional	= 8	1.472
Sulphate (SO ₄)	mg/l	24 hr flow proportional	= 83.6	15.38
Phenols (Sum)	µg/l	24 hr flow proportional	< 0.1	0.0184

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Table D.1(i)(c): DANGEROUS SUBSTANCE EMISSIONS TO SURFACE/GROUND WATERS - Characteristics of The Emission (Primary Discharge Point)

Discharge Point Code: SW-1

Substance	As discharged			
	Unit of Measurement	Sampling Method	Max Daily Avg.	kg/day
Atrazine	µg/l	24 hr flow proportional	< 0.01	0
Dichloromethane	µg/l	24 hr flow proportional	< 1	0
Simazine	µg/l	24 hr flow proportional	< 0.01	0
Toluene	µg/l	24 hr flow proportional	< 1	0
Tributyltin	µg/l	24 hr flow proportional	< 0.2	0
Xylenes	µg/l	24 hr flow proportional	< 1	0
Arsenic	µg/l	24 hr flow proportional	< 0.96	0
Chromium	µg/l	24 hr flow proportional	< 0.93	0
Copper	µg/l	24 hr flow proportional	= 31.4	2.11
Cyanide	µg/l	24 hr flow proportional	< 5	0
Flouride	µg/l	24 hr flow proportional	= 0.17	0.011
Lead	µg/l	24 hr flow proportional	< 0.38	0
Nickel	µg/l	24 hr flow proportional	< 0.47	0
Zinc	µg/l	24 hr flow proportional	= 36.7	2.46
Boron	µg/l	24 hr flow proportional	= 115.6	7.76
Cadmium	µg/l	24 hr flow proportional	< 0.09	0
Mercury	µg/l	24 hr flow proportional	< 0.2	0
Selenium	µg/l	24 hr flow proportional	= 1	0.067
Barium	µg/l	24 hr flow proportional	= 13	0.873

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Influent	Date of Sampling	Sample Type (C or G)	BOD mg/l	COD mg/l	TSS mg/l	Total P mg/l P	Ortho P mg/l P	Total N mg/l N	NH ₃ -N mg/l N	Nitrate NO ₃	Nitrite NO ₂	TON mg/l N	TKN mg/l N	Conductivity uscm	DO %	DO mg/l	pH	Phenols Total	Sulphate	Temp
Influent	2/11/2004	C	463	1649	1120	6.9	6.3		41	1.1										
Influent	3/4/2004	C	463	657	418		5.3	16	34	2										
Influent	4/7/2004	C	419	619	506	4.1	3.8		46	5.1										
Influent	4/21/2004	C	386	902	461	11	11		54	3.1										
Influent	5/12/2004	C	572	795	287		6.1		50	24										
Influent	6/16/2004	C	646	839	639	10.9	10.2	28	8.4	16										
Influent	7/21/2004	C	354	531	390		4		53	4										
Influent	8/24/2004	C	542	675	437		5.1		49											
Influent	9/15/2004	C	233	548	244	5.1	4.2		41	2.8										
Influent	11/2/2004	C	779	1519	437	5.2		13.1	31	8.8										
Influent	17-Feb-05	C	298	690	550	4.6	3.9		42	4.1						298				
Influent	19-Apr-05	C	467	731	480		6.2		68	3.9						467				
Influent	17-Aug-05	C	453	1438	609	8.6	8.2		58	3.3						453				
Influent	9-Nov-05	C	331	853	297		3.5		42	3						331				
Influent	23-Feb-06	C	224	413	385		5.3		35	5.3						224				
Influent	14-Apr-06	C	321	519	306	2	3.2		45	1.9						321				
Influent	19-Jul-06	C	356	642	500	6.3			63	1.8						356				
Influent	26-Sep-06	C	293	509	196		4.3		42	2						293				
Influent	19-Oct-06	C	326	776	380	5.8										326				
Influent	16-Jan-07	C	392	619	305	2			24							392				
Influent	25-Apr-07	C	418	916	298	3.91			42							418				
Influent	31-May-07	C	269	510	390	5.9			5.9							269				
Influent	11-Aug-07	C	215	516	166	12.74			29.22	0.15						215				
Influent	26-Oct-07	C	650	2750	1451				68.84	0.18						650				
Influent	26/02/2008	C	290	778	285	2.16		0.22	56.63							290				
Influent	18/05/2008	C	298	678	213	4.16		0.32	36.10							298				
Influent	19/09/2008	C	330	884	527	0.07		0.42	49.10							330				
Influent	12/11/2008	C	200	770	646	3.90		0.03												
Influent	02/10/2009	C	400	1074	582.00	7.61	6.8	52.81	36.05	0.09	0.256	0.17	52.64	903			7.1	<.1	74.97	7
Influent	25/02/2009	C	400	687	263	7.355	5.45	26.53	23.39	0.111		0.21	26.32	1487	55.1		7.9	<.1	215.58	8.1

For inspection purposes only
Consent of copyright holder required for any other use.

Table D.1 (iv) Influent Monitoring Data

Attachment D.2

For inspection purposes only.
Consent of copyright owner required for any other use.

PT_CD	PT_TYPE	LA_NAME	RWB_TYPE	RWB_NAME	DESIGNATION	EASTING	NORTHING	VERIFIED
SW1(P)	Primary	Monaghan County Council	River	Mountain Water	Not Designated	267964	343554	N

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Attachment E.1

*For inspection purposes only.
Consent of copyright owner required for any other use.*

TABLE E.1(i): WASTE WATER FREQUENCY AND QUANTITY OF DISCHARGE – Primary and Secondary Discharge Points

Identification Code for Discharge point	Frequency of discharge (days/annum)	Quantity of Waste Water Discharged (m ³ /annum)
SW-1	365	67160

For inspection purposes only.
Consent of copyright owner required for any other use.

Attachment E.2

For inspection purposes only.
Consent of copyright owner required for any other use.

ACCREDITATION CERTIFICATE

Euro Environmental Services

Unit 35, Boyne Business Park, Drogheda, Co Louth

Testing Laboratory

Registration Number

119T

is accredited by the Irish National Accreditation Board (INAB) to undertake testing as detailed in the Schedule bearing the Registration Number detailed above, in compliance with the International Standard

ISO/IEC 17025:2005 2nd Edition

“General Requirements for the Competence of Testing and Calibration Laboratories”

(This Certificate must only be read in conjunction with the Annexed Schedule of Accreditation)

Date of award of Accreditation: 16:08:2002

Date of last renewal of Accreditation: 14:09:2007

Expiry Date of this certificate of Accreditation: 14:09:2012

This Accreditation shall remain in force until further notice subject to continuing compliance with INAB accreditation criteria, ISO/IEC 17025 and any further requirements specified by the Irish National Accreditation Board.

Manager: Tom Dempsey
Mr Tom Dempsey

Chairperson: Maire Walsh
Dr Máire Walsh

Issued on 14 September 2007

Organisations are subject to annual surveillance and are re-assessed every five years. The renewal date on this Certificate confirms the latest date of renewal of accreditation. To confirm the validity of this Certificate please contact the Irish National Accreditation Board.

The INAB is a signatory of the European co-operation for Accreditation (EA) Testing Multilateral Agreement (MLA) and the International Laboratory Accreditation Cooperation (ILAC) Mutual Recognition Arrangement.

Wilton Park House
Wilton Place
Dublin 2

Tel: 353-1-607 3003
Fax: 353-1-607 3109
Email: inab@inab.ie
<http://www.inab.ie>



Permanent Laboratory:
Category A

Schedule of Accreditation

EURO environmental services

Chemical Testing Laboratory

Initial Accreditation Date: 09-10-2000

Postal Address: Unit 35
Boyne Business Park
Drogheda
Co Louth

Telephone: + 353 41 984 5440

Fax: + 353 41 984 6171

Email: info@euroenv.ie

Web: www.euroenv.ie

Contact: Natalie O'Brien

Facilities: Public Testing Facility

Wilton Park House
Wilton Place
Dublin 2

Tel: 353-1-607 3003
Fax: 353-1-607 3109
Email: inab@inab.ie
<http://www.inab.ie>



Permanent Laboratory:
Category A

THE IRISH NATIONAL ACCREDITATION BOARD (INAB) is the Irish organisation for the accreditation of organisations including laboratories.

Laboratory accreditation is available to testing and calibration facilities operated by manufacturing organisations, government departments, educational institutions and commercial testing/calibration services. Indeed, any organisation undertaking testing, measurement or calibration in any area of technology can seek accreditation for the work it is undertaking.

Each accredited laboratory has been assessed by skilled specialist assessors and found to meet criteria which are in compliance with ISO/IEC 17025 or ISO/IEC 15189 (medical laboratories). Frequent audits, together with periodic inter-laboratory test programmes, ensure that these standards of operation are maintained.

GLOSSARY OF TERMS

Facilities:

Public calibration/testing service: Commercial operations which actively seek work from others.

Conditionally available for public calibration/testing: Established for another primary purpose but, more commonly than not, is available for outside work.

Normally not available for public calibration/testing: Unavailable for public calibration/testing more often than not.

Testing and Calibration Categories:

Category A: Permanent laboratory calibration and testing where the laboratory is erected on a fixed location for a period expected to be greater than three years.

Category B: Site calibration and testing that is performed by staff sent out on site by a permanent laboratory that is accredited by the Irish National Accreditation Board.

Category C: Site calibration and testing that is performed in a site/mobile laboratory or by staff sent out by such a laboratory, the operation of which is the responsibility of a permanent laboratory accredited by the Irish National Accreditation Board.

Category D: Site calibration and testing that is performed on site by individuals and organisations that do not have a permanent calibration/testing laboratory. Testing may be performed using

- portable test equipment
- a site laboratory
- a mobile laboratory or
- equipment from a mobile or site laboratory

Standard Specification or Test Procedure Used:

The standard specification or test procedure that is accredited is the issue that is current on the date of the most recent visit, unless otherwise stated.

Laboratory users wishing to obtain assurance that calibration or test results are reliable and carried out to the Irish National Accreditation Board criteria should insist on receiving an accredited calibration certificate or test report. Users should contact the laboratory directly to ensure that this scope of accreditation is current. INAB will on request verify the status and scope.

EURO environmental services

Chemical Testing Laboratory



Permanent Laboratory:
Category A

SCOPE OF ACCREDITATION

INAB Classification number Materials/products tested	Type of test/properties measured Range of measurement	Standard specifications Equipment/techniques used
<p>766 Waters</p> <p>.01 Waters for potable and domestic purposes</p> <p>05 Trade Wastes <i>Industrial Waters</i></p> <p>766 Waters</p> <p>.01 Waters for potable and domestic purposes</p> <p>.04 Sewage</p> <p>.05 Trade Wastes <i>Industrial Waters</i></p> <p>.99 Other Waters <i>Surface Waters</i> <i>Groundwaters</i></p>	<p>PH(4-13) pH units</p> <p>Conductivity (5μs – 100,000 μscm⁻¹)</p> <p>BOD (2-6mg/L)</p> <p>COD (5-60,000 mg/L)</p> <p>Chloride (20 –10,000mg/L)</p> <p>Ammonia (0.2 – 1000 mg/L as N)</p> <p>Total Oxidised Nitrogen (TON) (1 – 8 mg/L as N)</p>	<p>Documented in-house methods based on</p> <p>Standard Methods for the examination of Water and Wastewater, 20th Edition Method 4500-H⁺B – SOP 110</p> <p>Standard Methods for the examination of Water and wastewater, 20th Edition Method 2510B – SOP 112</p> <p>Standard Methods for the examination of Water and wastewater, 20th Edition Method 5210B – SOP 113</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition Method 5220D – SOP 107</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition Method 4500 – C-E – SOP 100</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition Method 4500 NH₃F – SOP 114</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition Method 4500 NO₃H – SOP 151</p>

For inspection purposes only.
Consent of copyright owner required for any other use.

EURO environmental services

Chemical Testing Laboratory



Permanent Laboratory:
Category A

SCOPE OF ACCREDITATION

INAB Classification number Materials/products tested	Type of test/properties measured Range of measurement	Standard specifications Equipment/techniques used
<p>766 Waters</p> <p>.01 Waters for potable and domestic purposes</p> <p>.04 Sewage</p> <p>.05 Trade Wastes <i>Industrial Waters</i></p> <p>.99 Other Waters <i>Surface Waters</i> <i>Groundwaters</i></p>	<p>Orthophosphate (0.1 – 1000 mg/L as P)</p> <p>Sulphate (10 – 30 mg/L as SO₄)</p> <p>Total Phosphate (0.1 – 0.5 mg/L as P) (0.5 – 4 mg/L as P)</p> <p>Na, Ca, K and Mg ICP-MS run (0.5 – 100 ppm)</p> <p>BTEX (Benzene, Toluene, Ethylbenzene and Xylenes): Benzene (5 – 100µg/L) Ethylbenzene (5 – 100µg/L) Toluene (5 – 100µg/L) o-xylene (5 – 100µg/L) m,p-xylene (10 – 200µg/L)</p> <p>THMs (Trihalomethanes): Chloroform Bromochloromethane Dibromochloromethane Bromoform (5 - 200µg/L)</p>	<p>Documented in-house methods based on</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition. Method 4500 – P E – SOP 117</p> <p>Standard Methods for the examination of water and wastewater, 20th Edition. Method 4500-S O₄²⁻E– SOP 119</p> <p>Standard methods for the examination of water and wastewater, 20th Edition. Method 4500-P B – SOP 166</p> <p>Standard methods for the examination of water and wastewater, 20th Edition. Method 3120 B – SOP 184</p> <p>Based on USEPA methods, 524.2 SOP 179</p> <p>Based on USEPA methods, 524.2 SOP 186</p>

EURO environmental services

Chemical Testing Laboratory



Permanent Laboratory:
Category A

SCOPE OF ACCREDITATION

INAB Classification number	Type of test/properties measured	Standard specifications
Materials/products tested	Range of measurement	Equipment/techniques used
766 Waters .01 Waters for potable and domestic purposes .05 Trade Wastes <i>Industrial Waters</i> .99 Other Waters <i>Surface Waters</i> <i>Groundwaters</i>	Hardness (Total) (100 – 400 mg/L CaCO ₃)	Standard Methods for the Examination of Water and Wastewater, 20 th Edition Method 2340 C SOP 111
	Alkalinity (Total) (50 – 10,000 mg/L CaCO ₃)	Standard Methods for the Examination of Water and Wastewater, 20 th Edition Method 2320 B SOP 102
.04 Sewage .05 Trade Wastes <i>Industrial Waters</i> .99 Other Waters <i>Surface Waters</i> <i>Groundwaters</i>	Colour (Apparent) (10 – 500ptCo Units)	Standard Methods for the Examination Of Water and Wastewater, 20 th Edition Method 2120 B SOP 108
	Turbidity (0.01 – 1100 NTU)	Standard Methods for the Examination Of Water and Wastewater, 20 th Edition Method 2130 A SOP 109

Consent of copying for inspection purposes only. No other use permitted without prior written consent required for any other use.

Attachment E.3

For inspection purposes only.
Consent of copyright owner required for any other use.

PT_CD	PT_TYPE	MON_TYPE	EASTING	NORTHING	VERIFIED
SW1(P)s	Primary	S	267968 E	343563 N	N
aSW1(P)u	Primary	M	267744 E	343773 N	N
aSW1(P)d	Primary	M	268460 E	343137 N	N

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Attachment E.4

*For inspection purposes only.
Consent of copyright owner required for any other use.*

TABLE 1- ATTACHMENT E4

Emyvale Effluent

Effluent	Date of Sampling	Sample Type (C or G)	BOD mg/l	COD mg/l	TSS mg/l	Total P mg/l P	Ortho P mg/l P	Total N mg/l N	NH3-N mg/l N	Nitrate NO3	Nitrite NO2	TON mg/l N	TKN mg/l N	Conductivity uscm	DO %	DO mg/l	pH	Phenols Total	Sulphate	Temp
Effluent	11/02/2004	C	45	110	45	5.5	5.4		7.6	16										
Effluent	04/03/2004	C	37	116	38		3.1	8	14	12										
Effluent	07/04/2004	C	14	51	28	3.3	3		4.8	23										
Effluent	21/04/2004	C	25	75	23	4.2	4		8.1	11.1										
Effluent	12/05/2004	C	55	151	25	8	8	26	32.8	31										
Effluent	16/06/2004	C	54	162	38		3.5		36	8.1										
Effluent	21/07/2004	C	46	49	28		3.2		38											
Effluent	24/08/2004	C	22	65	16	3.3	3		6.5	15										
Effluent	15/09/2004	C	22	65	16	3.3	3		6.5	15										
Effluent	02/11/2004	C	30	100	27	0.8		15	23	36										
Effluent	17/02/2005	C	7.7	85	16	4	4.1		24	4										
Effluent	19/04/2005	C	11	59	11		3.7		18	6.8						7.7				
Effluent	17/08/2005	C	36	97	28	5.1	5.1		38	4						11				
Effluent	09/11/2005	C	33	67	27		3		10	41						36				
Effluent	23/02/2006	C	14	57	5		4		2.7	40						33				
Effluent	14/04/2006	C	17	76	32	2.4	2.1		14	14						14				
Effluent	19/07/2006	C	11	132	29	1.8			8.7	6.4						17				
Effluent	26/09/2006	C	16	64	14		2.1		6.3	10.2						16				
Effluent	19/10/2006	C	32.6	46	20	3.32										32.6				
Effluent	10/02/2009	C	7	41	7.00	4.01	3.581	24.99	0.96	23.74	0.125	23.87	1.12	850		7.5	<0.10	56.81	5.3	
Effluent	25/02/2009	C	6	69	11.00	6.70	6.639	35.25	1.29	31.2	0.139	31.33	3.92	964	61.4	7.28	7.5	<0.10	83.58	9.3

For information purposes only. Consent of copyright owner required for any other use.

TABLE 2 - ATTACHMENT E4

aSW1(P)u Upstream Monitoring Point

U.S.W	Date of Sampling	Sample Type (C or G)	BOD mg/l	COD mg/l	TSS mg/l	Total P mg/l P	Ortho P mg/l P	Total N mg/l N	NH3-N mg/l N	Nitrate NO3	Nitrite NO2	TON mg/l N	TKN mg/l N	Conductivity uscm	DO %	DO mg/l	pH	Phenols Total	Sulphate	Temp
U.S.W	11/02/2004	G	1.2	14	16	0.12	0.1		0.21	4.2										
U.S.W	07/04/2004	G	3.4	34	6	0.11	0.1		0.41	2.9						10.6				
U.S.W	21/04/2004	G	2	24	7	0.2	0.2		0.36	1.8										
U.S.W	12/05/2004	G	3.1	19	11		0.08		0.2	2.5						10.1				
U.S.W	16/06/2004	G	2.7	25	8	0.12	0.11	2.2	0.08	3.1										
U.S.W	21/07/2004	G		25	6		0.13		0.28	2.2										
U.S.W	15/09/2004	G	1.7	60	10	0.11	0.1		0.31	1.1										
U.S.W	02/11/2004	G	3	39	6	0.11		0.81	0.31	2										
U.S.W	17/02/2005	G	0.24	23	13	0.11	0.09		0.21	1.6						0.24				
U.S.W	19/04/2005	G	2.1	32	11		0.12		0.28	2.1						2.1				
U.S.W	17/08/2005	G	3	26	7	0.11	0.07		0.09	1.8						3				
U.S.W	09/11/2005	G	1.2	42	2		0.17		0.34	2.2						1.2				
U.S.W	23/02/2006	G	2.1	31	12		0.19		0.39	3.1						2.1				
U.S.W	14/04/2006	G	2.6	28	13	0.3	0.22		0.13	1.9						2.6				
U.S.W	19/07/2006	G	2.7	21	6	0.2			0.1	2.8						2.7				
U.S.W	19/10/2006	G	2.7		12	0.13										2.7				
U.S.W	25/04/2007	G	1.8	35	10	0.04			0.12							1.8				
U.S.W	31/05/2007	G	4	28	3	0.09			0.09							4				
U.S.W	11/08/2007	G	<2	30	11	0.33			0.25	2.58						<2				
U.S.W	26/10/2007	G	<2	23	4	0.116			0.09	0.92						<2				
U.S.W	26/02/2008	G	<2	33	<3	0.15		0.74	0.09							<2				
U.S.W	18/05/2008	G	<2	20	3	0.06		0.71	0.13							<2				
U.S.W	19/09/2008	G	<2	36	3	0.95		0.58	0.06							<2				
U.S.W	12/11/2008	G	<2	16	<3	0.07		0.39								<2				
U.S.W	02/10/2009	G	<2	22		0.04	0.03	1.29	<0.06	0.73	<0.003	0.73	<1.00	381			7.8	<.10	17.56	3
U.S.W	25/02/2009	G	<2	20	5	0.039	0.011	1.44	<0.06	0.85	0.005	0.85	<1.00	487	80.6	9.79	8	<.10	33.17	8.1

For Information Purposes Only
 Consent of Copyright Owner Required for any other use.

TABLE 3- ATTACHMENT E4

aSW1(P)d Downstream Monitoring Point

D.S.	Date of Sampling	Sample Type (C or G)	BOD mg/l	COD mg/l	TSS mg/l	Total P mg/l P	Ortho P mg/l P	Total N mg/l N	NH3-N mg/l N	Nitrate NO3	Nitrite NO2	TON mg/l N	TKN mg/l N	Conductivity uscm	DO %	DO mg/l	pH	Phenols Total	Sulphate	Temp
D.S.	11/02/2004	G	1.3	16	14	0.12	0.09		0.23	4.6										
D.S.	07/04/2004	G	3.6	39	6	0.1	0.09		0.46	3.2						10.4				
D.S.	21/04/2004	G	1.8	25	14	0.2	0.18		0.039	1.6										
D.S.	12/05/2004	G	5.1	26	12		0.17		0.28	3.2						10				
D.S.	16/06/2004	G	2.8	31	6	0.13	0.13	2.6	0.1	3.1										
D.S.	21/07/2004	G		29	5		0.18		0.41	2.5										
D.S.	15/09/2004	G	4	57	7	0.12	0.1		0.36	1										
D.S.	02/11/2004	G	2.8	41	5	0.11		0.86	0.34	2.1										
D.S.	17/02/2005	G	0.28	29	11	0.11	0.08		0.23	1.8						0.28				
D.S.	19/04/2005	G	2.2	32	10		0.12		0.26	2.6						2.2				
D.S.	17/08/2005	G	3.3	20	6	0.13	0.09		0.11	1.8						3.3				
D.S.	09/11/2005	G	1.3	39	6		0.2		0.41	2.8						1.3				
D.S.	23/02/2006	G	3.1	36	11		0.13		0.43	3.9						3.1				
D.S.	14/04/2006	G	3.1	36	14	0.35	0.23		0.19	2.4						3.1				
D.S.	19/07/2006	G	2.6	30	8	0.25			0.32	2.7						2.6				
D.S.	19/10/2006	G	2.5		13	0.1										2.5				
D.S.	25/04/2007	G	1.8	38	12	0.05			0.16							1.8				
D.S.	31/05/2007	G	3	26	4	0.11			0.11							3				
D.S.	11/08/2007	G	<2	26	9	0.266			0.15	0.09						<2				
D.S.	26/10/2007	G	3	21	4	0.175			<0.09	1.69						3				
D.S.	26/02/2008	G	<2	30	3	0.18		0.69	0.11							<2				
D.S.	18/05/2008	G	<2	21	3	0.13		1.16	0.26							<2				
D.S.	19/09/2008	G	<2	33	3	0.19		0.75	<0.06							<2				
D.S.	12/11/2008	G	<2	14	3	0.08		0.53								<2				
D.S.	10/02/2009	G	<2	17	4.00	0.15	0.086	1.73	<0.06	1.17	0.004	1.17	<1	374		7.9	<0.1	18.09	3	
D.S.	25/02/2009	G	<2	24	3	0.596	0.547	4.68	0.11	3.53	0.028	3.56	1.12	532	66.6	8.62	8	<0.1	40.24	8.10

For inspection purposes only. Consent of copyright owner required for any other use.

Attachment F.1

*For inspection purposes only.
Consent of copyright owner required for any other use.*

TABLE F.1(i)(a): SURFACE/GROUND WATER MONITORING

Primary Discharge Point

Discharge Point Code:	SW-1
MONITORING POINT CODE:	aSW-1d
Grid Ref (12 digits, 6E, 6N)	268460 / 343137

Parameter	Results (mg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	10/02/08	26/02/08	18/05/08	19/06/08			
pH					Grab	0.01	Method 4500-H+/Electrometry
Temperature					Grab	0	0
Electrical Conductivity (@ 25°C)	= 374				Grab	0.5	Method 2510 B/Electrometry
Suspended Solids		= 3	= 3		Grab	3	Method 2540 D/Filtration/Dry in 104C
Ammonia (as N)		= 0.11	= 0.26		Grab	0.06	Method 4500NH3F/Colorimetry
Biochemical Oxygen Demand		< 2			Grab	2	Method 5210 B/Electrometry
Chemical Oxygen Demand		= 30			Grab	5	Method 5220 D/Spectrophotometry
Dissolved Oxygen		< 2	< 2		Grab	0	DO Meter
Hardness (as CaCO ₃)					Grab	0	0
Total Nitrogen (as N)		= 0.69	= 0.16		Grab	1	Calculation
Nitrite (as N)					Grab	0.003	Method 4500-NO ₂ -B/Colorimetry
Nitrate (as N)					Grab	0.09	Method 4500-NO ₃ -H/Colorimetry
Total Phosphorous (as P)		= 0.18	= 0.13	= 0.19	Grab	0.042	Method 4500-P E/Colorimetry
OrthoPhosphate (as P)					Grab	0.004	Method 4500-P E/Colorimetry
Sulphate (SO ₄)					Grab	1.39	Method 4500-SO ₄ ²⁻ E/Colorimetry
Phenols (Sum)					Grab	0.1	EPA Method 525 GCMS

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Additional Comments:	No Hardness Data Available
----------------------	----------------------------

WWD Licence Application Annex I

Parameter	Results (mg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	19/09/08	12/11/08	10/02/09	25/02/09			
pH			= 7.9	= 8	Grab	0.01	Method 4500-H+/Electrometry
Temperature			= 3	= 8.1	Grab	0	0
Electrical Conductivity (@ 25°C)				= 532	Grab	0.5	Method 2510 B/Electrometry
Suspended Solids	= 3	= 3	= 4	= 3	Grab	3	Method 2540 D/Filtration/Dry in 104C
Ammonia (as N)	< 0.06		< 0.06	= 0.11	Grab	0.06	Method 4500NH3F/Colorimetry
Biochemical Oxygen Demand	< 2	< 2	< 2	< 2	Grab	2	Method 5210 B/Electrometry
Chemical Oxygen Demand	= 33	= 14	= 17	= 24	Grab	5	Method 5220 D/Spectrophotometry
Dissolved Oxygen	< 2	< 2		= 8.62	Grab	0	DO Meter
Hardness (as CaCO ₃)				= 0	Grab	0	0
Total Nitrogen (as N)	= 0.75	= 0.53	= 1.73	= 4.68	Grab	1	Calculation
Nitrite (as N)			= 0.004	= 0.028	Grab	0.003	Method 4500-NO ₂ -B/Colorimetry
Nitrate (as N)			= 1.17	= 3.53	Grab	0.09	Method 4500-NO ₃ -H/Colorimetry
Total Phosphorous (as P)		= 0.08	= 0.15	= 0.596	Grab	0.042	Method 4500-P E/Colorimetry
OrthoPhosphate (as P)			= 0.086	= 0.547	Grab	0.004	Method 4500-P E/Colorimetry
Sulphate (SO ₄)			= 18.09	= 40.24	Grab	1.39	Method 4500-SO ₄ -E/Colorimetry
Phenols (Sum)			< 0.1	< 0.1	Grab	0.1	EPA Method 525 GCMS

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Additional Comments:	No Hardness Data Available
----------------------	----------------------------

WWD Licence Application Annex I

Parameter	Results (mg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	18/05/09						
pH					Grab	0.01	Method 4500-H+/Electrometry
Temperature					Grab	0	0
Electrical Conductivity (@ 25°C)					Grab	0.5	Method 2510 B/Electrometry
Suspended Solids					Grab	3	Method 2540 D/Filtration/Dry in 104C
Ammonia (as N)					Grab	0.06	Method 4500NH3F/Colorimetry
Biochemical Oxygen Demand	< 2				Grab	2	Method 5210 B/Electrometry
Chemical Oxygen Demand	= 21				Grab	5	Method 5220 D/Spectrophotometry
Dissolved Oxygen					Grab	0	DO Meter
Hardness (as CaCO ₃)					Grab	0	0
Total Nitrogen (as N)					Grab	1	Calculation
Nitrite (as N)					Grab	0.003	Method 4500-NO ₂ -B/Colorimetry
Nitrate (as N)					Grab	0.09	Method 4500-NO ₃ -H/Colorimetry
Total Phosphorous (as P)					Grab	0.042	Method 4500-P E/Colorimetry
OrthoPhosphate (as P)					Grab	0.004	Method 4500-P E/Colorimetry
Sulphate (SO ₄)					Grab	1.39	Method 4500-SO ₄ 2-E/Colorimetry
Phenols (Sum)					Grab	0.1	EPA Method 525 GCMS

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Additional Comments:	No Hardness Data Available
----------------------	----------------------------

TABLE F.1(i)(b): SURFACE/GROUND WATER MONITORING (Dangerous Substances)

Primary Discharge Point

Discharge Point Code:	SW-1
MONITORING POINT CODE:	aSW-1d
Grid Ref (12 digits, 6E, 6N)	268460 / 343137

Parameter	Results (µg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	10/02/09						
Atrazine	< 0.01				Grab	0.01	USEPA Method 610 HPLC
Dichloromethane	< 1				Grab	1	USEPA Method 524 GCMS
Simazine	< 0.01				Grab	0.01	USEPA Method 610 HPLC
Toluene	< 1				Grab	1	USEPA Method 524.2 GCMS
Tributyltin	< 0.02				Grab	0.02	Subcontracted Test GCMS
Xylenes	< 1				Grab	1	USEPA Method 524.2 GCMS
Arsenic	< 0.96				Grab	0.96	USEPA Method 3125B ICPMS
Chromium	< 0.93				Grab	0.93	USEPA Method 3125B ICPMS
Copper	= 4.2				Grab	0.2	USEPA Method 3125B ICPMS
Cyanide	< 5				Grab	5	Hach Water Analysis Handbook 2nd Edition
Flouride	= 0.2				Grab	0.03	Method 4500 F - E Colorimetry
Lead	= 0.6				Grab	0.38	USEPA Method 3125B ICPMS
Nickel	< 0.47				Grab	0.47	USEPA Method 3125B ICPMS
Zinc	< 4.6				Grab	4.6	USEPA Method 3125B ICPMS
Boron	< 4.2				Grab	4.2	USEPA Method 3125B ICPMS
Cadmium	< 0.09				Grab	0.09	USEPA Method 3125B ICPMS
Mercury	< 0.2				Grab	0.2	USEPA Method 3125B ICPMS
Selenium	< 0.74				Grab	0.74	USEPA Method 3125B ICPMS

For inspection purposes only. Consent of copyright owner required for any other use.

WWD Licence Application Annex I

Barium	= 63.5				Grab	0.74	USEPA Method 3125B ICPMS
--------	--------	--	--	--	------	------	--------------------------------

Additional Comments:	
----------------------	--

For inspection purposes only.
Consent of copyright owner required for any other use.

TABLE F.1(i)(a): SURFACE/GROUND WATER MONITORING

Primary Discharge Point

Discharge Point Code:	SW-1
MONITORING POINT CODE:	aSW-1u
Grid Ref (12 digits, 6E, 6N)	267744 / 343773

Parameter	Results (mg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	26/02/08	18/05/08	19/09/08	12/11/08			
pH					Grab	0.01	Method 4500-H+/Electrometry
Temperature					Grab	0	0
Electrical Conductivity (@ 25°C)					Grab	0.5	Method 2510 B/Electrometry
Suspended Solids	< 3	= 3	= 3	< 3	Grab	3	Method 2540 D/Filtration/Dry in 104C
Ammonia (as N)	= 0.09	= 0.13	< 0.06		Grab	0.06	Method 4500NH3F/Colorimetry
Biochemical Oxygen Demand	< 2	< 2	< 2	< 2	Grab	2	Method 5210 B/Electrometry
Chemical Oxygen Demand	= 33	= 20	= 36	= 16	Grab	5	Method 5220 D/Spectrophotometry
Dissolved Oxygen					Grab	0	DO Meter
Hardness (as CaCO ₃)					Grab	0	0
Total Nitrogen (as N)	= 0.74	= 0.71	= 0.58	= 0.39	Grab	1	Calculation
Nitrite (as N)					Grab	0.003	Method 4500-NO ₂ -B/Colorimetry
Nitrate (as N)					Grab	0.09	Method 4500-NO ₃ -H/Colorimetry
Total Phosphorous (as P)	= 0.15	= 0.06	= 0.95	= 0.07	Grab	0.042	Method 4500-P E/Colorimetry
OrthoPhosphate (as P)					Grab	0.004	Method 4500-P E/Colorimetry
Sulphate (SO ₄)					Grab	1.39	Method 4500-SO ₄ -E/Colorimetry
Phenols (Sum)					Grab	0.1	EPA Method 525 GCMS

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Additional Comments:	No Hardness Data Available No hardness data available
----------------------	--

WWD Licence Application Annex I

Parameter	Results (mg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	10/02/09	25/02/09					
pH	= 7.8	= 8			Grab	0.01	Method 4500-H+/Electrometry
Temperature	= 3	= 8.1			Grab	0	0
Electrical Conductivity (@ 25°C)	= 381	= 487			Grab	0.5	Method 2510 B/Electrometry
Suspended Solids		= 5			Grab	3	Method 2540 D/Filtration/Dry in 104C
Ammonia (as N)	< 0.06	< 0.06			Grab	0.06	Method 4500NH3F/Colorimetry
Biochemical Oxygen Demand	< 2	< 2			Grab	2	Method 5210 B/Electrometry
Chemical Oxygen Demand	= 22	= 20			Grab	5	Method 5220 D/Spectrophotometry
Dissolved Oxygen		= 9.79			Grab	0	DO Meter
Hardness (as CaCO ₃)		= 0			Grab	0	0
Total Nitrogen (as N)	= 1.29	= 1.41			Grab	1	Calculation
Nitrite (as N)	< 0.003	= 0.005			Grab	0.003	Method 4500-NO ₂ -B/Colorimetry
Nitrate (as N)	= 0.73	= 0.85			Grab	0.09	Method 4500-NO ₃ -H/Colorimetry
Total Phosphorous (as P)	= 0.04	= 0.039			Grab	0.042	Method 4500-P E/Colorimetry
OrthoPhosphate (as P)	= 0.03	= 0.011			Grab	0.004	Method 4500-P E/Colorimetry
Sulphate (SO ₄)	= 17.56	= 33.17			Grab	1.39	Method 4500-SO ₄ 2-E/Colorimetry
Phenols (Sum)	< 0.1	< 0.1			Grab	0.1	EPA Method 525 GCMS

For Orthophosphate: this monitoring should be undertaken on a sample filtered on 0.45µm filter paper

For Phenols: USEPA Method 604, AWWA Standard Method 6240, or equivalent.

Additional Comments:	No Hardness Data Available No hardness data available
----------------------	--

TABLE F.1(i)(b): SURFACE/GROUND WATER MONITORING (Dangerous Substances)

Primary Discharge Point

Discharge Point Code:	SW-1
MONITORING POINT CODE:	aSW-1u
Grid Ref (12 digits, 6E, 6N)	267744 / 343773

Parameter	Results (µg/l)				Sampling method	Limit of Quantitation	Analysis method / technique
	10/02/09						
Atrazine	< 0.01				Grab	0.01	USEPA Method 610 HPLC
Dichloromethane	< 1				Grab	1	USEPA Method 524 GCMS
Simazine	< 0.01				Grab	0.01	USEPA Method 610 HPLC
Toluene	< 1				Grab	1	USEPA Method 524.2 GCMS
Tributyltin	< 0.02				Grab	0.02	Subcontracted Test GCMS
Xylenes	< 1				Grab	1	USEPA Method 524.2 GCMS
Arsenic	< 0.96				Grab	0.96	USEPA Method 3125B ICPMS
Chromium	< 0.93				Grab	0.93	USEPA Method 3125B ICPMS
Copper	= 3.2				Grab	0.2	USEPA Method 3125B ICPMS
Cyanide	< 5				Grab	5	Hach Water Analysis Handbook 2nd Edition
Flouride	= 0.17				Grab	0.03	Method 4500 F - E Colorimetry
Lead	< 0.38				Grab	0.38	USEPA Method 3125B ICPMS
Nickel	< 0.47				Grab	0.47	USEPA Method 3125B ICPMS
Zinc	< 4.6				Grab	4.6	USEPA Method 3125B ICPMS
Boron	< 4.2				Grab	4.2	USEPA Method 3125B ICPMS
Cadmium	< 0.09				Grab	0.09	USEPA Method 3125B ICPMS
Mercury	< 0.2				Grab	0.2	USEPA Method 3125B ICPMS
Selenium	< 0.74				Grab	0.74	USEPA Method 3125B ICPMS

WWD Licence Application Annex I


Barium	= 58.8				Grab	0.74	USEPA Method 3125B ICPMS
--------	--------	--	--	--	------	------	--------------------------------

Additional Comments:	
----------------------	--

For inspection purposes only.
Consent of copyright owner required for any other use.

Attachment F.2

*For inspection purposes only.
Consent of copyright owner required for any other use.*



LEGEND:
 LICENCE APPLICATION AREA

REV	DESCRIPTION	BY	CHK	APP	DATE

Monaghan County Council
 Comhairle Contae Mhúineacháin



PH MCGARTHY HOUSE
 NUTSGROVE OFFICE PARK
 NUTSGROVE AVENUE
 RATHERKINMAN, DUBLIN 14



Project:
EMYVALE DISCHARGE LICENCE APPLICATION

Drawing Title:
WASTE WATER TREATMENT WORKS & WATER ABSTRACTION POINT LOCATIONS

Scale @	Drawn	Date	Checked	Date	Approved	Date
1:10,000	HS	20/03/09	CS	20/03/09	SD	20/03/09
Project No.	Office	Type	Drawing No.	Revision		
C007400			DRAWING 9			

Attachment G.2

*For inspection purposes only.
Consent of copyright owner required for any other use.*

water matters

"Help us plan!"



Draft River Basin Management Plan for the Neagh Bann International River Basin District

December 2008




The Draft River Basin District Management Plan

The European Union Water Framework Directive was adopted in 2000. It requires governments to manage all of their waters: rivers, canals, lakes, reservoirs, groundwaters, wetlands, estuaries and coastal waters. Member States must ensure that their waters achieve at least good status by 2015 and that their status doesn't deteriorate.

The Directive requires the preparation of a management plan for all of the waters in an area called a River Basin District. Some 400 river basins on the island of Ireland have been grouped and assigned to a total of eight River Basin Districts; one of these lies wholly in Northern Ireland, four lie wholly in Ireland and three are International River Basin Districts, one of which is the Neagh Bann District.

Since 2000, the local authorities and the Northern Ireland Environment Agency have been working on the implementation of the Water Framework Directive. We have met all of the deadlines and our performance has been amongst the best in the European Union.



We have actively sought people's views at every stage of the implementation process. Management plans are considered by the District's Advisory Council (Ireland) and by the Catchment and National Stakeholder Groups (Northern Ireland). We produced a series of consultation documents and we discussed significant water management issues with interest groups, public authorities and local authorities at a series of public consultation events in 2007 and 2008.

The next stage is the production of a River Basin District Management Plan. It will cover the six-year period from 2009 until 2015; any remaining issues or new problems will be tackled in two further six-year plans, 2015–2021 and 2021–2027.

We have produced a draft of the plan and we are beginning a process of consultation to elicit views on the draft. In Ireland the final version of this plan must be adopted by all local authorities in the district, whilst in Northern Ireland the plan must be approved by the Environment Minister. The plan will come into effect at the end of 2009.



How the plan was developed

We followed a nine-step process in developing the plan. Our approach was structured: find out the issues, decide what action to take and make a plan.

What are our key water issues?	We investigated which water issues are causing problems, what actions we could take to solve them and where we should focus these actions.
What is the status of our waters?	Comprehensive monitoring established the condition of our waters; identifying where they are satisfactory and where they must be improved.
What do we plan to achieve?	We identified sustainable objectives for our waters.
What measures must we take?	The Water Framework Directive stipulates mandatory measures. We identified actions under these measures, setting out existing and new plans and programmes to ensure full and effective implementation.
What will these mandatory measures achieve?	We assessed how effective these mandatory measures will be in meeting our objectives and have identified cases where extra effort may be needed to improve our waters.
What further measures can we take?	We identified supplementary measures for the cases where the mandatory measures alone would not be sufficient to achieve our objectives.
What will supplementary measures achieve?	We assessed whether the combination of measures would achieve our objectives and how long it would take.
What are our objectives in the Neagh Bann District?	We outline the objectives we plan to achieve and specify where extended timescales or lower objectives are necessary.
What is our action plan for the Neagh Bann District?	The outcome of this planning process is a tailored action plan for the Neagh Bann District. We have proposed a detailed suite of measures setting out what, where and when actions are needed and who will do them.

Neagh Bann District: current status

The status of our surface waters and groundwaters is summarised in these two tables. These tables include the whole international district's waters: those in Northern Ireland, those in Ireland and the shared waters (those water bodies which lie along the border).

Surface water status in the Neagh Bann District

Surface Water Category	High	Good	Moderate	Poor	Bad	Yet to be Determined
Rivers and canals (number) % of total	(0) 0	(76) 23.1	(149) 45.3	(71) 21.6	(15) 4.6	(18) 5.5
Lakes and reservoirs (km ²) % of total	(0) 0	(0.17) 0.04	(3.48) 0.87	(6.63) 1.66	(388.7) 97.42	(0) 0
Estuaries (km ²) % of total	(0) 0	(0) 0		(41.72) 100		(0) 0
Coastal (km ²) % of total	(0) 0	(184.56) 55.7		(108.39) 32.7		(38.45) 11.6

Groundwater status in the Neagh Bann District

Groundwater	Good	Poor
Chemical Status (km ²) % of total	(6,683) 88.8	(843) 11.2
Quantitative Status (km ²) % of total	(6,759) 89.8	(767) 10.2
Combined Status (km ²) % of total	(6,683) 88.8	(843) 11.2



Protected Areas

Protected areas must achieve good or high status to support their designations, with specific targets for protection of priority species or habitats. There are 94 protected areas amongst the shared waters of the Neagh Bann International River Basin District. In the whole District there are 650 protected areas. These include drinking water sources such as Monalty Lough and Spelga Dam; the shellfish waters include Carlingford Lough; the bathing waters include Portstewart and Castlerock beaches. Nutrient-sensitive areas include Lough Muckno, the River Blackwater and Lough Neagh, Special Areas of Conservation include the Bann Estuary and Slieve Gullion and Special Protection Areas include Carlingford Lough and Lough Neagh/Lough Beg.

Pressures

The main pressures on our waters come from:

- wastewater and industrial discharges
- landfills, quarries, mines and contaminated land
- agriculture
- wastewater from unsewered properties
- forestry
- usage and discharge of dangerous substances
- physical modifications
- abstractions
- local and future issues. In the Neagh Bann District, they include climate change, aquaculture and invasive alien species, as well as the need to protect high quality areas and to manage shared waters issues properly.

We can achieve the greatest gain by concentrating our efforts on those issues that pose the greatest threat to our water environment. Two key sectors stand out, agriculture and the water industry. Both Northern Ireland Environment Agency and the Environmental Protection Agency have identified the need to take action in response to these sectors in the River Basin Management Plan. *“Discharges from municipal wastewater treatment works and from agricultural activities are the principal suspected causes of less than satisfactory water in the State. Industrial discharges and discharges from several other activities have also been identified as contributing to a lesser extent.”* (Environmental Protection Agency, 2008)



Measures and objectives

The measures to improve our waters fall into three categories:

- the implementation of 11 key directives, specified under the Water Framework Directive and already transposed into domestic legislation
- the implementation of other stipulated measures required by the Water Framework Directive
- the use of additional or supplementary measures.

Basic measures

The first two categories are referred to as **basic measures**. They are:

The 11 key EU Directives	Other stipulated measures
Bathing waters	Cost recovery for water use
Birds	Promotion of efficient and sustainable water use
Habitats	Protection of drinking water sources
Drinking waters	Control of abstraction and impoundment
Major accidents	Control of point source discharges
Environmental impact assessment	Control of diffuse source discharges
Sewage sludge	Authorisation of discharges to groundwaters
Urban wastewater treatment	Control of priority substances
Plant protection products	Controls on physical modifications to surface waters
Nitrates	Controls on other activities impacting on water status
Integrated pollution prevention control	Prevention or reduction of the impact of accidental pollution incidents

Supplementary measures

A range of possible supplementary measures has been identified by a series of technical studies. Some are already being taken: they include farm based environmental protection schemes and implementation of a suite of forestry good practice guidelines. Other possible measures are codes of practice, voluntary agreements, demand reduction and rehabilitation programmes and legal, administrative and economic instruments.

Supplementary measures range from **reducing** the pressure at source through **remediation** by technical or engineering solutions to **relocation** of the pressure. They have to be technically feasible; the combination of supplementary measures must be the most cost-effective and the cost of these combinations of measures must not be significantly greater than the benefits gained. The impacts of the supplementary measures on the wider environment have to be considered, through Strategic Environmental Assessment, to ensure that they are sustainable.

Our objectives for each category of waters


These charts show the improvements we expect in each category of waters over three cycles of the river basin district planning process.

GES or **GEP** means **good ecological status** or **good ecological potential**, in other words compliant with the Water Framework Directive. The standard of good ecological potential is applied to artificial and heavily modified waters (such as canals and reservoirs) where the benefits to humans need to be retained.


LSO means **less stringent objective**, which means that the waters won't achieve good status or good potential before 2027.

Rivers and Canals (number)


0.3% of rivers and canals are unclassified



Lakes and Reservoirs (km²)




Estuaries (km²)




Coastal Waters (km²)

11.6% of coastal waters are unclassified



Groundwaters (km²)



What happens next



The full text of the draft plan is available on www.wfdireland.ie along with background documents including technical studies into our key water issues, our register of protected areas, and documents detailing monitoring programmes and status development, economics, objectives, programmes of measures and links to plans and programmes. There is also a list of the District's relevant authorities and stakeholders, as well as documents on climate change and Strategic Environmental Assessment. Our interactive webmap viewing tool can also be accessed at www.wfdireland.ie.

Comments, views and suggestions may be sent by 22 June 2009 to:

Martin Murray
Monaghan County Council
Environment Section
County Offices
The Glen
Monaghan
Co Monaghan
mpmurray@monaghancoco.ie

Early responses would be appreciated to allow more time to clarify and resolve issues that may arise.



We will comply with data protection requirements and will use information that you provide to compile a digest of responses. Please let us know if you wish your response to remain anonymous: if you do, we will include your comments in the digest without saying who made them. If you want to add new comments or information you can contact our website at any stage (www.nbirbd.com).

Implementation



The Neagh Bann International River Basin District is cross-border; partly in Ireland and partly in Northern Ireland. This leaflet refers to the draft River Basin Management Plans for the District which were issued by the county councils of Monaghan, Cavan, Louth, and Meath and by the Northern Ireland Environment Agency. Preparation of the draft plans has been closely coordinated between the two jurisdictions and these coordinated arrangements are outlined in the document entitled **Working Together** (www.wfdireland.ie).

The task of implementing the management plans will fall mainly to the statutory authorities. In the case of the Neagh Bann District, it is envisaged that a unit will be set up by Monaghan County Council to coordinate the work of Ireland's statutory authorities and to coordinate work with the Northern Ireland Environment Agency. In Ireland, implementation of the plans will be coordinated by the Department of the Environment, Heritage and Local Government, working together with the local authorities, the Environmental Protection Agency and other relevant public authorities. In Northern Ireland, work will be coordinated by the Department of the Environment and Northern Ireland Environment Agency, through the Interdepartmental Working Group, which includes the four main government departments responsible for implementing the plan.



**Local Government (Water Pollution)
Act 1977
(Water Quality Standards for
Phosphorus) Regulations, 1998**



**MONAGHAN COUNTY
COUNCIL**

4th Implementation Report

July 2006

Local Government (Water Pollution) Act 1977 (Water Quality Standards for Phosphorus) Regulations, 1998.

4th Implementation Report

Monaghan Co Council.

Introduction:

The Phosphorus Regulations (1998) require the Monaghan Co Council to protect satisfactory waters and to improve unsatisfactory waters. Water quality interim targets have been set for 2007. However Monaghan Co Council has applied for an extension to 2013. (In the 2004 EPA audit, an EPA officer advised against reliance on the 2013 deadline as the more stringent Water Framework Directive deadline of 2015 for both good chemical and biological status will also need to be complied with.) The Phosphorus Regulations require Monaghan Co Council to submit a biennial implementation report to the Environment Protection Agency. The 4th Implementation Report is due for submission to the Agency on 31/7/2006.

Section 1. Water Quality in Co Monaghan

River Monitoring

Baseline Data

The baseline data for the County, established from the EPA's Biological Monitoring Programme (Q Ratings) since 1995 indicates that **30%** of river stations monitored were of satisfactory quality (Q rating ≥ 4) while **70%** of stations monitored were unsatisfactory (Q rating $\leq 3-4$). Table 1.1 refers.

Current Status Rivers

This 4th Implementation Report relates to the reporting period Jan 2004 to Dec 2005. Reference to physio-chemical data in this document relates to water quality monitoring carried out by Monaghan Co Council in the period Jan 2004 to Dec 2005.

Reference to river current Q ratings, relate to the Q rating assigned by the EPA. The 06 Hydrometric area was monitored in 2003 while the 03 and 36 Hydrometric areas were monitored in 2004. Table 1.1.refers

Current data indicates

- 33% (22 out of 66) of river stations monitored are classified as unpolluted (Q ratings > 4 - 2003/04 data). This figure is low by national standards.
- 24% (16No.) of river monitoring stations show an improvement in Q rating from baseline data

- 27% (18No.) of stations monitored show a decline in Q rating.
- 71% (55 out of 77) of stations with Q data and/or Median P values achieve standards set out in Section 3(2) of the Phosphorus Regulations. Section 3(2) allows compliance with the Phosphorus Regulation targets by achieving either the standards set for Q rating or MRP (Molybdate Reactive Phosphate) value.

Water Quality Trends: Rivers

Q Ratings

Since the 95-97 baseline period no significant improvement in overall biological water quality in the County is apparent. Although 24% of sites monitored in the 2003 and 2004 do show an improvement from baseline data, a further 27% of sites monitored show a decline in quality. Since the mid 90's there are no longer any pristine sites (Q 5) recorded in Co Monaghan. However the improvements in the Erne catchment noted in 2004 are promising.

Physio-chemical Data:

Water quality data does provide some information on water quality trends in the county. A decline in river phosphate levels has been noted in some rural areas. However, many other river stations do not show a similar decline as yet.

Noticeable water quality improvements have followed the upgrading of urban wastewater treatment plants and upgrading/removal of industrial treatment plant discharges. The Blackwater River below Monaghan Town and the Proules River below Carrickmacross have improved from baseline quality. However water quality in these river stretches – designated as “sensitive waters” under the Urban Waste Water Regulations, remains unsatisfactory (as defined by the EPA). Continued urban development is placing additional pressures on infrastructure and water quality downstream of urban areas. Discharges of untreated or partially treated urban waste waters via storm overflows or overloaded collection systems can have significant effects on water quality and these problems have been referred to Water Services for examination and appropriate remediation.

Since Jan. 2004 the frequency of river monitoring has been increased to 12 samples per annum every 2 years. Median P values are now available for almost all EPA Q rated sites. Results for Median P levels are shown in Table 1.1.

Lake Monitoring

Monaghan Co Council's lake monitoring programmes for 2004 and 2005 have been completed and results reported to the EPA. A total of 50 lakes have been monitored at sampling frequency of one lake sample per annum for the smaller lakes and two to four lake samples for the larger lakes. Lake sampling is resource intensive and Monaghan's sampling frequency has remained low. However the new Water Framework Directive Monitoring Programme, due to commence in Dec 2006 requires a review of sampling frequency – final details have yet to be decided.

Currently lake sampling is carried out in the summer months with the assistance of Civil Defence staff (2 persons) and equipment (boat and pickup truck) and a summer student. The current sample collection takes 10 to 12 days approximately. Water samples are analysed by the EPA Laboratory in Monaghan Town.

Due to low frequency of lake sampling only the Chlorophyll level can be used for classification purposes and compliance checking. If the Total Phosphorus (TP) parameter were to be included a minimum of 10 samples per annum would be required.

Lake Water Supply Sources

Work is currently ongoing to integrate the protection of the 23 lakes used as water supply sources into development planning and control. Maps of surface water sources are included in the current Draft Co Development Plan for Co Monaghan.

Current Status - Lakes

Lake Trophic Status (2004/2005)

The lake trophic status shown in Table 1.2 is derived from the maximum Chlorophyll level measured in the period 2004 to 2005. Current data indicates 46% of lakes comply with requirements of the Phosphorus Regulations based on chlorophyll levels only. Table 1:2 refers

Note:

Lake chlorophyll levels can fluctuate significantly throughout the year. Chlorophyll levels do not always indicate the same degree of eutrophication as do the available Total Phosphorus levels. Total Phosphorus levels in some lakes in Co Monaghan are extremely high.

Water Quality Trends: Lakes

The 2004/2005 lake data indicates an increased number of lakes in the satisfactory category (i.e oligotrophic and mesotrophic). However the high number of lakes (over 80%) with elevated Total Phosphorus levels is a cause for concern.

Tables A and B below show a comparison of current lake trophic status with baseline status and Lake Total Phosphorus (TP) levels for the 2001 to 2005 period..

Table A: Comparison of Lake Data 1995-2003

Annual Max Chlorophyll level ppb	Trophic Status	Baseline data 95-2001 (no. of lakes)	Current Trophic (2004/2005) Classification (no. of lakes)
<8	Oligotrophic		6
≥8 <25	Mesotrophic	11	9
≥25<75	Eutrophic	19	24
≥75	Hypertrophic	16	11

Table B: Lake Total Phosphorus Levels –Average Value of 2001 to 2005 data

Total Phosphorus Average Conc (ppb) 2001-2005 (MCC data)	No. of Lakes in each category
<30	8
30-59	16
60-99	17
>100	10

Water Framework Directive lakes:

Lakes proposed for additional monitoring under the Proposed WFD Monitoring Programme and their current trophic status includes:

Lake	Current Status
Avaghon lake	Mesotrophic (– but algal blooms noted in recent years)
Drumlona	Eutrophic
Emy	Mesotrophic
Egish	Eutrophic.
Inner	Hypertrophic
Naglack	Hypertrophic
Monalty	Hypertrophic
Muckno	Hypertrophic
White	Eutrophic
Dromore	Status unknown

Groundwater Quality

The Phosphorus Regulations 1998 deal with surface waters and although ground water quality may impact on surface waters sufficient data is not available in relation to this aspect. The situation regarding groundwater quality will be addressed as the Water Framework Directive is rolled out. A Groundwater Protection Scheme for Co Monaghan has been produced by the GSI. Work is currently ongoing to integrate the Groundwater Protection Scheme into planning decision making and maps of groundwater sources and resources are included in the current Draft Co Development Plan.

Section 2. Implementation of Measures

Monaghan Co Council's Measures Report in 1999 identified a need for additional resources to implement proposals to protect and improve water quality. Although additional staff were recruited following completion of negotiations under BLG (Better Local Government) in 2001, the Phosphorus Team has since lost 2 experienced Environmental Officers. One Environmental Officer (temp) is now in training.

Use of Consultants

In 2005 additional resources were allocated to employ consultants (*RPS Consultant Engineers*) to carry out farm surveys and to highlight farms that will require follow up action by the Council staff. However, without experienced field staff in-house catchment survey work and the necessary follow up of problem premises is currently suspended with a review of the situation due in October 2006.

Monaghan Co Council continue to use the services of Conservation Services to carry out detailed Biological Surveys of rivers. This work highlights "hot spots" and a number of such "hot spots" are awaiting follow-up surveys.

In the 2004-2005 period the Phosphorus Team has been involved in a number of specific work areas as follows:

- Catchment surveys - initially work has been concentrated moderately polluted river stretches and unsatisfactory lakes. Work has progressed well but extensive areas of the County are as yet not surveyed. See Map in Appendix 1 outlining Progress.
- Database management and updating GIS programme
- Review and updating of water quality monitoring programmes and the introduction of additional Biological Monitoring using a private consultant.
- A survey and report of Urban Wastewater Treatment plants and collection systems.
- Continued enforcement of Water Pollution Acts and Waste Management Act.
- Awareness raising to achieve sectoral involvement in protection and improvement of water quality.

The Phosphorus Team also tries to work closely with Planning control staff, other Environment Section staff and Water Services Section although more integration in this area is deemed necessary.

Future Developments in the area of Water Management

During 2004 a number of Projects relating to water quality issues in Co Monaghan have been initiated. These include:

- North South SHARE Project on River Basin Management Planning.
- Blackwater Regional Partnership TRACE Project on the Definition and Mitigation of Excessive Multi-source Nutrient Loss to Water, lead by University of Ulster and Queens University, Belfast.
- Churchill Oram Source Protection Pilot Scheme led by the National Federation of Group Water Schemes and the Freshwater Studies Unit at DKIT.
- Blackwater Vital Signs Schools project .

- Monaghan Co Council has participated in the Erne Blackwater Surface Waters Working Group.
- The County Development Board has included the Improvement of Water Quality in Co Monaghan as an Action in the CDB Strategy for Co Monaghan.

Monaghan Co Council will provide available water quality data for the Project leaders and is involved as Steering Group members and/or in an advisory role. The benefits of such projects are expected to be increased knowledge of water quality issues, improved water quality management, improved public and sectoral participation, and increased awareness.

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Section 3.

Progress to Date

There is evidence that the biological quality of rivers continues to decline in Co Monaghan. Of particular concern is the recent loss of pristine and high quality sites in upland areas. It is expected that resource intensive catchment survey work, additional monitoring, enforcement and in some cases changes in land use or other measures will be required to bring about water quality improvements. It is expected that the turn-around period between intensive catchment survey work, enterprise improvements and water quality improvements could be a minimum of 2-3 years depending on catchment characteristics.

Improvements in Hydrometric Area 36 (Erne Catchment)

Promising results were evident in the 2004 EPA Biological Monitoring of Hydrometric Area 36 (Erne Catchment).

Although Monaghan Co Council have completed catchment survey work in sub-catchments of the Erne River (Bunroe and Maghery Rivers have been surveyed in 2002 and 2003) improvements are also noted in other sub-catchments. It is suspected that the intensive surveillance and enforcement work carried out by the Northern Regional Fisheries Board (NRFB) for several years has contributed significantly to improvements in water quality in this area. Discussions with the Eastern and Northern Regional Fisheries Boards have revealed that additional resources have been dedicated to surveillance and enforcement work in the NRFB area for a number of years.

Progress has been made in pursuing measures set out to tackle water pollution in Co Monaghan. Improvement in the chemical data at some river stations is evident, upgrading of industrial treatment plants continues and investment in Water Services is ongoing. Progress in various work areas is detailed below and in Table 3,4, and 5 attached in Appendix 2. However additional resources are considered necessary to successfully identify and follow up on pollution sources in the county.

Catchment Surveys

Catchment surveys commenced in May 2002 with a focus on small rural catchments where water quality was classified as moderately polluted. All agricultural, industrial and commercial premises were surveyed in each catchment. Communal septic tanks and village areas were also surveyed. The aim of catchment surveys was to identify and eliminate point sources of pollution and identify potential diffuse sources of pollution for further attention.

Over the period Jan 2004 to Dec 2005, a total of 352 premises (mainly agricultural) were surveyed. 110 advisory letters were issued, 21 Section 12 Notices were issued. A total of 450 reinspections of silage making facilities (including facilities surveyed pre 2004) and 158 reinspections of medium and high-risk wintering facilities were reinspected in the summer and winter periods respectively.

Current Status of Catchment Survey Work Table (refer to Map of progress Appendix 1)

Table C

Catchment /River	Survey By	Comments
Emy Lough catchment	2003, MCC Staff	Limited follow up of due
Mountain Water Tributary	2004/05 -TRACE Project	Pollution mitigation measures due to be installed in 2006
Scotstown River	2004, MCC Staff	Follow up inspections due
Blackwater (upper reaches)	2004, MCC Staff	Follow up inspections due
Maghery, Kilcoran and Magherarney Lakes	2002 MCC	Limited follow up due
Lough Oony	2003 MCC	Follow up on 1 farm due
Conawary River	2005/06 MCC	Follow up inspections due
Ballagh lake	2006 MCC	Follow up inspections due
Clontibret Stream	2003/04 MCC	Follow up inspections due
Bunroe River and Annamakerrig Lake	2003 MCC	Limited follow up due
Drum lake	2003 MCC	Limited follow up due
Avaghon lake Stream, Mullanary and Corkeeran Lakes	2002 MCC	Limited follow up due
Namachree Lake	2002 MCC	Follow up on 1 septic tank due
Milltown lake Catchment	2005/06 Dundalk Inst. Of Tech.	Extensive monitoring completed – Farm and septic tank survey due 2006
Rossdreenagh River	2006 RPS on behalf of MCC	All follow up outstanding. (MCC to carry out follow up)
Inner Lough	2003 NRFB	

Database Management and Mapping

Consultants completed a GIS Mapping Project and Sludge Management Plan for Co Monaghan in Spring of 2002. The GIS Project provides a comprehensive mapping tool for catchment survey work. As the catchment surveys progress it is intended that data on all enterprises are entered on an access database and mapped using GPS.

Due to the extent of agricultural activities in the County and their potential impact on the environment, work commenced in 1999 on collection of relevant agricultural data. A comprehensive database on intensive agricultural enterprises, soil phosphorus returns, and a poultry manure waste tracking system has been established.

Monitoring Programmes

Lake Monitoring Programme

As detailed in Section 2 page 3.

River Monitoring

From Jan 2004 monthly river water samples have been collected and each river monitored for one 12 month period every two years. This work is contracted out to the EPA Regional Lab, Monaghan Town. The river sampling programme has been extended to include all river stations Q rated since 1995.

Additional Monitoring

Additional Monitoring Programmes carried out to identify “Hot Spots” and provide additional information of water quality in selected catchments and their tributaries are shown on Table D below.

Table D

River	Type of Monitoring	Comments
R Blackwater (03/B/01), and Tributaries including 03/S/02, 03/S01,	Physio-chemical, flow and biological monitoring in 2002-2003 period	Partial catchment survey work carried out in 2004– survey follow up due.
Mountain Water (03 M01) and Tributaries	Physio-chemical and biological monitoring – 2003-2004 period	Some problem areas identified – catchment awaiting survey
Emy Lough Stream	Physio-chemical and biological monitoring in 2004	Mini catchment survey completed 2003.
Finn River (36/F/01) and Tributaries	Physio-chemical monitoring 2004	Not yet scheduled for catchment Survey
Avaghon Lake Stream (36 A07)	Post survey Biological Monitoring	Catchment surveyed 2002, Lake outflow identified as significant
Maghery River (36/M/03)	Post survey Biological Monitoring	Both catchment survey in 2002 and Biological Monitoring 2005 failed to pinpoint source of low Q values in the upper reaches.
Knappagh (36/K/01)	Biological Monitoring (partial survey)	Suspected source ceased, River Q improved.
Conawary Lower (03/C/01) and tributaries	Physiochemical Monitoring	Catchment Survey 2005/06. Follow up due.
Proules (06/P/01)	Biological Monitoring (partial Survey)	Mini catchment Survey- urban sources of pollution identified

General Activities under the Water Pollution and Waste Management Act:

General activities of the Environment Section in the reporting period 2004 to 2005 Monaghan Co Council include the following enforcement work under the Water Pollution and Waste Management Acts.

11 cases referred for prosecution under of the WPA and WMA

28 Section 12 notices have been issued

17 Section 55 Notices have been issued.

The Council's Environment Section continues to investigate environmental complaints. Approximately 800 environmental complaints were received in From Jan 2004 to Dec 2005, many of which related to illegal dumping and litter. 58 water pollution complaints were investigated in same period.

Industrial Discharges

Significant improvements have been carried out by Industry in Co Monaghan. There are currently 22 "active" Licences issued under Section 4 of the Water Pollution Act. There are currently Section 4 Licence applications under consideration Almost all active Licences have been inspected at least once in the 2004 to 2005 period and monitoring of discharges is ongoing.

No prosecution cases for breaches of Section 4 of the WPA were taken in this period.

Landfill

Monaghan Co Council's Landfill being operated under a Licence from the EPA.

Awareness Raising During 2004 and 2005

The Phosphorus Teams Awareness Raising Programme has included the following activities:

Information / Public Meetings, During the reporting period a total of 5 meetings with the following groups were organized, IFA, Northern and Eastern Regional Fisheries Boards, and an Industry Group. Council staff gave presentations at 3 meetings organized by the IFA Co Executive and IFA Waste Management Committee. Presentations were given at 4 REPS meetings at the request of a REPS Planner. The Co Development Board Environment and Agriculture Working Group, the Erne Blackwater Surface Water working Group and TRACE Steering Group Meetings have also increased networking and information sharing between Council, stakeholders and research bodies.

Catchment Information Leaflets

Individual information leaflets with local water quality information have been produced for each catchment surveyed. Leaflets are distributed to each premises surveyed. See Appendix 2.

Information Leaflets on *Managing Phosphorus in Farming* (2 No) and *Prevent Silage Pollution* have been produced and pre 2004 were circulated via the Dairy CoOps. We continue to send out these leaflets where a need /problem is identified. A leaflet on *Septic Tank and Wastewater Treatment System Guidelines* has been produced and is distributed

to households with problem or suspect septic tanks. From June 2006 it is proposed to circulate the “Septic Tank/Treatment System “leaflet with planning approval notices. Press Articles and Adverts/ Radio A total of 25 articles and adverts relating to water quality appeared on local press. Adverts related to Good Farming Practice, slurry spreading and silage making. Articles on general water quality were placed in 2 Council Environment Bulletins.

Advisory Letters. Approximately 80 farmers were sent advisory letters in relation to Soil Testing for Phosphorus. Over 110 advisory letters have been issued following catchment surveys.

One to one Site meetings Staff have carried out over 400 site visits in relation to catchment surveys and water pollution complaints during the 2004 and 2005 period.

Liaison with the Planning Section

Environment section staff continues to liaise with the Planning Section regarding environmental assessment and control of new developments. A very substantial (two and a half fold) increase in the number of planning files examined by the environment section was recorded in the 2004-2005 period. In the period 2004 to 2005 the environment section have examined and reported on 761 planning files that include 205 agricultural, 201 housing schemes, 364 industrial/commercial developments and 9 public schemes. Contributions have been submitted to the proposed Development Plan to improve aspects of sustainable development.

Period	Agricultural	Comm./Industrial	Housing Dev/ other	Other	Totals
2003-2003	113	93	52		258
2004-2005	205	346	201	9	761

Liaison with Water Services:

A member of the Phosphorus Team surveyed 21 local authority operated waste water treatment plants in early 2005. A report is currently in preparation and will be presented to management and discussed with Water Services in late 2006.

Problems Encountered

The continued decline in water quality is still evident. Development pressures are a cause for concern. A very substantial increase in development activity is evident. Criteria for sustainable development would be useful. Monitoring of new developments to ensure compliance with planning conditions attached to protect waters is considered necessary but as yet not undertaken.

Staff Retention – the Phosphorus Team lost 2 fully trained members of staff one in May 2004 and the second in May 2006. Some slow down in catchment survey work is evident as a result. In addition to replacement of staff members with trained officers it is essential that further resources will be required to achieve the targets set in the Phosphorus Regulations and to build capacity within the council to implement the required programme of measures that will accompany the River Basin Management Plans under the Water Framework Directive.

Lack of integration of environmental protection policies into the activities of various sectors (particularly in the recent past).

Cross border pollution incidents can be more difficult to resolve.

It would be beneficial to develop a reliable risk assessment tool for diffuse source pollution.

Computer facilities/tools for the interrogation of environmental data and trend analysis are also considered necessary.

The local authority role of “poacher” and “gamekeeper” can give rise to concerns by the public of the effectiveness of local authority’s pollution control role.

Successes to date

The review of CAP and the changes in farm payments from production based payments to single payments scheme is likely to benefit water quality in the medium to long term. Information meetings resulted in offers of cooperation and are considered very beneficial. Good relationships with industry and improvements in industrial wastewater treatment in recent years.

Cooperation with the IFA is resulting in regular contacts with farming groups. Staff are encountering a positive response to site inspections on farms.

The EPA biological monitoring for one of the three catchments surveyed by council staff in the 2002/2003 period indicated significant improvements in water quality in 2004. The other two catchments remain as yet moderately polluted – requiring further investigation. Improvements in the Biological Quality of the Erne Catchment are promising (page 8 refers)

Participation in projects described on page 6 should result in better knowledge of activities contributing to water pollution, effective mitigation measures and improved participation.

Summary

Co Monaghan faces a particular set of problems in relation to water quality, which to some extent are unique to this county. It is a drumlin county, with heavy soils in many areas resulting in high runoff risk. The extent of intensive agricultural activities in Co Monaghan poses problems for the recovery /disposal of agricultural waste in an environmentally sustainable manner. In addition many of the county's rivers have low assimilative capacity.

Rapidly expanding industrial and commercial activities, rural housing and expansion of urban areas need to be controlled and monitored. Monaghan Co Council need a fully resourced and dedicated Team to progress measures set out in the Measures and Implementation Reports

There will be ongoing review of measures to maximize effectiveness of measures to improve water quality in the county.

For inspection purposes only. Consent of copyright owner required for any other use.

TABLE 1.1: RIVER WATER QUALITY STANDARDS TO BE ACHIEVED BY 2007												
Monaghan		Implementation Report Year			2006							
River Name	River Code	Biological Monitoring Station	Station Location Name	Grid Reference	Grid Ref. Cont	Baseline Q-value	Is Baseline Quality Satisfactory? Yes/No	Current Q-Value (2003-2005)	Current MRP Value ug/l P (04-05)	Standard to be Achieved by 2007 Q Value	Standard to be Achieved by 2007 MRP Value	Has Either Standard Been Achieved ?
				Easting	Northing							
MOUNTAIN WATER	03M01	0400	1st Br u/s Emyvale	267050	343350	4	y	3-4	30	4	30	y
MOUNTAIN WATER	03M01	0500	Br 1.1 km d/s Emyvale	268540	343110	3-4	n	3	40	4	30	n

For inspection purposes only.
Consent of copyright owner required for any other use.