

KPMG Restructuring Stokes Place St. Stephen's Green Dublin 2 Ireland Telephone +35 Fax +35 Internet www

ne +353 1 410 1000 +353 1 412 1122 www.kpmg.ie

Environmental Protection Agency IPPC Licensing Office PO Box 3000 Johnstown Castle Estate Co Wexford

20 May 2013

Dean Waste Co Limited (In Receivership) Sale of Transfer Station at Greenhills Road, Walkinstown, Dublin 12 Licence No W0045-01

Dear Sirs,

I wish to advise you that I was appointed Receiver and Manager over certain assets of Dean Waste Co Limited on 8 June 2010. The assets over which I was appointed Receiver and Manager include the Waste Transfer Station on the Greenhills Road, Walkinstown, Dublin 12.

I wish to advise you that I have entered into a contract for the sale of this Transfer Station to Key Waste Management Limited on 8 September 2011.


I enclose herewith the Transfer of Licence Application Form to transfer the Licence from Dean Waste Co Limited to Key Waste Management Limited, together with cheque in the amount of €5,000 to cover the application fee.

I understand from your colleague, Lisa Maher that there is a short time frame expiring on 8 June 2013 on the transfer of the Licence and I look forward therefore to hearing from you as soon as possible.

Yours faithfully,

TAOhic

Padraic Monaghan Receiver Dean Waste Co Limited (In Receivership)



Terence O'Rourke • Marie Armstrong • Darina Barrett • Alan Boyne • John Bradley • Gareth Bryan • Sharon Burke • Niall Campbell Patricia Carroll • Brian Clavin • Jim Clery • Colm Clifford • Kevin Cohen • Mark Collins • Ivor Conlon • Michele Connolly Adrian Crawford • Hubert Crehan • Killian Croke • Brian Daly • Jon D'Arcy • Michael Daughton • Paul Dobey • Eamonn Donaghy Robert Dowley • Michael Farrell • Patrick Farrell • Caroline Flynn • Michael Gaffney • Andrew Gallagher • Laura Gallagher • Donall Gannon Frank Gannon • Michael Gibbons • Ruaidhri Gibbons • Roger Gillespie • Colm Gorran • Searnus Hand • Johnny Hanna • John Hansen Ken Hardy • Michael Hayes • Selwyn Hearns • Paul Hollway • Declan Keane • David Kennedy • Jonathan Lew • Liam Lynch • Olivia Lynch Ryan McCarthy • Pat McDaid • Tom McEvoy • John McGione • Emer McGrath • Niamh Marshall • David Meagher • Brian Morrissey Cliona Mullen • Shaun Murphy • Arthur O'Brien • Colin O'Brien • Conor O'Brien • Barrie O'Connell • Connell O'Halloran • Searn Clean Reaithe • Garlagher • Anna Scally • Vincent Reilly • Colim Rogers • Selwan Russell • Anna Scally • Paul Toner • Eric Wallace • Kieran Wallace • David Wilkinson • Tom Woods • Lukas Ziewer

KPMG, an Irish partnership and a member firm of the KPMG network of independent member firms affiliated with KPMG International Cooperative ("KPMG International"), a Swiss entity Offices: Dublin, Belfast, Cork and Galway

KPMG is authorised by Chartered Accountants Ireland to carry on-Investment Business: EPA Export 04-06-2013:23:45:10

For inspection purpose only any other

EPA Export 04-06-2013:23:45:10

150



110

Environmental Protection Agency

2.1 MAY 2013

IPPC/Waste Licence Transfer Application Form

This document does not purport to be and should not be considered a legal interpretation of the provisions and requirements of the Waste Management Acts, 1996 to 2012 or Environmental Protection Agency Acts 1992 to 2012.

ور المراجع ال

Environmental Protection Agency P.O. Box 3000, Johnstown Castle, County Wexford Telephone: Lo-Call 1890 335599; 053-9160600 Fax: 053-9160699

çoa

Section 1 of this application form must be completed by the current Licensee and accompanied by required attachments. Section 2 must be completed by the Proposed Transferee and accompanied by required attachments. Both parties must complete Section 3. The transfer application shall not be regarded as complete and will not be processed unless all information requirements as set out in this form are met in advance of the application being submitted to the EPA.

Section 1: To be Completed by Current Licence Holder (Licensee)

F		
1.1	Register Number of	W0045-01
	Licence to be Transferred	
1.2	Name of Current Licensee	Dean Waste Co. Limited.
		(In Receivership)
1.3	Address of Current	C/o Padraic Monaghan
1.5	Licensee	Receiver
	Licensee	
		Dean Waste Co. Limited
		1 Stokes Place se
		St. Stephen's Green
· ·		Dublin 23 and
l.		
		1110 ruite
1.4	Contact details for	Radraic Monaghan
	nominated person(s) or the	01 4101707
	persons in relation to the	
	transfer application	
	sent	
1.5	Class/Nature of Activity	Waste Transfer
1.6	Location of activity to	Greenhills Road, Walkinstown,
1.0	which the licence relates	Dublin 12
	which the heater relates	
1.7	Name of Proposed	KeyWaste Management Ltd
1./		
	Transferee	
1.0	Desser for lisener	Discontract dated & Contamber 2011
1.8	Reason for licence	By contract dated 8 September 2011
	transfer request (provide	the property at Greenhills Road, D 12,
	detail in fifty words or	which the licence relates to, is being
	less)	sold by Dean Waste Co. Limited (in
	· · · · ·	Receivership) to Key Waste
	·	Management Limited.
1.9	Desired date for proposed	8 September 2011
	transfer to take effect?	
L		

Version 5: 08/10/2012

1.10	Has the Licensee	Yes – A fully costed ELRA has been
	arranged for the	completed and submitted to the EPA.
	completion, by an	
	independent and	Yes - see attached approval letter dated 10
	appropriately qualified	May 2013 from EPA
	consultant, of an up-to-	
	date and fully costed	
	Risk Assessment of	
	environmental liabilities	
• • • : . ·	for the site (ELRA or	
	equivalent), which will	
· •••	address liabilities from	
	past and present	
	activities?	
		의 철말 경제한 時代 위치가 가지 않는 것이 가지 않는 것이 있다.
	And	
		and a second second Second second
	Has the Risk Assessment	
·	been approved by OEE?	
·• *	(Provide copy of OEE approval	
	letter as Attachment 1B)	A USO
		othe
1.11	Has the Licensee	Yes – A fully costed Closure &
	prepared an up-to-date	Decommissioning report has been
1. A.	and fully detailed and	completed and submitted to the EPA.
	costed plan for the	thon per t
	decommissioning of	Yes – see attached approval letter dated 10
	closure ¹ (DMP/CRAMPOOR	May 2013 from EPA
• • •	equivalent) of the site or	
	part thereof?	
~	Cons	
	And	
· · · .	Has the Decommissioning	
	/Closure Plan been	
	approved by OEE?	
	(Provide copy of OEE approval	
	letter as Attachment 1C)	
	L	

- The plan must show estimated expenditure for each phase of the activity/activities and include:
 - (i) Likely costs of abatement installation, control & monitoring;
 - (ii) Likely costs of closure & remediation of the site;
 - (iii) Likely costs of clean-up following a plausible accident/incident;
 - (iv) Likely costs of long-term aftercare for residual environmental, ilabilities;
 - (v) Statement or details of provisions made for the underwriting of these costs/liabilities.



Section 1 Attachments: The following documents <u>must</u> be provided to the EPA by the current Licensee to support the licence transfer request. Failure to do so will result in the transfer application form being returned.

Attachment 1A	As per Section 47(3) of the Waste Management Acts 1996 to 2012 / Section 94(3) of the Protection of the Environment Acts 1992 to 2012), provide a copy of the licence to be transferred.
Attachment 1B	Provide a letter of approval from the EPA's Office of Environmental Enforcement (OEE) for the Risk Assessment referred to in Q1.10.
Attachment 1C	Provide a letter of approval from the EPA's Office of Environmental Enforcement (OEE) for the Decommissioning/Closure Plan described in Q1.11.

Page 4 of 11

ିତ୍ରେ

; :

Section 2: To be Completed by Proposed Transferee

2.1	Name of Proposed	KeyWaste Management Ltd
	Transferee	1.18、18.11、1911年代(1911年)(1911年)(1911年)(1911年)(1911年)) 1.11日(1911年)(1911年)
2.2	Address of Proposed	Greenview, Greenhills Road,
	Transferee	Walkinstown, D,12
		alter et al de la companya de la comp
2.3	Contact details for	Mark Butler
2.5	nominated person(s) in	01 4299846
	relation to the transfer	01 72 9 90 70
	application	
		Kay Masta Managament 1td provides
2.4	General background on the	KeyWaste Management Ltd provides
	Proposed Transféree. (approx. 150 words or less)	waste collection services. The company
	Details to include:	was established in 2005. The company
	Business activity of	is a trading entity based in Ireland. The
	Dropogod Transform	company has a turnover of between
	Date established	€5-€10m.
	(companies only)	see.
	Most recent details on	Not the second sec
	total assets value,	N. NO
i	turnover and profit	Softor
	(where available)	o ^{osered}
· .	State whether Proposed	- Tureout
	Transferee is a holding	And the t
	company	LOT
	provide similar details	
· ·	for ultimate parent	
	company (also include jurisdiction where	
	ultimate parent company	
	is registered)	
2.5	Has the Proposed	No
2.5	Transferee/other relevant	
1.	person been convicted	
	under any of the	
	following:	
	EPA Acts 1992 to	
	• EPA ACIS 1992 to 2012?	
. •	•	
	Waste Management Acts 1996 to 2012?	
.	Local Government (Water Bellution) Acts	
	(Water Pollution) Acts	
	1977 and 1990?	
	• Air Pollution Act 1987?	· · ·
·		
	If yes, provide full details.	

Page 5 of 11



Version 5: 08/10/2012

2.6	Provide:	Dritan Gjoni, Logistics.
		Dritan has worked as a facility manager
	(a) names	for both Thorntons Recycling and
	(b) details of relevant	Greyhound Recycling over a seven year
· .	education, training	period. Dritan joined KeyWaste in 2011
5 A A	and experience; and	and has managed the logistic function
	(c) responsibilities	in the business over the past two
		years. Dritan will also manage the
	of all persons to provide	movement of waste on and off the
	management and	Greenhills road facility when it becomes
•	supervision of the	operational.
	activities authorised by	
	the licence (in particular	Arek Michonski, Fleet & Resources.
	the name of the facility	Arek was previously a Weighbridge
· · ·	manager and any	operator at Greyhound Recycling &
	nominated deputies).	Recovery and was promoted to Site
		Manager in 2007. Arek joined
		KeyWaste in 2008, he is a senior
,		manager with responsibility for
. •		managing vehicle fleet and operational
		personnel. 💞

Consent of copyrige

Page 6 of 11

. . . .

Licence Transfer Appl	ication Form

êoa.

n) e

Version 5: 08/10/2012

	e e e e e e e e e e e e e e e e e e e	
2.7	Has the Proposed	The letter from the OEE approving the
	Transferee made	Financial Provisions as required by
	adequate financial	section 2.7 is outstanding.
	provision ² to meet the	Consideration of the Key Waste
.•	financial commitments/	Management Ltd Financial Provision
	liabilities that will be	submission is on-going.
		submission is on-going.
	entered into/incurred in	
	carrying on the activity to	
	which the licence relates	
•	or in consequence of	
• •	ceasing to carry on that	
	activity as the licence may	
· .	specify*?	
	And	
· .		
	Has the financial provision	
	been approved by OEE?	
	(Provide copy of OEE approval	
	letter as Attachment 2D).	
		not No.
		owner required for any other use.
	*Refer to 'Guidance on Environmental Liability Risk	onthe
	Environmental Liability Risk Assessment, Residuals	See all
	Management Plans and	outequit
	Financial Provision' EPA, 2006	Non stre
	and consult with OEE.	OWL
	A THE A	<u>۲</u>
2.8	Provide a statement	See attached letter from Key Waste
	(signed by the Proposed	Management Ltd dated 9 May 2013
	Transferee) that "the	
	Proposed Transferee has	
	assumed and accepted all	
	liabilities, requirements	
•	and obligations provided	
	for in or arising under the	
	licence, or revised licence,	•
	regardless of how and in	
	respect of what period,	
	including a period prior to	
	the transfer of the licence	
	or revised licence they	
	may arise."	
<u> </u>	· · · · · ·	

² The amount of financial provision must always be capable of covering the liabilities identified and must have been updated at least within the last twelve months.

Page 7 of 11

2.9	Has the Proposed	No
	Transferee, their parent	
	company or any 'relevant	
-	person' had an application	
- 1	for a licence:	
	(a)Granted?	
	(b)Rejected?	
	(c) Revoked?	
• •	If yes, provide full details.	
2.10	Has the Proposed	No
	Transferee, their parent	
	company or any 'relevant	
	person' been refused by	
	the EPA as a transferee	
	for a licence?	
•	If yes, provide full details.	

5

N. 20N OF

Page 8 of 11

4



Section 2 Attachments: The following documents <u>must</u> be provided to the EPA by the Proposed Transferee to support the licence transfer request. Failure to do so will result in the transfer application being rejected.

Attachment 2A	Provide a copy of the Certified Copy of Certificate of Incorporation.
•	See Attached
Attachment 2B	Provide particulars of Registered Office of the Company (if not included in 2A above).
	KeyWaste Management 36 Rushbrook Avenue, Templeogue, Dublin 6w
Attachment 2C	Where appropriate provide an organisional chart showing company structure, including parent company, subsidiaries and related addresses.
	See Attached
Attachment 2D	Provide a letter of approval from the Office of Enforcement for the financial provision described in Q2.7.
	See reply above to Q2.7
· · ·	Consent of cont

Page 9 of 11



Licence Transfer Application Form Version 5: 08/10/2012

Section 3: To be Completed by Both Parties and the same 4

3.1: Payment of Fee

The licence transfer application can not be processed, unless accompanied by the transfer fee (*please tick*):

Waste Licence Transfer Application €5,000

IPPC Licence Transfer Application €2,000

Consent of const

ê da

Declaration

I/We, the undersigned, hereby apply to the Environmental Protection Agency, as per Section 47 of the Waste Management Acts 1996 to 2012 / Section 94 of the Environmental Protection Agency Acts 1992 to 2012 (delete as appropriate) for the transfer of licence reg. no. WOO45-O1 from Dean Waste Co Limited (In Receivership) to KeyWaste Management Limited.

•	
Signed:	(DAME MOMMEN
Licensee Name:	Dean Waste Co Limited (In Receivership)
Date:	20 May 2013
Company Seal: (where available)	Signed by Promic Homogen As Recempe OF
	As Receiver of OP Denne Wooker & Lit purposed of the (In le concohing)
	tionset
Signed:	AT INSPECTION
Proposed Transferee Name:	ReyWaste Management Limited
Date: Conse	20 May 2013
Company Seal: (where available)	
	SE EN

Page 11 of 11

State and a

T.MILM.

and the states

Chief & Barbark

the stand which a fight of the stand

. وبلغوية الإنهاجية المحو

EPA Export 04-06-2013:23:45:11

Environmental Protection Agency 2 1 MAY 2013

Attachment 1A

Consent for inspection parposes only any other use.

Consent of copying to one required for any other

11. 人名卢尔

150

EPA Export 04-06-2013:23:45:11

Headquarters, P.O. Box 3000, Johnstown Castle Estate County Wexford, Ireland

WASTELIČENCE

Waste Licence
Register Number:45-1Licensee:Dean Waste Company LtdLocation of Facility:Greenhills Rd, Walkinstown, Dublin 12

t g^{an} vie

а 1 с. -

Table of Contents

REASONS FOR THE DECISION	1
PART I: ACTIVITIES LICENSED	. 1
INTERPRETATION	2
PART II: CONDITIONS	5
CONDITION 1 SCOPE	5
CONDITION 2 MANAGEMENT OF THE ACTIVITY	6
CONDITION 3 NOTIFICATION AND RECORD KEEPING	8
	10
CONDITION 5 WASTE ACCEPTANCE AND HANDLING	13
CONDITION 6 ENVIRONMENTAL NUISANCES	16 ,
CONDITION 7 EMISSIONS AND ENVIRONMENTAL IMPACTS	16
CONDITION 8 RESTORATION AND AFTERCARE	18
	19
CONDITION 10 CONTINGENCY ARRANGEMENTS	19
CONDITION 11 CHARGES AND FINANCIAL PROVISIONS	20
SCHEDULE A : Content of the Environmental Management Programme	22
SCHEDULE B : Content of the Annual Environmental Report	23
SCHEDULE C : Recording and Reporting to the Agency	24
SCHEDULE D : Specified Engineering Works	25
SCHEDULE E : Monitoring	25
SCHEDULE F : Emission Limits	28
SCHEDULE G : Waste Acceptance	29

Page No.

Reasons for the Decision

The Agency is satisfied, on the basis of the information available, that subject to compliance with the conditions of this licence any emissions from the activity will comply with and not contravene any of the requirements of Section 40(4) of the Waste Management Act, 1996.

In reaching this decision the Agency has considered the application and supporting documentation received from the applicant, the submission and objection received and the reports of its inspectors.

Part I: Activities Licensed

In pursuance of the powers conferred on it by the Waste Management Act, 1996, the Environmental Protection Agency (the Agency), under Section 40(1) of the said Act, hereby grants this Waste Licence to Dean Waste Company Limited, to carry on the waste activities listed below at Greenview, Greenhills Rd, Walkinstown, Dublin 12 subject to eleven conditions, with the reasons therefor and the associated schedules attached thereto set out in the licence.

Licensed waste disposal activities, in accordance with the Third Schedule of the Waste Management Act, 1996

Class 11:

Blending or mixture prior to submission to any activity efferred to in a preceding paragraph of this Schedule.

This activity is limited to the bulking up of non-hazardous commercial, construction /demolition and industrial wastes prior to their recycling or disposal to landfill.

Class 13:

Storage prior to submission to any activity referred to in a preceding paragraph of this Schedule, other than temporary storage, pending collection, on the premises where the waste concerned is produced of

This activity is limited to the temporary storage of non-hazardous commercial, construction / demolition and industrial waste at the facility for disposal off-site.

Licensed waste recovery activities, in accordance with the Fourth Schedule of the Waste Management Act, 1996

Class 2: Recycling or reclamation of organic substances which are not used as solvents (including composting and other biological transformation processes).

This activity is limited to the recycling of cardboard, paper, timber and plastic wastes at the facility.

Class 3: Recycling ore reclamation of metals and metal compounds.

This activity is limited to the receipt, collection and holding of metal wastes to be sent off site for reprocessing and/or recycling.

Class 4:

Recycling or reclamation of other inorganic materials.

This activity is limited to the receipt, holding of inert construction and demolition wastes to be sent off site for use as an inert fill for land restoration or other use to be agreed in advance with the Agency.

Class 13. Storage of waste intended for submission to any activity referred to in a preceding paragraph of this Schedule, other than temporary storage, pending collection, on the premises where such waste is produced.

This activity is limited to the storage of non-hazardous commercial, construction / demolition and industrial waste received at the facility, prior to recovery at an alternative appropriate facility.

INTERPRETATION

Act	The Waste Management Act, 1996 (No. 10 of 1996).
Adequate lighting	20 lux measured at ground level.
Agency	Environmental Protection Agency
Agreement	Agreement in writing.
Attachment	Any reference to Attachments in this licence refers to attachments submitted as part of the waste licence application.
Application	The application by the licensee for this waste licence, including any other material submitted to the Agency in writing by the licensee between the date of the application and the date of grant of this licence.
Annually	All or part of a period of twelve consecutive months.
Appropriate facility	A waste management facility, duly authorised under relevant law and technically suitable.
BATNEEC	Best Available Technology Not Entailing Excessive Cost as defined in section 5 (2) of the Act.
Bi-annually	All or part of a period of six consecutive months.
Bund	A structure to provide containment for any loss of liquid from a storage tank and associated pipework. The Agency's Landfill Design Manual (draft) sets forth design criteria.
Condition	A condition of this licence. In any case where this licence refers to a numbered condition, the reference shall be taken to mean the condition and any sub-condition therein which the context of the reference requires that reference is made to.
Containment boom	A boom which can contain spillages and prevent these from entering drains or watercourses.
Daily	Consecutive 24 hour periods
Day	A period from 0.00 hours to 2400 hours.
Daytime	8.00 a.m. to 10.00 p.m.
Documentation	Any report, record, result, data, drawing, proposal, interpretation or other document in written or electronic form which is required by this licence
Drawing	Any reference to a drawing or drawing number means a drawing or drawing number contained in the application, unless otherwise specified in this licence.

Environmental Protection Agency WL 45-1

EmissionAs defined in Section 5 (1) of the Act.Emission LimitThose limits, including concentration limits and deposition levels
established in Schedule F.Environmental
PollutionAs defined in Section 5 (1) of the Act.FacilityThat area or areas defined under Condition 1.2Green wasteWaste wood, plant matter and other vegetation.Hazardous WasteAs defined in Section 4 (2) of the Act.

Any reference to an incident in this licence means an incident as defined in Condition 3.1.

Industrial waste

Impulsive Noise

Incident

As defined in British Standard BS 4142, 1990. "Method for rating industrial noise affecting mixed residential and industrial areas".

Keep in a fit state, including such regular inspection, servicing and

Non-Hazardous Waste is any waste which is not a hazardous waste as

Device installed according to the draft European Standard prEN 858

Waste which is readily biodegradable such as vegetable matter, green

A period of three calendar months, the first period of which

(Installations for the separation of light liquids, eg. oil and petrol).

repair as may be necessary to adequately perform its function.

At least 12 times per year, at approximately monthly intervals.

Instruction

Instruction in writing

10.00 p.m. to 8.00 a.m.

defined in the Act.

waste, etc.

A Waste Licence issued in accordance with the Act.

As defined in Section 5 (1) of the Act

Licensee Dean Waste Company Limited.

Liquid Waste Any waste in liquid form and containing less than 2% dry matter

Local Authority South Dublin Council

Maintain

Licence

Monthly

Night-time

Non-hažardous waste

Oil Separator

Putrescible waste

Quarterly

Recovery

As defined in Section 4 (4) of the Act.

Sample(s) Unless the context of this licence indicates to the contrary, samples shall include measurements by electronic instruments

commences on the date of grant of this licence

Sanitary Authority

South Dublin County Council

Environmental Protection Agency WL 45-1

Page 12 of 29

Specified Engineering Works	Those engineering works listed in Schedule D: Specified Engineering Works of this licence.
Submit	Unless the context of this licence indicates otherwise, submit to the Agency in writing for agreement
Trigger Level	A parameter value which when achieved or exceeded requires certain actions to be taken.
Waste	As defined in Section 4(1) of the Act.
Weekly	During all weeks of plant operation, and in the case of emissions, when emissions are taking place, with no more than one measurement in any one week.
Working Day	0000 to 24 hours

1 I.

Environmental Protection Agency WL 45-1

í:

: *.

ij. Angele

 (\cdot, \cdot)

Part II: CONDITIONS

CONDITION 1 SCOPE

1 17

- 1 A 1

. . .

- 1.1. Waste activities at the facility shall be restricted to those listed and described in Part 1: Activities Licensed and required by this licence.
 - 1.2. Waste activities shall be restricted to the area of land outlined in red on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)" Any reference in this licence to "facility" shall mean the area thus outlined in red.
 - Every plan, programme or proposal submitted to the Agency for agreement pursuant to 1.3. any condition of this licence shall include a proposed timescale for its implementation. The Agency may modify or alter any such plan, programme or proposal in so far as it considers such modification or alteration to be necessary. Every plan, programme or proposal shall be carried out within the timescale fixed by the Agency but shall not be undertaken without the agreement of the Agency.
 - This licence is for the purposes of waste licensing under the Waste Management Act 1.4. 1996: only and nothing in this licence shall be construed as negating the licensee's statutory obligations or requirements under any other enactments or regulations.
 - Where the Agency considers that a non-compliance with the Conditions of this licence 1.5. has occurred, it may serve a notice on the licensee specifying:

ر س

- n in the t in the second . . . a) that only those wastes as specified, if any, in the notice are to be accepted at the facility after the date set down in the notice;
- FOLVILO that the licensee shall undertake the works stipulated in the notice, and/or otherwise b) comply with the requirements of the notice as set down therein, within the time-scale contained in the notice; and,

Cor 1

c) that the licensee shall carry out any other requirement specified in the notice

When the notice has been complied with, the licensee shall provide written confirmation that the requirements of the notice have been carried out. No waste, other than that which is stipulated in the notice, shall be accepted at the facility until written confirmation is received from the Agency that the notice is withdrawn.

To clarify the scope of this licence. Reason:

149 11 12

Environmental Protection Agency WL 45-1

EPA Export 04-06-2013:23:45:11

MANAGEMENT OF THE ACTIVITY **CONDITION 2**

2.1 Environmental Management System

The licensee shall within eighteen months from the date of grant of this - 2.1.1 licence, submit to the Agency for its agreement a proposal for a documented Environmental Management System (EMS) for the facility. Following the agreement of the Agency, the licensee shall establish and maintain such a system. The EMS shall be updated on an annual basis with amendments being submitted to the Agency for agreement.

The EMS shall include as a minimum those elements specified in the 2.1.2 Conditions 2.2 to 2.7 below:

Schedule of Environmental Objectives and Targets

2.2.1 The licensee shall, within twelve months from the date of grant of this licence. submit to the Agency for its agreement a Schedule of Objectives and Targets. The objectives should be specific and the targets measurable.

.

The Schedule shall address a five-year period as a minimum and shall be reviewed and submitted annually to the Agency for its agreement.

15e

Environmental Management Programme 2.3

The licensee shall, within twelve months from the date of grant of this licence, 2.3.1 submit to the Agency for its agreement an Environmental Management Programme (EMP), The EMP shall include a time-scale for achieving the Schedule of Objectives and Targets and shall comply with any other guidance issued by the Agency.

The EMP shall include, as a minimum, the information specified in Schedule A: 2.3.2 Content of the Environmental Management Programme. The EMP shall be reviewed and submitted to the Agency for its agreement annually.

 $(1, n, n) = \{1, \dots, n\}, (n, n) = \{1, \dots, n\}$

2.4 Corrective Action

2.2.2

2.2

Within six months of the date of grant of this licence, the licensee shall 2.4.1 establish and maintain written Corrective Action Procedures to ensure that corrective action is taken should specified requirements to this licence not be fulfilled.

Awareness and Training 2.5

2.5.1 Within six months of the date of grant of this licence, the licensee shall establish and maintain Awareness and Training Procedures for identifying training needs and for providing appropriate training, for personnel whose work is related to the licensed facility. Written records of training shall be maintained.

2.6 Management Structure

2.6.1 Within three months from the date of grant of this licence, the licensee shall submit written details of the management structure of the facility for the agreement of the Agency. Any proposed changes in the management structure shall be submitted in writing to the Agency for its agreement. Written details of the management structure shall include the following information:

Environmental Protection Agency WL 45-1

Page 12 of 29

- a) the names of all persons who are to provide the management and supervision of the waste activities authorised by the licence;
- b) a named contact person for communications with the Sanitary Authority;
- c) details of the responsibilities for each individual named under a) above;
- d) details of the relevant experience, competence and qualifications held by each of the persons nominated under a) above; and
- e) contingency arrangements for the absences of the named persons from the facility.
- 2.7 Communications
 - 2.7.1 Within twelve months from the date of grant of this licence, the licensee shall submit for agreement to the Agency a Communications Programme to ensure that members of the public can obtain information concerning the environmental performance of the facility at all reasonable times.
- 2.8 Annual Environmental Report

1

- 2.8.1 The licensee shall submit to the Agency for its agreement, within thirteen months from the date of grant of this licence, and within one month of the end of each year thereafter, an Annual Environmental Report (AER).
- 2.8.2 The AER shall include as a minimum the information specified in Schedule B: Content of Annual Environmental Report and shall be prepared in accordance with any relevant written guidance issued by the Agency.
- 2.9 The licensee shall employ a subably qualified and experienced facility manager who
- 2.10 shall be designated as the person in charge. The facility manager or a suitably qualified and experienced deputy shall be present at all times during the operation of the facility.
- 2.11 The licensee shall ensure that personnel performing specifically assigned tasks shall be qualified on the basis of appropriate education, training and/or experience, as required and shall be aware of the requirements of this licence.

Reason: To make provision for management of the activity on a planned basis having regard to the desirability of ongoing assessment, recording and reporting of matters affecting the environment.

CONDITION 3 NOTIFICATION AND RECORD KEEPING

3.1 The licensee shall make written records of the following incidents:

- a) any nuisance caused by the activity; '
- b) any emission which does not comply with the requirements of this licence;
- c) any trigger level specified in this licence which is attained or exceeded;
- d) any indication that environmental pollution has, or may have, taken place;
- e) any emergency; and

3.2

- The written record shall include all aspects described in section (a) to (e) of Condition 10.6
- Unless otherwise instructed in writing by the Agency, the licensee shall:
 - a) notify the Agency as soon as practicable and in any case not later than 10.00 a.m. the following working day after the occurrence of any incident;
 - b) submit the written record required by this condition to the Agency as soon as practicable and in any case within five working days after the occurrence of any incident; and
 - c) in the event of any incident which relates to discharges to surface water, notify the Eastern Regional Fisheries Board as soon as practicable and in any case not later. than 10.00 a.m. on the following working day after such an incident.
 - d) notify the Local Authority and the Agency as soon as is practicable after the occurrence of any one of the following:
 - any incident with the potential for environmental contamination of surface water or groundwater, or posing a threat to land, or a Sanitary Authority sewer or personnel working in connection with a sewer, or requiring an emergency response by the Local Authority
 - ii) any emission which relates to a discharge to sewer which does not comply with the requirements of this licence.
- 3.3 Should any further actions be taken after the date of written notification, as a result of an incident occurring, the licensee shall forward a written report of those actions to the Agency as soon as practicable and no later than ten days after the initiation of those actions.
- 3.4 Unless otherwise agreed by the Agency, all documentation submitted to the Agency shall:
 - (a) be sent to the Agency's headquarters;
 - (b) comprise one original and three copies;
 - (c) be formatted in accordance with any written instruction or guidance issued by the Agency;
 - (d) include whatever information as is specified in writing by the Agency;

Environmental Protection Agency WL 45-1

Page 12 of 29

- (e) be identified by a unique code, indicate any modification or amendment, and be correctly dated to reflect any such modification or amendment;
- (f) be submitted in accordance to the relevant reporting frequencies specified by this licence; and

(g) in the case of results of any environmental monitoring, be accompanied by a written interpretation setting out their significance.

- Copies of all environmental monitoring data obtained by the licensee which relates to the facility shall be forwarded to the Agency at the frequencies set out in Schedule C: Recording and Reporting to the Agency of this licence.
- All documentation and records required to be made under this licence, shall be retained by the licensee, unless otherwise agreed with the Agency
- The licensee shall provide additional copies of any documentation and records referred to in this licence to the Agency upon written request, within the time specified in writing by the Agency.

The licensee shall keep the following documents at the facility office referred to in Condition 4.5.

- a) the current waste licence relating to the facility;
- b) the current EMS for the facility;

3.5

3.6

3.7

3.8

3.9

- c) the previous year's AER for the facility
- d) all written procedures produced by the licensee which relate to the licensed activities.

The licensee shall maintain a written record, or a record in a format to be agreed with the Agency, for each load of waste arriving at and departing (where applicable) from the facility. The licensee shall record the following:

- a) the date of arrival ordispatch;
- b) the name of the carrier;
- c) the vehicle registration number;
- d) the name of the producer(s)/collector(s) of the waste as appropriate;
- e) a description of the waste;
- f) the quantity of the waste accepted at the facility, recorded in tonnes;
- g) the name of the person checking the load;
- h) where loads or wastes are removed or rejected, details of the date of occurrence, the types of waste and the facility to which they were removed;
 - the quantity of waste leaving the facility, recorded in tonnes;
- j) the destination of the load; and
- k) the total number of containers being stored overnight on a daily basis.
- 1) any other information which might be required from time to time subject to prior agreement with the Agency.
- 3.10 The licensee shall maintain a written record of all complaints relating to the operation of the activity. Each such record shall give details of the following:
 - a) date and time of the complaint;
 - b) the name of the complainant;

Page 12 of 29

- c) details of the nature of the complaint;
- d) actions taken on foot of the complaint and the results of such actions; and,
- e) the response made to each complainant.

Reason : To provide for the notification of incidents, to update information on the activity and to provide for the keeping of records.

CONDITION 4 SITE INFRASTRUCTURE

4.1 The licensee shall establish all infrastructure referred to in this licence or as instructed by the Agency.

4.2 Site Notice Board

- 4.2.1 The licensee shall provide and maintain a Site Notice Board on the facility within three months of the grant of this licence, so that it is legible to persons outside the main entrance to the facility. The minimum dimensions of the identification board shall be 1200 mm by 750 mm.
- 4.2.2 The board shall clearly show:
 - a) the name and telephone number of the facility;
 - b) the normal hours of opening si
 - c) the name, address and telephone number of the licence holder;
 - d) an emergency out of hours contact telephone number;
 - e) the name, address and telephone number of the operator of the facility;
 - f) the licence reference number;
 - g) where and when environmental monitoring information relating to the facility can be obtained.

4.3 Site Security

- 4.3.1 Security walls and gates shall be maintained as described in Attachment D.1.a of the application.
- 4.3.2 The licensee shall remedy any defect in the gates and/or fencing as follows:
 - a) a temporary repair shall be made by the end of the working day; and,
 - b) a repair to the standard of the original gates and/or fencing shall be undertaken within three working days or as otherwise agreed with the Agency.
- 4.3.3 Gates shall be locked shut when the facility is unsupervised.
- المترج المعاويرة المعتمان المناج والمعاجم والمرج والمرج المعاقي والمعاد المعاق والمعاد المتاجع

4.4 Hardstanding

4.4.1 The facility shall contain only hardstanding areas. Any new hardstanding areas at the facility shall be concrete slabs constructed to British Standard 8110 or other standard agreed in advance with the Agency.

Environmental Protection Agency WL 45-1

Site Offices

4.5

- 4.5.1 The licensee shall maintain an office on the facility, at the location shown on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice of 07/07/00" The office shall be constructed and maintained in a manner suitable for the processing and storing of documentation.
- 4.5.2 The licensee shall provide and maintain a working telephone and facsimile machine in the offices specified in Condition 4.5.1.
- 4.6 Waste Inspection/ Waste Quarantine Area
 - 4.6.1 Within six months of the date of grant of this licence, a Waste Inspection Area and a Waste Quarantine Area shall be provided and maintained at a location to be agreed with the Agency.
 - 4.6.2 The licensee shall ensure that this area shall be constructed and maintained in a manner suitable and be of a size appropriate for the inspection of waste and subsequent quarantine if required. The waste inspection area and the waste quarantine area shall be suitably and clearly segregated from each other.

4.7 Weighbridge

- 4.7.1 The licensee shall maintain the weighbridge at the location shown Drawing No.
 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)" unless otherwise agreed with the Agency.
- 4.7.2 Within twelve months of the date of grant of this licence, the accuracy of the weighbridge shall be tested to the manufacturer's specifications and reported to the Agency as part of the Annual Environmental Report. A written record of such tests and any maintenance or remedial work arising from them shall be maintained by the licensee.

4.8 Fuel Storage

4.8.2

4.8.1 Within six months of the date of grant of this licence and unless otherwise agreed with the Agency, the licensee shall provide and maintain a bunded fuel storage area at the facility. The location of the fuel storage area shall be agreed in advance with the Agency. Fuels shall only be stored at the agreed location.

Prior to the construction of the above bunded fuel storage area, fuel shall be held in a temporary bunded storage area at a location to be agreed with the Agency.

- 4.8.3 Subject to Condition 4.8.1, all tank and drum storage areas shall be rendered impervious to the materials stored therein. In addition, tank and drum storage areas shall, as a minimum be bunded, either locally or remotely, to a volume not less than the greater of the following
 - a) 110% of the capacity of the largest tank or drum within the bunded area; or
 - b) 25% of the total volume of substance which could be stored within the bunded area.
- 4.8.4 All drainage from bunded areas shall be diverted for collection and safe disposal.
- 4.8.5 All inlets, outlets, vent pipes, valves and gauges must be within the bunded area.

The integrity and water tightness of the diesel fuel storage bunds and their resistance to penetration by water or other materials stored therein shall be tested and demonstrated by the licensee and shall be reported to the Agency following its installation and prior to its use as a fuel storage area. This testing shall be carried out by the licensee at least once every three years thereafter and reported to the Agency for its agreement in each case a written report on the storage of fuels on site. A written record of all integrity tests and any maintenance or remedial work arising from them shall be maintained by the licensee.

4.8.7 All tanks and containers shall be labelled to clearly indicate their contents.

4.8.8 All tanks and containers shall be secured against unauthorised access.

4.9 Drainage

1.9.5

4.9.7

4.8.6

4.9.1 All surface water run-off from the facility (other than roof water) shall pass through a silt trap and Class II interceptor prior to discharge to the foul sewer.

4.9.2 Within nine months of the date of grant of this licence all roof waters shall be segregated and separately discharged to ground via a gravel filled french drain as per the Building Regulations.

- 4.9.3 The Class II interceptor shall be tested for integrity upon construction and at annual intervals thereafter. A report on the integrity and any maintenance or remedial work arising shall be submitted to the Agency upon construction and at yearly intervals thereafter. The Class d interceptor shall be fitted with a high level alarm.
- 4.9.4 The drainage system, sumps, bunds and oil separators shall be inspected weekly, desludged as necessary and properly maintained at all times. All sludge and drainage from these operations shall be collected for safe disposal. A written record shall be kept of the inspections, desludging, cleaning, disposal of associated waste products, maintenance and performance of the interceptors, sumps, bunds and drains.

All drainage in the waste transfer buildings, truckwash and hardstanding areas shall drain only to the sumps shown on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)". Sump A shall drain the foul sewer network referred to in Condition

4.9.6 Vehicle cleaning facilities, including detergent storage, shall be maintained at the location shown on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)" unless otherwise agreed with the Agency.

The integrity and water tightness of all underground pipes, sumps in the bunkers as shown on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)" and tanks and their resistance to penetration by water or other materials carried or stored therein shall be tested and demonstrated by the licensee and shall be reported to the Agency within twelve months of the date of grant of this licence. This testing shall be carried out by the licensee at least once every five years thereafter and reported to the Agency on each occasion. A written record of all integrity tests and any maintenance or remedial work arising from them shall be maintained by the licensee.

4.10 The licensee shall provide and use adequate lighting during the operation of the facility in hours of darkness.

Environmental Protection Agency WL 45-1

Page 12 of 29.

4.11 Specified Engineering Works

4.11.1 The licensee shall submit written proposals for all Specified Engineering Works, as defined in Schedule D: Specified Engineering Works, to the Agency for its agreement at least two months prior to the intended date of commencement of any such works. No such works shall be carried out without the prior agreement of the Agency.

4.11.2 All specified engineering works shall be supervised by a competent person(s) agreed in advance by the Agency and that person, or persons, shall be present at all times during which relevant works are being undertaken.

4.11.3 Following the completion of all specified engineering works, the licensee shall complete a construction quality assurance validation. The validation report shall be made available to the Agency on request. The report shall include the following information;

a) a description of the works;

b) as-built drawings of the works;

c) - records and results of all tests carried out (including failures);

d) where relevant a drawing and sections showing the location of all samples and tests carried out;

- e) where relevant daily records sheets/diary;
- name(s) of contractor(s)/individual(s) responsible for undertaking the **f)** engineering works;
- g) name(s) of individual(s) responsible for supervision of works and for quality assurance validation of works; ومودعات المأمون بالوياماتية
- h) records of any problems and the remedial works carried out; and
- i) any other information requested in writing by the Agency.

4.12 The licensee shall within six months of grant of this licence carry out a preliminary hydrogeological investigation of the site, incorporating at least one borehole downstream. The scope and programme for the investigation, including report structure and reporting schedule, must be agreed by the Agency prior to implementation. Recommendations arising from the report, as agreed with the Agency, must be implemented within six months of the date of agreement by the Agency.

Reason: To provide for the protection of the environment.

CONDITION 5 WASTE ACCEPTANCE AND HANDLING

5.1:

No hazardous or liquid wastes shall be accepted at the facility.

5.2. Subject to Condition 5.1, only those waste types and quantities listed in Schedule G: Waste Acceptance or listed in Table E.1.3 of the Article 16 Response dated 21st May 1999, shall be accepted at the facility unless the prior agreement of the Agency has been obtained.

5.3. Waste Acceptance Procedures

- 5.3.1. Within six months of the date of grant of this licence, the licensee shall submit to the Agency for its agreement detailed written procedures for the acceptance and handling of all wastes.
- 5.3.2. Each load of waste arriving at the transfer station shall be visually inspected to ensure that it complies with the requirements of this licence prior to unloading in accordance with "Level 3: On-site Verification" outlined in the Agency's Draft Manual on Waste Acceptance.
- 5.3.3. Any wastes deemed to be in contravention of this licence shall be removed for disposal or recovery at an appropriate alternative facility. Such waste shall be stored in the Waste Quarantine Area only.
- 5.3.4. Unacceptable Wastes.
 - 5.3.4.1. Within six months of the date of grant of this licence, the licensee shall submit a written procedure for the management of unacceptable wastes received at the facility for the agreement of the Agency. This procedure will detail unacceptable waste types, handling procedures, waste quarantine procedures, record keeping and levels of staff responsibility.
 - 5.3.4.2. All suspect materials identified by the visual inspection of the waste shall be diverted to the Waste Quarantine Area, or other designated area as agreed in advance by the Agency, for further examination and classification. Materials other than those permitted by this licence shall be submitted to an alternative appropriate facility.
- 5.4. Waste arriving at the facility shall be weighed, documented and directed to the Waste Transfer Building. The waste shall then be deposited on the floor of the Waste Transfer Building for visual inspection. Only following visual inspection and assessment shall the waste be processed.
- 5.5. All waste accepted into the Transfer Station for compaction shall be compacted within 12 hours, except for that waste accepted at the facility on Saturdays which shall be compacted within 48 hours of acceptance at the facility. Waste accepted at the facility on a Saturday preceding a Bank Holiday Monday must be compacted within 72 hours of acceptance.
- 5.6. The compactor and shredder shall be maintained in accordance with the manufacturer's instructions.
- 5.7. The quantity of wastes to be accepted at the facility shall not exceed 300,000 tonnes per annum unless otherwise agreed in advance with the Agency.
- 5.8. Hours of operation.
 - 5.8.1. Waste may be accepted 24 hours a day, 7 days a week.
 - 5.8.2. Waste which is received at night-time, following its acceptance, shall only be deposited on the floor of the Transfer Station. Unless agreed otherwise by the Agency, the transfer of waste from the floor of the Transfer Station (unless it is unacceptable waste) or any other waste handling or processing shall be restricted to daytime hours.

Page 12 of 29

- 5.9. Waste Recovery:
 - 5.9.1. The following shall be achieved by 31/12/2003, unless otherwise agreed with the Agency:

recycling of at least 50% of construction and demolition waste accepted at the facility.

5.9.2. The following shall be achieved by 31/12/2005, unless otherwise agreed with the Agency:

recycling/recovery of at least 35% of the paper and timber waste accepted at the facility.

5.9.3. All waste metal loads accepted at the facility shall be segregated on-site for recovery off-site.

5.10. Storage/Designated Areas

11.2

18 - 14 ¹⁸

- 5.10.1. No waste shall be stored overnight at the facility in other than designated and, where appropriate, secure storage areas. Within six months of the date of grant of this licence, the licensee shall submit a report and drawing illustrating the designated waste storage areas for agreement with the Agency.
- 5.10.2. Putrescible waste shall only be stored in enclosed containers which shall only be stored within the Transfer Building.
- 5.10.3. Full or partially full trailers loaded with waste for disposal or recovery shall be appropriately covered at all times, except while being loaded.

5.10.4. A maximum of four enclosed waste containers (including fully enclosed collection vehicles containing waste and full or partially full trailers of waste) shall be stored on the facility overnight.

- 5.11. Scavenging shall not be permitted at the facility.
- 5.12. No smoking shall be allowed on the facility other than in the office buildings shown on Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)".

5.13. No waste shall be burned or otherwise combusted at the facility.

5.14. At the end of the working day the floor of the Transfer Station Building, the tipping pits, the conveyors, the shredders and the compactors shall be cleared of waste.

5.15. Waste sent off-site for disposal or recovery shall only be conveyed to a waste contractor agreed in writing by the Agency. The ultimate disposal facility for all wastes shall be agreed in advance with the Agency. All wastes removed off-site for disposal or recovery shall be transported from the facility to the consignee in a manner which will not adversely affect the environment.

5.16. Within six months of the date of grant of this licence, the licensee shall submit to the Agency for its approval an Internal Traffic Management Plan which shall provide details of the management of traffic within the red-line boundary as specified in Condition 1.2 of this licence.

Reason: To provide for the acceptance and management of wastes authorised under this waste licence.

Environmental Protection Agency WL 45-1

Page 12 of 29

EPA Export 04-06-2013:23:45:11

CONDITION 6 ENVIRONMENTAL NUISANCES

- 6.1. All waste for disposal, other than inert waste, shall be removed from the facility within seventy-two hours of its arrival at the facility.
- 6.2. The licensee shall, at a minimum of one-week intervals, inspect the facility and its immediate surrounds for nuisances caused by vermin, birds, flies, mud, dust and odours. Written records shall be made of all inspections and any actions taken as a result of these inspections.
- 6.3. The road network in the vicinity of the facility shall be kept free from any debris caused by vehicles entering or leaving the facility. Any such debris or deposited materials shall be removed without delay.
- 6.4. All loose litter accumulated within the facility and its environs shall be removed and appropriately disposed of on a daily basis.
- 6.5. Any waste placed on or in the vicinity of the facility, other than in accordance with the requirements of this licence, shall be removed by the licensee immediately and in any event by 10.00 a.m. of the next working day, after such waste is discovered. Such waste shall be disposed of at an appropriate facility.
- 6.6. The licensee shall ensure that all vehicles delivering waste to and removing waste and materials from the facility are covered and clean and shall not give rise to offensive odours or other nuisance.
- 6.7. Dust Control
 - 6.7.1. In dry weather, site roads and any other areas used by vehicles shall be sprayed with water as and when required to minimise airborne dust nuisance.
 - 6.7.2. Water sprinklers shall be operated in waste handling areas as and when required.
- 6.8. Within three months of the date of grant of this licence, a Vermin Control Plan shall be submitted to the Agency for its agreement.
- 6.9. The licensee shall ensure that vermin, birds, flies, mud, dust and odours do not give rise to nuisance at the facility or the immediate area of the facility. Any method used by the licensee to control any such nuisance shall not cause environmental pollution.

Reason: To provide for the control of nuisance.

CONDITION 7 EMISSIONS AND ENVIRONMENTAL IMPACTS

- 7.1. No specified emission from the facility shall exceed the emission limit values set out in Schedule F: Emission Limits of this licence. There shall be no other emissions of environmental significance.
- 7.2. All treatment/abatement and emission control equipment shall be calibrated and maintained, in accordance with the instructions issued by the manufacturer/supplier or installer. Written records of the calibrations and maintenance shall be made and kept by the licensee.

Environmental Protection Agency WL 45-1

Page 12 of 29

The licensee shall ensure that the activities shall be carried out in a manner such that emissions do not result in significant impairment of, or significant interference with the environment beyond the facility boundary.

Dust

7.3.

7.4.

114

,: [.].

7.4.1. Within seven months of the date of grant of this licence, a Dust Monitoring and Control Plan shall be submitted to the Agency for it agreement. As a minimum, this Plan shall include the installation of sprinklers at the entrance to both waste transfer buildings as shown in Drawing No. 9763.S.01A Revision A Site Plan in the volume entitled "Response to Article 16(1) Notice (November 1999)".

Sec. 16

7^{*}5. Noise

Within three months of the date of grant of this licence, the licensee shall submit for the agreement of the Agency a Noise Minimisation Plan. This Plan shall include a proposal for muffling of the waste shredder and any other equipment as necessary.

7.6. Surface Water

7.5.1.

7.6.1. There shall be no emissions to surface water.

- 7.7. Groundwater
 - 7.7.1. There shall be no direct emissions to groundwater.
- 7.8. Emissions to Sewer:

7.8.1. The following conditions and the emission limit values as specified in Schedule F.1: Emissions to Sewer shall apply for discharges to sewer which shall only be made at the location specified in Schedule F.1. unless otherwise agreed in advance with the Agency and the Sanitary Authority.

7.8.2. No specified discharge or emission to sewer shall exceed the emission limit values set out in Schedule F.1 to this licence, entitled Emissions to Sewer – Limit Values. There shall be no other discharge or emission to sewer of environmental significance.

7.8.3. Monitoring and analytical equipment shall be operated and maintained as necessary so that monitoring accurately reflects the discharge or emission.

7.8.4. No substance shall be present in emissions to sewer in such concentrations as would constitute a danger to sewer maintenance personnel working in the sewerage system, or as would be damaging to the fabric of the sewer, or as would interfere with the biological functioning of a downstream wastewater treatment works.

The licensee shall permit authorised persons of the Agency and the Sanitary Authority to inspect, examine and test, at all reasonable times, any works or apparatus installed in connection with the discharge or emission and to take samples of the discharge or emission.

7.8.6.

7.8.5.

No emission to sewer shall take place which gives rise to any reaction within the sewer or to the liberation of by-products which may be of environmental significance. The licensee shall ensure that the discharge shall not contain dissolved methane, petroleum spirits or organic solvents (including chlorinated organic solvents), at concentrations which would give rise to flammable or explosive vapours in the sewer.

7.8.8. Non-trade effluent wastewater (e.g. firewater, accidental spillage) which occurs on-site shall not be discharged to the sewer without the prior authorisation of the Sanitary Authority. The Agency shall be notified of such an event.

7.8.9. The licensee shall provide and maintain an inspection chamber in a suitable position in connection with each pipe through which the trade effluent is being discharged. Each such inspection chamber or manhole shall be constructed and maintained by the licensee so as to permit the taking of samples of the discharge.

- 7.8.10. The licensee shall submit monitoring results to the Sanitary Authority on an annual basis.
- 7.8.11. The trade effluent shall be screened prior to discharge to remove gross solids and avoid blockages in the sewer.
- 7.8.12. Materials, liquids and/or sludges classified as hazardous waste by the second schedule of the Waste Management Act 1996 may not be discharged to sewer.
- 7.8.13. The Licensee shall provide a means of measuring the volume of trade effluent discharged to the foul sewer.
- 7.8.14. A sampling point shall be constructed, by the licensee, at the point of discharge of the trade effluent from Sump A (designated Sample Point A). This sample point shall be constructed subject to the approval of the sanitary Authority. The sampling point shall be maintained by the Licensee.

Reason: To control emissions from the facility and provide for the protection of the environment.

CONDITION 8 RESTORATION AND AFTERCARE

8.1. A proposal for a Decommissioning and Aftercare Plan for the facility shall be submitted to the Agency within twelve months of the date of grant of this licence. The licensee shall update these schemes when required by the Agency and submit amendments to the Agency for its agreement.

Reason: To provide for decommissioning of the facility and aftercare of the site on which the facility is located.

7.8.7.

CONDITION 9 ENVIRONMENTAL MONITORING

- 9.1. The licensee shall carry out such monitoring and at such locations and frequencies as set out in Schedule E: Monitoring and as specified in the Conditions of this licence.
- 9.2. Noise Monitoring
 - 9.2.1. Noise monitoring as specified in Schedule E.3 shall be carried out on a biannual basis during operational hours. The first such monitoring shall be undertaken within six months of the date of grant of this licence:
- 9.3. The licensee shall provide safe and permanent access to all on-site sampling and monitoring points as required by the Agency.
- 9.4. The licensee shall maintain all sampling and monitoring points, and clearly label and name (including national grid number) all sampling and monitoring locations, subject to the agreement of the landowners in the case of such points which are outside the facility, so that they may be used for representative sampling and monitoring.
- 9.5. Monitoring and analysis equipment shall be operated and maintained in accordance with the manufacturers instructions (if any) so that all monitoring results accurately reflect any emission or discharge or environmental parameter.
- 9.6. The licensee shall amend the frequency, locations, methods and scope of monitoring, sampling, analyses and investigations only upon the written instruction of the Agency and shall provide such information concerning such amendments as may be requested in writing by the Agency. Such alterations shall be carried out within any timescale nominated by the Agency.
- 9.7. A written record shall be kept of the names, qualifications and a summary of relevant experience of all persons who carry out all sampling and monitoring as required by this licence and who carry out the interpretation of the results of such sampling and monitoring, unless otherwise agreed with the Agency.
- 9.8. The licensee shall install on all emission points such sampling points or equipment, including any data-logging or other electronic communication equipment, as may be required by the Agency. All such equipment shall be consistent with the safe operation of all sampling and monitoring systems.

Reason: To ensure compliance with the requirements of other conditions of this licence by provision of a satisfactory system of measurement and monitoring of emissions.

CONDITION 10 CONTINGENCY ARRANGEMENTS

10.1:

The licensee shall, within six months of the date of grant of this licence, submit a written Emergency Response Procedure (ERP) to the Agency for its agreement. The ERP shall address any emergency situations which may originate on the facility and shall include provision for minimising the effects of any emergency on the environment.

10.2. The licensee shall have in storage an adequate supply of containment booms and/or suitable absorbent material to contain and absorb any spillage at the facility. Once used the absorbent material shall be disposed of at an appropriate facility.

Page 12 of 29

- 10.3. All significant spillages occurring at the facility shall be treated as an emergency and immediately cleaned up and dealt with so as to alleviate their effects.
- 10.4. No waste shall be burnt within the boundaries of the facility. A fire at the facility shall be treated as an emergency. Immediate action shall be taken to extinguish it and the appropriate authorities notified.
- 10.5. The licensee shall carry out a risk assessment to determine the requirements at the facility for fire fighting and fire water retention facilities and shall, within six months from the date of grant of this licence submit a report, including recommendations on the risk assessment to the Agency for its agreement. The Chief Fire Officer of South Dublin County Council shall be consulted by the licensee during this assessment.
- 10.6. Unless otherwise notified in writing by the Agency in the event that any monitoring, sampling or observations indicate that an incident has, or may have, taken place, the licensee shall immediately:
 - a) identify the date, time and place of the incident;
 - b) carry out an immediate investigation to identify the nature, source and cause of the incident and any emission;
 - c) isolate the source of the emission;
 - d) evaluate the environmental pollution, if any, caused by the incident;
 - e) identify and execute measures to minimise the emissions/malfunction and the effects thereof;
 - f) provide a proposal to the Agency for its agreement within one month to:
 - (i) identify and put in place measures to avoid reoccurrence of the incident;
 - (ii) identify and put in place any other appropriate remedial action.

Reason: To provide for the protection of the environment.

and

CONDITION 11 CHARGES AND FINANCIAL PROVISIONS

11.1 Agency Charges

11.1.1The licensee shall pay to the Agency an annual contribution of £9,121 (€11,581) or such sum as the Agency from time to time determines, towards the cost of monitoring the activity or otherwise in performing any functions in relation to the activity, as the Agency considers necessary for the performance of its functions under the Waste Management Act, 1996. The licensee shall in 2001 and subsequent years, not later than January 31 of each year, pay to the Agency this amount updated in accordance with changes in the Public Sector Average Earnings Index from the date of the licensee by the Agency. For 2000, the licensee shall pay a pro rata amount from the date of this licence to 31st December 2000. This amount shall be paid to the Agency within one month of the date of grant of this licence.

11.1.2In the event that the frequency or extent of monitoring or other functions carried out by the Agency needs to be increased or decreased the licensee shall contribute such sums as determined by the Agency to defraying its costs.

Environmental Protection Agency WL 45-1

Page 12 of 29

- 11.2 Financial Provision for Closure, Restoration and Aftercare
 - 11.2.1The licensee shall arrange for the completion of a comprehensive and fully costed Environmental Liabilities Risk Assessment for the facility which will address liabilities arising from the carrying on of the activities to which this licence relates. A report on this assessment shall be submitted to the Agency for its agreement within six months of date of grant of this licence.
 - 11.2.2Within nine months of the date of grant of this licence, the licensee shall make a Proposal for Financial Provision to the Agency for its agreement to cover any liabilities incurred by the licensee in carrying on the activities to which this licence relates. Such provision shall be maintained by the licensee unless otherwise agreed by the Agency.
 - 11.2.3The amount of financial provision, held under Condition 11.2.2 shall be reviewed and revised as necessary, but at least annually. Any proposal for such a revision shall be submitted to the Agency for its agreement.
 - 11.2.4The licensee shall within two weeks of purchase, renewal or revision of the financial provision required under Condition 11.2.2, forward to the Agency written proof of such indemnity.

Reason: To provide for adequate financing for monitoring and financial provisions for measures to protect the environment.

Environmental Protection Agency WL 45-1 Page 12 of 29

SCHEDULE A : Content of the Environmental Management Programme

Environmental Management Programme

Details of Operator

Name and Address of Operator and Site. Included should be contact names in respect of persons with managerial responsibility for site operations, including the facility manager. Relevant telephone numbers should also be given. All relevant drawings should be included in the EMP.

Types of Waste Accepted

A detailed description of the types of waste that can be accepted on the site should be given.

Quantity of Wastes Accepted

Details should be given on the annual quantity of waste taken into the site.

Engineering Details

Details of all significant site engineering works should be included. Where applicable the information should cover:

fencing, gates and other security.

- site access roads and secondary site roads
- offices fuel stores etc.
- site infrastructure etc.

Operational Matters

- These should include:
- description of the operations
- measures for the control of environmental misances
- measures for the control of emissions of the control of emissions of the control of emissions of the control of t
- site opening and operating times
- access control
- waste acceptance procedures (including those for customers and drivers)
- procedures for dealing with unacceptable wastes
- equipment to be utilised
- site personnel, including qualifications, duties and responsibilities
- monitoring and maintenance procedures
- trigger levels for emissions
- operational and safety rules (including safety statement)
- emergency procedures

Objectives and Targets

Objectives and targets for improving the environmental performance of the facility shall be detailed. These should include:

- emissions
- resource use
- recycling/recovery of waste

Timescale for achieving the objectives and targets listed in the Schedule of Objectives and Targets Designation of Responsibility for Achieving Targets and Objectives

Other items specified by the Agency

SCHEDULE B : Content of the Annual Environmental Report

Annual Environmental Report Content

Reporting Period.

Waste activities carried out at the facility.

Details of quantities of waste sent off-site for recovery and their destination.

Quantity and Composition of waste received, disposed of and recovered during the reporting period and each previous year and the total amount of waste being held at the facility at the time of the report.

Summary report on emissions

Summary of results and interpretations of environmental monitoring, including a location plan of all monitoring locations along with their respective 12 digit grid references.

Resource and energy consumption summary

Report on development works undertaken during the reporting period, and a timescale for those proposed for the coming year.

Schedule of Environmental Objectives and Targets for the forthcoming year.

Report on the progress towards achievement of the Environmental Objectives and Targets contained in previous year's report.

Full title and a written summary of any procedures developed by the licensee in the year which relates to the facility operation.

Tank, drum, pipeline and bund testing and inspection report.

dicor

Reported Incidents and Complaints summaries.

Review of Nuisance Controls.

Reports on financial provision made under this licence, management and staffing structure of the facility, and a programme for public information.

Destination of all wastes received at the facility (accepted and rejected).

Any other items specified by the Agency.

Environmental Protection Agency WL 45-1

SCHEDULE C : Recording and Reporting to the Agency

Table C.1 Recurring Reports

Report	Reporting Frequency Note1	Report Submission Date
Environmental Management System Updates	Annually	Eighteen months from the date of grant of licence and one month after the end of the year reported on.
Annual Environment Report (AER)	Annually	Thirteen months from the date of grant of licence and one month after the end of each year thereafter.
Record of incidents	As they occur	Within five days of the incident.
Specified Engineering Works reports	As they arise	Prior to the works commencing
Bund, tank and container integrity assessment	Every three years	Six months from the date of grant of licence and one month after end of the three year period being reported on
Underground pipe and tank integrity assessment	5 yearly	Eighteen months from the date of grant of licence and one month after end of the three year period being reported on.
Monitoring of emissions to sewer	Every three months	Ten days after end of the quarter being reported on.
Noise Monitoring	Bi-annually the	Three months from date of grant of licence and one month after the completion of the monitoring thereafter.
Dust Monitoring	1 Quarterly	One month after the completion of the monitoring.
Any other monitoring	As they occur	Within ten days of obtaining results.

Note 1: Unless altered at the request of the Agency

Environmental Protection Agency WL 45-1

Page 12 of 29

SCHEDULE D : Specified Engineering Works

Specified Engineering Works

Extension of Waste Transfer Building and development of waste storage areas.

Additions to site security, walls etc.

Installation of vehicle wash area.

Installation of sumps and interceptors and other drainage controls.

Installation of bunded fuel storage areas.

Installation of increased waste processing capacity.

Dust control measures as agreed with the Agency under Condition 7.4^{Note 1}

Any relocation of key equipment such as the waste shredder. Note 1

Construction of permanent offices.

Any other works notified by the Agency.

Note 1: Not subject to Condition 4.11.3

SCHEDULE E : Monitoring

Monitoring to be carried out as specified below.

E.1: Monitoring of Emissions to Sewer

Monitoring of emissions to sewer shall be from the monitoring location as set out in Table E.1.1

 Table E.1.1
 Sewer Monitoring Location

STATION

Sampling Point ANote 1, SUMP A

Note 1: To be constructed

Environmental Protection Agency WL 45-1

Table E.1.2 Sewer Monitoring Parameters and Frequencies

Parameter	Monitoring Frequency	Sampling Method/Type
Flow to sewer	Quarterly	To be agreed with the Agency
BOD	Quarterly	Grab
COD	Quarterly	Grab
Ammonical Nitrogen	Quarterly	Grab
Suspended Solids	Quarterly	Grab
Sulphates (as SO4)	Quarterly	Grab
Temperature	Quarterly	Grab
рН	Quarterly	Grab
Fats, Oil, Grease	Quarterly	Grab
Detergents (as MBAS)	Quarterly	Grab

E.2: Dust

Dust monitoring locations shall be those as set out in Table E.2.1.

 Table E.2.1
 Dust Monitoring Locations as shown on Figure J.1 "Environmental Monitoring" of the Article 14 Response dated August 1998.

21

	STATION	× ¢
	D1	
	D2 COR	
·	D3	
	D4	

Table E.2.2

2 Dust Monitoring Frequency and Technique

-	Paran	neter (mg/m ²	(day)	Monitoring Frequency	· Analysis:Method/Technique
	Dust	n ingeneration Tringeneration		Quarterly	Standard Method Note 1

Note 1: Standard method VDI2119 (Measurement of Dustfall, Determination of Dustfall using Bergerhoff Instrument (Standard Method) German Engineering Institute). A modification (not included in the standard) where 2- methoxy ethanol may be employed to eliminate interference due to algae growth in the gauge.

E.3: Noise

Noise monitoring locations shall be those as set out in Table E.3.1.

Table E.3.1 Noise Monitoring Locations as shown on Figure J.1 "Environmental Monitoring" of the Article 14 Response dated August 1998.

	STATION	
	N1	
	N2	
	N3	
	N4	
1 1 - 2 - 1	N5	
	N6	
	N7	

Table E.3.2 Noise Monitoring Frequency and Technique

and the second		
 Parameter	Monitoring Frequency	Analysis Method/Technique
L(A) _{Eq} [30 minutes]	For Hie Bi-annually Note 1	Standard ^{Note 2}
L(A) ₁₀ [30 minutes]	Bi-annually	Standard ^{Note 2}
L(A)هو [30 minutes]	Bi-annually	Standard ^{Note 2}
Frequency Analysis(1/3 Cotto Octave band analysis)	Bi-annually	Standard ^{Note 2}

Note 1. Schedule C specifies that the first noise monitoring report must be submitted within 3 months of the date of

grant of the licence. Note 2: "International Standards Organisation. ISO 1996. Acoustics - description and Measurement of Environmental noise. Parts 1, 2 and 3."

SCHEDULE F : Emission Limits

F.1 Emissions to Sewer– Limit Values

Emission Point Reference Number: SUMP A Emission to: Sanitary Authority Sewer on Greenhills Road Volume to be emitted: Maximum 50 m³/day

Parameter	Emission	Limit .	Value
	/Grab Sample (mg/l)	Dally Mean Concentration (mg/l)	Dally Mean: Loading (kg/day)
Biological Oxygen Demand	2500	2000	100
Chemical Oxygen Demand	7500	6000 _e .	300
Ammonical nitrogen	100	NIFO IL	3.5
Suspended Solids	1,000	any any 800	40
Sulphates (as SO4)	500	solly any 800	20.0
pH Temperature	6 - 10 Pulled		
Detergents (as MBAS)	FOT NTROO	100	1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 -
Fats, Oils, Grease	A COP 100	100	5.0

F.2 Dust Deposition Limits: (Measured at the monitoring points indicated in Table E.2.1).

			· · · · · · · · · · · · · · · · · · ·	- T		· •		٠,
A CALL STREET, SALES STREET, SALES		1.000 - 2 - 2011	1.4. Ar a.	184 KT 41 MAL	410 P.1.	12012月1日内午127		10
	13,1973	evel (n	na/m	dav)	HUNDER TO BE	67. PR 971	Sec. 64, 218.	
小生命的 医生化性 化	A PARANTE	ANT A SOL LAND	S. Starte C.		家山方中的	1. 1. 1. 1. 1.	花的花花。 在1	
			350			•		
			000					

Note 1: 30 day composite sample with the results expressed as mg/m²/day. Note 2: This limit to be met within twelve months of the date of grant of this licence.

F.3

Noise Limits: (Measured at the monitoring points indicated in Table E.3.1).

dB(A) (daytime)	dB(A.) (n	ightime) ^{Note}	1 - 5-5 (67) 1 - 5-5 (67) 1 - 5-5 (7)
55	3	45	

Note 1: This limit to be met after six months of the date of grant of this licence.

Environmental Protection Agency WL 45-1

EPA Export 04-06-2013:22

SCHEDULE G : Waste Acceptance

G.1 Waste Acceptance

Table G.1 Waste Categories and Quantities

WASTE TYPE	MAXIMUM TONNES PER
Commercial and Industrial non-hazardous	100,000 ^{Note 1}
Construction and Demolition	200,000 ^{Note 1}
TOTAL	300,000

Note 1: These figures may change subject to the prior agreement of the Agency; however, the total waste to be accepted at the facility shall not exceed 300,000 tonnes per annum.

Sealed by the seal of the Agency on this 18th day of December, 2000.

PRESENT when the seal of the Agency was affixed hereto:

Anne Butler /Authorised Person

Consent of construction purposes only any other i

4 í



Environmental Protection Agency 2 1 MAY 2013

Environmental Protection Agency P.O. Box 3000 Johnstown Castle Co Wexford

9th May 2013

Dear Sirs,

KeyWaste Management Limited assumes and accepts the liability, requirements and obligations provided for in or arising under the licence, regardless of how and in respect of what period, including a period prior to the transfer of the licence, they may arise.

Consent of copyright owner

Regards.

Mark Butler

KeyWaste Management Ltd, Greenview, Greenhills Road, Walkinstown, Dublin 12 Tel +353 1 4299846 Fax +353 1 4080849 Email info@keywaste.ie Web www.keywaste.ie


Consent of copyright owned required for any other is 150.

ENVIRONMENTAL PROTECTION AGENCY 2 1 MAY 2013

EPA Export 04-06-2013:23:45:12

Attachment 1B

Consent for inspection purposes only any other use.



Ŷ

Attachment 1C

Consent of copyright owner required for any other use.

Consent for inspection purposes only any other i

. (* + * ≇*a ∫

.

150



Regional Inspectorate, McCumiskey House,

Cigireacht Réigiúnach, Teach Mhic Chumascaigh,

Richview, Clonskeagh Road, Dublin 14, Ireland

T: +353 1 268 0100

F: +353 1 268 0199 E: info@epa.ie

LoCall: 1890 33 55 99

W: www.epa.ie

Dea-Radharc, Bóthar Cluain Sceach, Baile Átha Cliath 14, Éire

Mr. Padraic Monaghan Receiver KPMG 1 Stokes Place St. Stephens Green Dublin 2

Ref: Dean Waste Co. Ltd (in receivership), W0045-01.

10/05/2013

Our Ref: W0045-01/AK16LM

Approval of Closure & Decommissioning Plan and ELRA Report

Dear Mr. Monaghan,

I refer to the finalised Closure & Decommissioning Plan submitted to the Agency by email on 29/05/2012, the finalised ELRA report submitted to the Agency by email on 25/07/2012, and correspondence from Key Waste Management Ltd. dated 25/10/2012 and received by the Agency on 15/11/2012

I am to advise you that the Closure & Decommissioning Plan, the ELRA report and the associated costings of $\in 531,101$ are approved by the Agency.

Please quote the above reference in any future correspondence relating to this matter. Any queries relating to the above can be directed to Lisa Maher on 01 2680100.

Yours sincerely

M

Ms. Mary Gurrie, Dublin Regional Enforcement Manager Office of Environmental Enforcement

CC: Mr. Mark Butler, Director, KeyWaste Management Ltd., Greenview, Greenhills Road, Walkinstown, Dublin 12.

٢

Consent of copyright owner required for any other use.

ENVIRONMENTAL PROTECTION AGENCY 2 1 MAY 2013

Attachment 2A

.....

Consent of copyright owner required for any other use.

147 ١, ÷... ÷

Consent of copyright owner required for any other use.

* EPA Export 04-06-2013:23:45:12

Duplicate Certificate

Short Certificate of Incorporation of a Company

\$ cor

nty any other us

I hereby certify,

that company number 400662,

KEY WASTE MANAGEMENT LIMITED

was Incorporated under the Companies Acts, 1963 to 2003

as a Limited Company, on

Thursday, the 14th day of April, 2005.

Given under my hand at Dublin, this Tuesday, the 6th day of March, 2012.

for Registrar of Companies

Companies Act, 1963, sec. 370(1)



ī,

psent of copyright owner portugation of the task ζų,

con

. ÷. ,

and said

۶.

e.,

÷, . . ·

,4 3.4 . .

 $\{i, j\}$

. : : :

٩. ٢

Attachment 2C


Consent for inspection purposes only any other use.

EPA Export 04-06-2013:23:45:12

Consent of copyinght owner required for any other is

.

150



KeyWaste Managemen<mark>t L</mark>td

Tatver Properties Ltd

