## **Attachment-7-3-3 Sewer Discharge Consent**

Details of the foul water discharge and consultation with Irish Water are included in the North City Operations Depot Engineering Services Report submitted with the planning application to Fingal County Council. The Engineering Services Report is included at Section 4.8 Reports of this Waste Licence Application.


A pre-connection enquiry was issued to Irish Water on 31/07/17. Discharge figures and associated hydraulic and organic loadings from the staff and visitors of the proposed development are in accordance with the EPA Wastewater Treatment Manual "Treatment Systems for Small Communities, Business, Leisure Centres and Hotels". A wastewater flow rate for full time staff of 60 litres/person/day and 30 BOD<sub>5</sub> grams/person/day is assumed from Table 3 of the above manual. A wastewater flow rate for fleet staff/visitors of 20 litres/person/day and 15 BOD<sub>5</sub> grams/person/day is also assumed.

Based on a desktop study, preliminary figures for effluent from the road sweepers and gully trucks were calculated. These figures were then issued to Irish Water as part of the pre-connection enquiry. A copy of these calculations is included in Appendix A. Irish Water concluded that "based upon the details you have provided with your pre-connection enquiry and on the capacity currently available as assessed by Irish Water, we wish to advise you that subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network can be facilitated". A copy of this letter from Irish Water is included Appendix Based on the capacity currently available as

Since the initial consultation with Irish Water, data became available through testing of the effluent from similar sites which has resulted in more accurate flows and hydraulic and organic loadings from the trucks. Based on these new figures, the loading to the public system has been reduced when compared to the original figures. A copy of these calculations is also included in Appendix A.

## Appendix A – Foul Water Discharge

Consent of copyright owner required for any other use.



A TABL						
TOBIN Patrick J. Tobin & Co. L.	16.					
1 80 80 80 80 80 80 80 80 80 80 80 80 80					Checked Ref No:	PC 10243
	(	CALCULATION SHEET			Sheet No:	10243
PROJECT:	Ballymun Depot				Designer:	cs
ELEMENT:	Foul Water Discharg	ge Loading			Date:	19.09.201
File location:	\\FSERVER4-DUB\\Tobin\\Projects\\10243 - Ballymun Depot, DCC North Operation\\05					
This Element:	Foul Water Discharge	e Loading				
Sanitary Wastewa	<u>ter</u>					
Applying BS EN 75 Design Population						
	Site	Max. No. Fleet Staff + Visitors	Max. No. Full time Staff			
	Offices + Workshops	510.0 persons	181.0 persons			
				1		
			Max. No. Small			
	Site	Max. No. Large Trucks (decanted once a week)	Trucks (decanted once a week)			
	Road Sweepers	8.0 large sweepers	6.0 small sweepers			
		Full time Staff	60.0 l/person/day	-		
		Fleet Staff + Visitors	20.0 l/person/day	စ်.		
		Large Road Sweeper	340,000 l/day	per large swee	per	
		Waste Material Small Road Sweeper	\$70,000 l/day	per small swee	per	
		Waste Material	spired .	l'		
Average Flow C	Office and Workshop	DWF 100 of	0.244 l/sec	or	21.060 m³/d	1
		oect wife				
	Flow Offices and rkshops	6*DWF	1.463 l/sec	or	126.360 m³/d	
Average Flow	/ Road Sweepers	DWF CO	0.043 l/sec	or	3.740 m³/d	
Peak Design Fl	ow Road Sweepers	6*DWE	0.260 l/sec	or	22.440 m³/d	
	e Flow Site	DWF	0.287 l/sec	or	24.800 m³/d	
		6*DWF	1.722 l/sec	or	148.800 m³/d	
Peak Desig	n Flow for Site					
Colebrook-White F	Formula					
	0-	1 722 1/202	Bino Dio Ø –	225 00 mm	1	Ī
	Q =	1.722 l/sec	Pipe Dia. Ø =	225.00 mm	]	
	ks =	1.50 mm	Gradient =	1 in 200.0		
	Kinematic viscosity	1.141x10^-6 m²/sec	Q =	32.197 l/sec	<u>ок</u>	
	Self Cleansing Vel.	0.750 m/sec	v =	0.810 m/sec	<u>ок</u>	
			•			
BOD₅	Full time Staff BOD <sub>5</sub>	30.0 g/person/day	Thes	e are the	most	
	Fleet Staff Vissitors	15.0 g/person/day		nt foul lo		
	Large RS BOD <sub>5</sub> Small RS BOD <sub>5</sub>	93.5 g/sweeper/day	-		•	
	Total BOD <sub>5</sub>	46.8 g/sweeper/day 14.11 kg/day	calcu	lations th	nat now	
		Tring/day	supe	rsede the	e ones ser	nt
	PE	235	1 .			
Summary			to Irish Water. Please see Section 4 of report			
Canimal y	l l l l l l l l l l l l l l l l l l l				•	
	Use 225mmØ min. pi	se 225mmØ min. pipe size if using gravity sewers for furth			ails	

## Appendix B – Irish Water Correspondence

Consent of copyright owner required for any other use.

Letter Ref: CDSCOF2 - CDSCOF5

Craig Scully
Tobin Engineers
Block 10-4,
Blanchardstown Corporate Park,
Dublin 15 D15X98N

UISCE EIREANN : IRISH WATER Uisce Éireann

Bosca OP 6000 Baile Átha Cliath 1 Éire

Irish Water PO Box 6000 Dublin 1 Ireland

T: +353 1 89 25000 F: +353 1 89 25001 www.water.ie

09 October 2017

Dear Sir/Madam,

Re: 1147376321 pre-connection enquiry - Subject to contract | Contract denied Connection for non-domestic premises at Saint Margaret's Road, Ballymun, Dublin 11

Irish Water has reviewed your pre-connection enquiry in relation to
water and wastewater connections at Saint Margaret's Road, Ballymun, Dublin 11
Based upon the details you have provided with your pre-connection enquiry and on the capacity currently available as assessed by Irish Water, we wish to advise you that, subject to a valid connection agreement being put in place, your proposed connection to the Irish Water network can be facilitated.

There is an existing 800mm HL watermain along south edge of the site. New connections for water and wastewater to the existing network are feasible subject to required diversion of the watermain being assessed as feasible.

Before completing the design of services infrastructure at the Premises (including diversion proposals), and prior to submitting any planning application, you are advised to contact Irish Water. The design has to be in accordance with published Irish Water Code of Practice and Standard Details (for water and wastewater)

You are advised that this correspondence does not constitute an offer in whole or in part to provide a connection to any Irish Water infrastructure and is provided subject to a connection agreement being signed at a later date.

A connection agreement can be applied for by completing the connection application form available at **www.water.ie/connections**. Irish Water's current charges for water and wastewater connections are set out in the Water Charges Plan as approved by the Commission for Energy Regulation.

If you have any further questions, please contact Waxing Byrne from the design team on 01 8925991 or email mzbyrne@water.ie. For further information, vist www.water.ie/connections

Date Received

1 2 OCT 2017

Yours sincerely,

## Maria O'Dwyer Connections and Developer Services

Stillerhöir? / Directors: Viches VcNicholas (Charman), Brenden Wurphy, Wichasi O'Sultivan, Jerry Grant, Cathal Marley
Offig Childrolithe / Registered Office: Teach Colvill, 24-26 Stille Shalbdid, Bale Atha Clash 1, D01 NP86 / Colvill House, 24-25 Talbot Street, Dublin 1, D01 NP86 is cuideachte ghniomhalochte einmnithe atli feel theorems sceineanne é Usice Breann / Insh Water is a designated activity complany, Smited by shares,
Ulimbie Childrolithe in Brines / Registered in Ireland No.: 530262

Consent of copyright owner required for any other use.