




CONSULTANTS IN ENGINEERING,
ENVIRONMENTAL SCIENCE & PLANNING

APPENDIX 2

Causeway Geotechnical Reports

*For inspection purposes only.
Consent of copyright owner required for any other use.*





CAUSEWAY
— GEOTECH

Historical Landfills in North Kerry - Ahascra

Client: Kerry County Council

Client's Representative: Feehily Timoney

Report No.: 18-1068b

Date: September 2019

Status: Final for Issue

For inspection purposes only.
Consent of copyright owner required for any other use.

CONTENTS

Document Control Sheet

Note on: Methods of describing soils and rocks & abbreviations used on exploratory hole logs




1	AUTHORITY.....	4
2	SCOPE.....	4
3	DESCRIPTION OF SITE	4
4	SITE OPERATIONS	5
	4.1 Summary of site works.....	5
	4.2 Boreholes.....	5
	4.3 Standpipe installations.....	5
	4.4 Trial Pits.....	5
	4.5 Surveying.....	6
5	LABORATORY WORK.....	6
	5.1 Geotechnical laboratory testing of soils	6
	5.2 Environmental laboratory testing of soils.....	6
6	GROUND CONDITIONS	7
	6.1 General geology of the area	7
	6.2 Ground types encountered during investigation of the site.....	7
	6.3 Groundwater.....	7
7	REFERENCES	8

For inspection purposes only.
Consent of copyright owner required for any other use.

APPENDICES

Appendix A	Site and exploratory hole location plans
Appendix B	Borehole logs
Appendix C	Trial pit logs
Appendix D	Trial pit photographs
Appendix E	Geotechnical laboratory test results
Appendix F	Environmental laboratory test results

Document Control Sheet

Report No.:		18-1068b			
Project Title:		Historical Landfills in North Kerry - Ahascra			
Client:		Kerry County Council			
Client's Representative:		Fehily Timoney			
Revision:	A00	Status:	Final for Issue	Issue Date:	23 September 2019
Prepared by:		Reviewed by:		Approved by:	
 Sean Ross BSc MSc		 Colm Hurley BSc FGS		 Darren O'Mahony BSc MSc MIEI EurGeol PGeo	

The works were conducted in accordance with:

British Standards Institute (2015) BS 5930:2015, Code of practice for site investigations.

BS EN 1997-2: 2007: Eurocode 7 - Geotechnical design - Part 2 Ground investigation and testing.

Geotechnical Society of Ireland (2016), Specification & Related Documents for Ground Investigation in Ireland

Laboratory testing was conducted in accordance with:

British Standards Institute BS 1377:1990 parts 2, 4, 5, 7 and 9

METHODS OF DESCRIBING SOILS AND ROCKS

Soil and rock descriptions are based on the guidance in BS5930:2015, The Code of Practice for Site Investigation.

Abbreviations used on exploratory hole logs	
U	Nominal 100mm diameter undisturbed open tube sample (thick walled sampler)
UT	Nominal 100mm diameter undisturbed open tube sample (thin walled sampler)
P	Nominal 100mm diameter undisturbed piston sample
B	Bulk disturbed sample
LB	Large bulk disturbed sample
D	Small disturbed sample
C	Core sub-sample (displayed in the Field Records column on the logs)
L	Liner sample from dynamic sampled borehole
W	Water sample
ES / EW	Soil sample for environmental testing / Water sample for environmental testing
SPT (s)	Standard penetration test using a split spoon sampler (small disturbed sample obtained)
SPT (c)	Standard penetration test using 60 degree solid cone
x,x/x,x,x,x	Blows per increment during the standard penetration test. The initial two values relate to the seating drive (150mm) and the remaining four to the 75mm increments of the test length. The length achieved is stated (mm) for any test increment less than 75mm
N=X	SPT blow count 'N' given by the summation of the blows 'X' required to drive the full test length (300mm)
N=X/Z	Incomplete standard penetration test where the full test length was not achieved. The blows 'X' represent the total blows for the given test length 'Z' (mm)
V VR	Shear vane test (borehole) Hand vane test (trial pit) Shear strength stated in kPa V: undisturbed vane shear strength VR: remoulded vane shear strength
dd/mm/yy: 1.0 dd/mm/yy: dry	Date & water level at the borehole depth at the end of shift and the start of the following shift
▽	Water strike: initial depth of strike
▼	Water strike: depth water rose to
Abbreviations relating to rock core – reference Clause 36.4.4 of BS 5930: 2015	
TCR (%)	Total Core Recovery: Ratio of rock/soil core recovered (both solid and non-intact) to the total length of core run.
SCR (%)	Solid Core Recovery: Ratio of solid core to the total length of core run. Solid core has a full diameter, uninterrupted by natural discontinuities, but not necessarily a full circumference and is measured along the core axis between natural fractures.
RQD (%)	Rock Quality Designation: Ratio of total length of solid core pieces greater than 100mm to the total length of core run.
FI	Fracture Index: Number of natural discontinuities per metre over an indicated length of core of similar intensity of fracturing.
NI	Non Intact: Used where the rock material was recovered fragmented, for example as fine to coarse gravel size particles.
AZCL	Assessed zone of core loss: The estimated depth range where core was not recovered.
DIF	Drilling induced fracture: A fracture of non-geological origin brought about by the rock coring.
(xxx/xxx/xxx)	Spacing between discontinuities (minimum/average/maximum).

Historical Landfills in North Kerry - Ahascra

1 AUTHORITY

On the instructions of Fehily Timoney Consulting Engineers, (“the Client’s Representative”), acting on the behalf of Kerry County Council (“the Client”), a ground investigation was undertaken at the above location to allow the geotechnical and environmental assessment of the historical landfill present on site. The information will input into the Tier 2 and 3 reports being compiled by the Client’s Representative.

This report details the work carried out both on site and in the geotechnical and chemical testing laboratories; it contains a description of the site and the works undertaken, the exploratory hole logs and the laboratory test results.

All information given in this report is based upon the ground conditions encountered during the site investigation works, and on the results of the laboratory and field tests performed. However, there may be conditions at the site that have not been taken into account, such as unpredictable soil strata, contaminant concentrations, and water conditions between or below exploratory holes. It should be noted that groundwater levels usually vary due to seasonal and/or other effects and may at times differ to those recorded during the investigation. No responsibility can be taken for conditions not encountered through the scope of work commissioned, for example between exploratory hole points, or beneath the termination depths achieved.

This report was prepared by Causeway Geotech Ltd for the use of the Client and the Client’s Representative in response to a particular set of instructions. Any other parties using the information contained in this report do so at their own risk and any duty of care to those parties is excluded.

2 SCOPE

The extent of the investigation, as instructed by the Client’s Representative, included boreholes, trial pits, soil sampling, environmental sampling, laboratory testing, and the preparation of a factual report on the findings.

3 DESCRIPTION OF SITE

As shown on the site location plan in Appendix A, the works were conducted on the site located halfway between Ballybunion and Listowel, Co. Kerry, in the townland of Ahascra. The site is adjacent to Kiltan Bog and 1.5km north east of the River Feale. The site is surrounded on all sides by agricultural lands.

4 SITE OPERATIONS

4.1 Summary of site works

Site operations, which were conducted between 30th May and 20th June 2019, comprised:

- two boreholes rotary drilling methods;
- two standpipe installations; and
- five machine dug trial pits.

The exploratory holes and in-situ tests were located as instructed by the Client's Representative, as shown on the exploratory hole location plan in Appendix A.

4.2 Boreholes

Two boreholes (BH01-BH02) were put to their completion by rotary drilling techniques only. The boreholes were completed using a Hanjin 8D tracked rotary drilling rig.

Symmetrix-cased full hole rotary percussive drilling techniques were employed to advance the boreholes to scheduled depths.

Appendix B presents the borehole logs.

4.3 Standpipe installations

A groundwater monitoring standpipe was installed in BH01 and BH02.

Details of the installations, including the depth range of the response zone, are provided in Appendix B on the individual borehole logs.

4.4 Trial Pits

Four trial pits (TP01-TP02, TP04-TP05) were excavated using a JCB 3CX excavator fitted with a 600mm wide bucket, to a maximum depth of 2.60m.

Environmental samples were taken at various depths of in each trial pit.

Disturbed (bulk bag) samples were taken at standard depth intervals and at change of strata.

Groundwater was not noted in any of the trial pits. The stability of the trial pit walls was noted on completion.

Appendix C presents the trial pit logs with photographs of the pits and arising provided in Appendix D.

4.5 Surveying

The as-built exploratory hole positions were surveyed following completion of site operations by a Site Engineer from Causeway Geotech. Surveying was carried out using a Trimble R6 GPS system employing VRS and real time kinetic (RTK) techniques.

The plan coordinates (Irish National Grid) and ground elevation (mOD Malin) at each location are recorded on the individual exploratory hole logs. The exploratory hole plan presented in Appendix A shows these as-built positions.

5 LABORATORY WORK

Upon their receipt in the laboratory, all disturbed samples were carefully examined and accurately described, and their descriptions incorporated into the borehole logs.

5.1 Geotechnical laboratory testing of soils

Laboratory testing of soils comprised:

- **permeability testing:** permeability by triaxial compression

Laboratory testing of soils samples was carried out in accordance with British Standards Institute: *BS 1377, Methods of test for soils for civil engineering purposes; Part 1 (2016), and Parts 2-9 (1990)*.

The test results are presented in Appendix E.

5.2 Environmental laboratory testing of soils

Environmental testing, as specified by the Client's Representative was conducted on selected environmental soil samples by Chemtest at its laboratory in Newmarket, Suffolk.

Testing was carried out according to Engineer's Ireland Suite E which comprises a single stage waste acceptance criteria (WAC) test.

Results of environmental laboratory testing are presented in Appendix F.

6 GROUND CONDITIONS

6.1 General geology of the area

Published geological mapping indicate the superficial deposits underlying the site comprises peat and glacial till. These deposits are underlain by Waulsortian limestones.

6.2 Ground types encountered during investigation of the site

A summary of the ground types encountered in the exploratory holes is listed below, in approximate stratigraphic order:

- **Topsoil:** encountered across the site with a thickness range of 100 – 300mm.
- **Made Ground (fill):** reworked sandy gravelly clay fill with various amounts of landfill waste encountered at all trial pit locations to a depth of 2.60m in TP03.
- **Recent deposits (peat):** BH01 and BH02 encountered peat to a maximum depth of 3.20m.
- **Glacial Till:** sandy gravelly clay, frequently with low cobble content, typically firm or stiff in upper horizons, becoming very stiff with increasing depth.
- **Bedrock (Limestone):** Rockhead was encountered at depths of 7.00mbgl and 2.00mbgl in BH01 and BH02 respectively.

6.3 Groundwater

Details of the individual groundwater strikes, along with any relative changes in levels as works proceeded, are presented on the exploratory hole logs for each location.

Groundwater was encountered during drilling as water strikes as shown in Table 1 below.

Table 1 Groundwater strikes encountered during the ground investigation

GI Ref.	Water level (mbgl)	Comments
BH01	7.00	
BH02	6.90	

It should be noted that any further groundwater strikes within bedrock may have been masked by the fluid used as the drilling flush medium.

Groundwater was not noted during excavation of the trial pits.

7 REFERENCES

Geotechnical Society of Ireland (2016), Specification & Related Documents for Ground Investigation in Ireland

IS EN 1997-2: 2007: Eurocode 7 - Geotechnical design - Part 2 Ground investigation and testing.

BS 1377: 1990: Methods of test for soils for civil engineering purposes. British Standards Institution.

BS 5930: 2015: Code of practice for ground investigations. British Standards Institution.

BS EN 1997-2: 2007: Eurocode 7 - Geotechnical design - Part 2 Ground investigation and testing. British Standards Institution.

BS EN ISO 14688-1:2018: Geotechnical investigation and testing. Identification and classification of soil. Part 1 Identification and description.

BS EN ISO 14688-2:2018: Geotechnical investigation and testing. Identification and classification of soil. Part 2 Principles for a classification.

BS EN ISO 14689-1:2018: Geotechnical investigation and testing. Identification and classification of rock. Identification and description

BS EN ISO 22282-2: 2012: Geotechnical investigation and testing. Geohydraulic testing – Part 2: Water permeability tests in a borehole using open systems.

For inspection purposes only
Consent of copyright owner required for any other use



CAUSEWAY
— GEOTECH

APPENDIX A
SITE AND EXPLORATORY HOLE LOCATION PLANS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



Project No.: 18-1068b

Client: Kerry County Council

Project Name: Historical Landfills in North Kerry - Ahascra

Client's Representative: Fehily Timoney

Legend Key




*For inspection purposes only.
Consent of copyright owner required for any other use.*

Site Location

Title:
Site Location Plan

Last Revised:
16/08/2019

Scale:
1:20000



Microsoft product screen shot(s) reprinted with permission from Microsoft Corporation





Project No.: 18-1068b


Client: Kerry County Council

Project Name: Historical Landfills in North Kerry - Ahascra

Client's Representative: Fehily Timoney

Legend Key

- Locations By Type - RO
- Locations By Type - TP



Title:
Exploratory Hole Location Plan

Last Revised:
16/08/2019

Scale:
1:2500



CAUSEWAY
—
GEOTECH

APPENDIX B
BOREHOLE LOGS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Borehole No.: BH01
Coordinates: 91029.70 E	Client: Kerry County Council	Sheet 1 of 1
Method Rotary Drilling	Plant Used Hanjin 8D	Top 0.00
Base 8.50	Client's Representative: Fehily Timoney	Scale: 1:50
Ground Level: 8.56 mOD	Dates: 20/06/2019 - 20/06/2019	Driller: KW
		Logger: PF

Depth (m)	Sample / Tests	Casing Depth (m)	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water	Backfill
						(0.30)		TOPSOIL. (Driller's description)		
						0.30		PEAT. (Driller's description)		
						(2.90)				
						3.20		Grey sandy gravelly CLAY. (Driller's description)		
						(3.80)				
				Water strike at 7.00m		7.00		Grey LIMESTONE. (Driller's description)		
						(1.50)				
						8.50		End of Borehole at 8.50m		
						0.06				

For inspection purposes only.
Consent of copyright owner required for any other use.

Remarks Terminated at scheduled depth.	Water Strikes				Chiselling Details		
	Struck at (m)	Casing to (m)	Time (min)	Rose to (m)	From (m)	To (m)	Time (hr:mm)
	7.00	7.00					
	Water Added		Casing Details				
From (m)	To (m)	To (m)	Diam (mm)				
		8.50	200				



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Borehole No.: BH02
Coordinates: 91185.17 E	Client: Kerry County Council	Sheet 1 of 1
Method Rotary Drilling	Plant Used Hanjin 8D	Top 0.00
Base 8.50	Client's Representative: Fehily Timoney	Scale: 1:50
Ground Level: 9.65 mOD	Dates: 20/06/2019 - 20/06/2019	Driller: KW
		Logger: PF

Depth (m)	Sample / Tests	Casing Depth (m)	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water	Backfill
						(0.30) 0.30		TOPSOIL. (Driller's description)		
						(1.70)		PEAT. (Driller's description)		
						7.65 2.00		Grey LIMESTONE. (Driller's description)		
						(6.90)				
				Water strike at 6.90m		1.15 8.50		End of Borehole at 8.50m		

Consent of copyright owner required for any other use.

Remarks Terminated at scheduled depth.	Water Strikes				Chiselling Details		
	Struck at (m)	Casing to (m)	Time (min)	Rose to (m)	From (m)	To (m)	Time (hr:mm)
	6.90	6.90					
	Water Added		Casing Details				
From (m)	To (m)	To (m)	Diam (mm)				
		8.50	200				



CAUSEWAY
—
GEOTECH

APPENDIX C

TRIAL PIT PHOTOGRAPHS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Trial Pit No.: TP01
Co-ordinates: 91069.63 E	Client: Kerry County Council	Sheet 1 of 1
Method: Trial Pitting	Client's Representative: Fehily Timoney	Scale: 1:25
Plant: 3T Tracked Excavator	Ground Level: 11.82 mOD	Date: 30/05/2019
		Logger: PF

Depth (m)	Sample / Tests	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water
0.10	B3		11.67	(0.15) 0.15		TOPSOIL: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content. Sand is fine to coarse	
0.80	ES1			(1.75)		MADE GROUND: Firm dark brownish black slightly sandy slightly gravelly silty CLAY with low cobble content and alot of rubbish including, block, plastic bags, wire rope, engine part, glass bottles and fragments, plastic bottles, glass jars, clothing. Sand is fine to coarse. Gravel is angular to subrounded fine to coarse of limestone. Cobbles are subrounded of limestone.	0.5 1.0 1.5
1.70	ES2		9.92	1.90		End of trial pit at 1.90m	2.0 2.5 3.0 3.5 4.0 4.5

For inspection purposes only.
Consent of copyright owner required for any other use.

Remarks No groundwater encountered. Terminated due to >1.50m landfill material present.	Water Strikes:		Stability:
	Struck at (m):	Remarks:	Slightly unstable
			Width: 0.70
		Length: 2.90	



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Trial Pit No.: TP02
Co-ordinates: 91124.40 E	Client: Kerry County Council	Sheet 1 of 1
Method: Trial Pitting	Client's Representative: Fehily Timoney	Scale: 1:25
Plant: 3T Tracked Excavator	Ground Level: 11.92 mOD	Date: 30/05/2019
		Logger: PF

Depth (m)	Sample / Tests	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water
0.80	ES1		11.82	(0.10) 0.10		TOPSOIL: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content. Sand is fine to coarse. Gravel is angular to subrounded fine to coarse of limestone. Cobbles are subrounded of limestone.	
1.00	B3			(1.60)		MADE GROUND: Firm dark brown to black slightly sandy slightly gravelly silty CLAY with low cobble and boulder content, plastic bags, glass, plastic bottles, wood and cloth. Sand is fine to coarse, Gravel is subangular to subrounded fine to coarse of limestone. Cobbles and boulders are subrounded of mixed lithologies.	
1.60	ES2		10.22	1.70		End of trial pit at 1.70m	

For inspection purposes only.
Consent of copyright owner required for any other use.

Remarks No groundwater encountered. Terminated due to >1.50m landfill material present.	Water Strikes:		Stability: Stable
	Struck at (m):	Remarks:	
			Width: 0.80 Length: 2.20



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Trial Pit No.: TP03
Co-ordinates: 91178.84 E	Client: Kerry County Council	Sheet 1 of 1
Method: Trial Pitting	Client's Representative: Fehily Timoney	Scale: 1:25
Plant: 3T Tracked Excavator	Ground Level: 12.17 mOD	Date: 30/05/2019
		Logger: PF

Depth (m)	Sample / Tests	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water
1.10	ES1		12.07	(0.10) 0.10	[Pattern]	<p>TOPSOIL: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content. Sand is fine to coarse. Gravel is angular to subangular fine to coarse of limestone.</p> <p>MADE GROUND: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content. Sand is fine to coarse. Gravel is angular to subangular fine to coarse of limestone.</p>	
2.10	ES2		10.87	1.30	[Pattern]	<p>MADE GROUND: Firm very dark greyish black slightly sandy slightly gravelly silty CLAY with low cobble and boulder content, bits of plastic bags, glass bottles and fragments of cloth, wood and concrete. Gravel is subangular to subrounded fine to coarse of limestone. Cobbles are of limestone, sandstone and concrete. Boulders are of concrete and sandstone.</p>	
			9.57	2.60		End of trial pit at 2.60m	

Consent of copyright owner required for any other use.

Remarks No groundwater encountered. Terminated due to >1.50m landfill material present.	Water Strikes:		Stability: Stable
	Struck at (m):	Remarks:	
			Width: 0.80 Length: 2.80



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Trial Pit No.: TP04
Co-ordinates: 91088.86 E	Client: Kerry County Council	Sheet 1 of 1
Method: Trial Pitting	Client's Representative: Fehily Timoney	Scale: 1:25
Plant: 3T Tracked Excavator	Ground Level: 11.61 mOD	Date: 30/05/2019
		Logger: PF

Depth (m)	Sample / Tests	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water
			11.51	(0.10) 0.10		TOPSOIL	
0.50	B3			(0.60)		MADE GROUND: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content. Sand is fine to coarse. Gravel is subangular to subrounded fine to coarse of limestone. Cobbles are subrounded of limestone.	
1.20	ES1		10.91	0.70		MADE GROUND: Firm dark brownish black slightly sandy slightly gravelly silty CLAY with low cobble content and rubbish including plastic bags, glass, wood, saw dust, plastic and glass bottles. Sand is fine to coarse. Gravel is subangular to subrounded fine to coarse of limestone. Cobbles are subrounded of mixed lithologies.	
				(1.50)			
2.20	ES2		9.41	2.20		End of trial pit at 2.20m	

For inspection purposes only.
Consent of copyright owner required for any other use.

Remarks No groundwater encountered. Terminated due to >1.50m landfill material present.	Water Strikes:		Stability: Stable
	Struck at (m):	Remarks:	
			Width: 0.70 Length: 2.90



CAUSEWAY
GEOTECH

Project No.: 18-1068b	Project Name: Historical Landfills in North Kerry - Ahascra	Trial Pit No.: TP05
Co-ordinates: 91159.29 E	Client: Kerry County Council	Sheet 1 of 1
Method: Trial Pitting	Client's Representative: Fehily Timoney	Scale: 1:25
Plant: 3T Tracked Excavator	Ground Level: 11.23 mOD	Date: 30/05/2019
		Logger: PF

Depth (m)	Sample / Tests	Field Records	Level (mOD)	Depth (m) (Thickness)	Legend	Description	Water
0.20	B3		11.13	(0.10) 0.10	[Hatched Pattern]	TOPSOIL	
			10.93	(0.20) 0.30	[Cross-hatched Pattern]	MADE GROUND: Firm brown slightly sandy slightly gravelly silty CLAY with low cobble content and small amount of white plastic. Sand is fine to coarse. Gravel is subangular to subrounded fine to coarse of limestone. Cobbles are subrounded of limestone.	
1.00	ES1			(1.70)	[Cross-hatched Pattern]	MADE GROUND: Firm orangish brown, dark brown and black slightly sandy slightly gravelly silty CLAY with rubbish including plastic bags, cloth, glass and plastic bottles and wood. Sand is fine to coarse. Gravel is subangular to subrounded fine to coarse of mixed lithologies.	
1.80	ES2		9.23	2.00	[Cross-hatched Pattern]	End of trial pit at 2.00m	

For inspection purposes only.
Consent of copyright owner required for any other use.

Remarks No groundwater encountered. Terminated due to >1.50m landfill material present.	Water Strikes:		Stability:
	Struck at (m):	Remarks:	Slightly unstable
			Width: 1.10
			Length: 2.60



CAUSEWAY
— GEOTECH

APPENDIX D
TRIAL PIT PHOTOGRAPHS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



TP01 - NE Face



TP01 - SE Face



TP01 – SW Face



TP01 – NW Face



TP01 - Base



TP01 - Spoil heap



TP01 – Spoil heap

For inspection purposes only.
Consent of copyright owner required for any other use.



TP02 – ENE Face



TP02 – SSE Face



TP02 – WSW Face



TP02 – NNW Face



TP02 - Base



TP02 - Spoil heap



TP02 – Spoil heap

For inspection purposes only.
Consent of copyright owner required for any other use.



TP03 – NNW Face



TP03 – ENE Face



TP03 – SSE Face



TP03 – WSW Face



TP03 - Base



TP03 - Spoil heap



TP03 – Spoil heap

For inspection purposes only.
Consent of copyright owner required for any other use.



TP04 – ENE Face



TP04 – SSE Face



TP04 – WSW Face



TP04 – NNW Face



TP04 - Base



TP04 - Spoil heap



TP04 – Spoil heap

For inspection purposes only
Consent of copyright owner required for any other use



TP05 - W Face



TP05 - N Face



TP05 – E Face



TP05 – S Face



TP05 - Base



TP05 - Spoil heap



TP05 – Spoil heap

For inspection purposes only.
Consent of copyright owner required for any other use.



CAUSEWAY
—
GEOTECH

APPENDIX E
GEOTECHNICAL LABORATORY TEST RESULTS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



LABORATORY REPORT



4043

Contract Number: PSL19/3893

Report Date: 06 August 2019
Client's Reference: 18-1068b
Client Name: Causeway Geotech
8 Drumahiskey Road
Ballymoney
Co. Antrim
BT53 7QL

For the attention of: Stephen Watson

Contract Title: Ahascra
Date Received: 26/6/2019
Date Commenced: 26/6/2019
Date Completed: 6/8/2019

Notes: Opinions and Interpretations are outside the UKAS Accreditation

A copy of the Laboratory Schedule of accredited tests as issued by UKAS is attached to this report. This certificate is issued in accordance with the accreditation requirements of the United Kingdom Accreditation Service. The results reported herein relate only to the material supplied to the laboratory. This certificate shall not be reproduced other than in full, without the prior written approval of the laboratory.

Checked and Approved Signatories:

R Gunson
(Director)

S Royle
(Laboratory Manager)

A Watkins
(Director)

S Eyre
(Senior Technician)

R Berriman
(Quality Manager)

L Knight
(Senior Technician)

5 – 7 Hexthorpe Road, Hexthorpe,
Doncaster DN4 0AR
tel: +44 (0)844 815 6641
fax: +44 (0)844 815 6642
e-mail: rgunson@prosoils.co.uk
awatkins@prosoils.co.uk

Page 1 of

PERMEABILITY IN A TRIAXIAL CELL

BS 1377 : Part 6 : 1990: Clause 6

Hole Number: TP03 **Top Depth (m) :** 0.50
Sample Number: 1 **Base Depth (m) :**
Sample Type: B **Lift Number:**
Date **Grid Reference:**

Description of Specimen	
Brown gravelly very sandy very silty CLAY	
Remarks	
Undisturbed	

Initial Specimen Conditions		
Height	mm	103.60
Diameter	mm	101.60
Area	mm ²	8107.32
Volume	cm ³	839.92
Mass	g	1705
Dry Mass	g	1457
Bulk Density	Mg/m ³	2.03
Dry Density	Mg/m ³	1.73
Moisture Content	%	17
Voids Ratio	-	0.528
Specific Gravity (assumed/measured)	Mg/m ³ -	2.65 assumed

Final Specimen Conditions		
Moisture Content	%	19
Bulk Density	Mg/m ³	2.06
Dry Density	Mg/m ³	1.73

Test Setup		
Date Started		31/07/2019
Date Finished		03/08/2019
Top Drain Used		Y
Base Drain Used		Y
Method of Saturation		By back pressure
Direction Of Flow		Vertically Downwards
Saturation Time	Days	1
Consolidation Time	Days	1
Permeability Time	Days	2



PSL
Professional Soils Laboratory


Ahascra

Contract No.
PSL19/3893
Client Ref
18-1068b


PERMEABILITY IN A TRIAXIAL CELL

BS 1377 : Part 6 : 1990 Clause 6

Specimen Details		
Hole Number		TP03
Sample Depth	m	0.50
Sample No.		1
Grid Reference		
Lift Number		
Saturation		
Cell Pressure Incr.	kPa	50
Back Pressure Incr.	kPa	50
Differential Pressure	kPa	10
Final Cell Pressure	kPa	150
Final B Value	-	0.96



Consolidation		
Effective Pressure	kPa	100
Cell Pressure	kPa	400
Back Pressure	kPa	300
Final PWP	kPa	300
PWP dissipation	%	100



PSL
Professional Soils Laboratory

Ahasra


Contract No.
PSL19/3893
Client Ref
18-1068b

PERMEABILITY IN A TRIAXIAL CELL

BS 1377 : Part 6 : 1990 Clause 6

Specimen Details		
Hole Number		TP03
Sample Depth	m	0.50
Sample No.		1
Grid Reference		
Lift Number		

Permeability Stage



Permeability Stage		
Cell Pressure	kPa	400
Mean Effective Stress	kPa	100
Back Pressure Diff.	kPa	20
Mean Rate of Flow	ml/min	0.0033
Average Temperature	'C	20
Vertical Permeability K _v	m/s	3.5E-10



Ahascra

Contract No.
PSL19/3893
Client Ref
18-1068b



CAUSEWAY
— GEOTECH

APPENDIX F
ENVIRONMENTAL LABORATORY TEST RESULTS

*For inspection purposes only.
Consent of copyright owner required for any other use.*



Final Report

Report No.: 19-18929-1

Initial Date of Issue: 17-Jun-2019

Client: Causeway Geotech Ltd

Client Address: 8 Drumahiskey Road
Balnamore
Ballymoney
County Antrim
BT53 7QL

Contact(s): Carin Cornwall
Colm Hurley
Darren O'Mahony
Gabiella Horan
John Cameron
Lucy Newland
Lucy Peaker
Matthew Gilbert
Neil Haggan
Paul Dunlop
Paul McNamara
Sean Ross
Stephen Franey
Stephen Watson
Stuart Abraham

Project: 18-1068b Ahascra

Quotation No.: Q18-13245 **Date Received:** 05-Jun-2019

Order No.: **Date Instructed:** 10-Jun-2019

No. of Samples: 2

Turnaround (Wkdays): 5 **Results Due:** 14-Jun-2019

Date Approved: 17-Jun-2019

Approved By:



Details: Martin Dyer, Laboratory Manager

*For inspection purposes only.
Consent of copyright owner required for any other use.*

Results - Single Stage WAC

Project: 18-1068b Ahascra

Chemtest Job No: 19-18929				Landfill Waste Acceptance Criteria			
Chemtest Sample ID: 837902				Limits			
Sample Ref:					Inert Waste Landfill	Stable, Non-reactive hazardous waste in non-hazardous Landfill	Hazardous Waste Landfill
Sample ID:							
Sample Location: TP03							
Top Depth(m): 2.10							
Bottom Depth(m):							
Sampling Date: 30-May-2019							
Determinand	SOP	Accred.	Units				
Total Organic Carbon	2625	U	%	8.3	3	5	6
Loss On Ignition	2610	U	%	11	--	--	10
Total BTEX	2760	U	mg/kg	< 0.010	6	--	--
Total PCBs (7 Congeners)	2815	U	mg/kg	< 0.10	1	--	--
TPH Total WAC (Mineral Oil)	2670	U	mg/kg	1500	500	--	--
Total (Of 17) PAH's	2700	N	mg/kg	< 2.0	100	--	--
pH	2010	U		8.0	--	>6	--
Acid Neutralisation Capacity	2015	N	mol/kg	0.024	--	To evaluate	To evaluate
Eluate Analysis			10:1 Eluate mg/l	10:1 Eluate mg/kg	Limit values for compliance leaching test using BS EN 12457 at L/S 10 l/kg		
Arsenic	1450	U	0.0014	< 0.050	0.5	2	25
Barium	1450	U	0.045	< 0.50	20	100	300
Cadmium	1450	U	< 0.00010	< 0.010	0.04	1	5
Chromium	1450	U	0.0011	< 0.050	0.5	10	70
Copper	1450	U	0.0030	< 0.050	2	50	100
Mercury	1450	U	0.0026	0.026	0.01	0.2	2
Molybdenum	1450	U	0.036	0.36	0.5	10	30
Nickel	1450	U	0.0057	0.057	0.4	10	40
Lead	1450	U	< 0.0010	< 0.010	0.5	10	50
Antimony	1450	U	0.0068	0.068	0.06	0.7	5
Selenium	1450	U	0.0022	0.022	0.1	0.5	7
Zinc	1450	U	0.036	< 0.50	4	50	200
Chloride	1220	U	3.5	35	800	15000	25000
Fluoride	1220	U	0.31	3.1	10	150	500
Sulphate	1220	U	230	2300	1000	20000	50000
Total Dissolved Solids	1020	N	490	4800	4000	60000	100000
Phenol Index	1920	U	< 0.030	< 0.30	1	-	-
Dissolved Organic Carbon	1610	U	13	130	500	800	1000

Solid Information	
Dry mass of test portion/kg	0.090
Moisture (%)	37

Waste Acceptance Criteria

Landfill WAC analysis (specifically leaching test results) must not be used for hazardous waste classification purposes. This analysis is only applicable for hazardous waste landfill acceptance and does not give any indication as to whether a waste may be hazardous or non-hazardous.

Results - Single Stage WAC

Project: 18-1068b Ahascra

Chemtest Job No: 19-18929 Chemtest Sample ID: 837904 Sample Ref: Sample ID: Sample Location: TP04 Top Depth(m): 2.20 Bottom Depth(m): Sampling Date: 30-May-2019				Landfill Waste Acceptance Criteria Limits			
				Inert Waste Landfill	Stable, Non-reactive hazardous waste in non-hazardous Landfill	Hazardous Waste Landfill	
Determinand	SOP	Accred.	Units				
Total Organic Carbon	2625	U	%	4.1	3	5	
Loss On Ignition	2610	U	%	6.9	--	10	
Total BTEX	2760	U	mg/kg	< 0.010	6	--	
Total PCBs (7 Congeners)	2815	U	mg/kg	< 0.10	1	--	
TPH Total WAC (Mineral Oil)	2670	U	mg/kg	< 10	500	--	
Total (Of 17) PAH's	2700	N	mg/kg	< 2.0	100	--	
pH	2010	U		8.2	--	>6	
Acid Neutralisation Capacity	2015	N	mol/kg	0.036	--	To evaluate	
Eluate Analysis			10:1 Eluate mg/l	10:1 Eluate mg/kg	Limit values for compliance leaching test using BS EN 12457 at L/S 10 l/kg		
Arsenic	1450	U	0.0056	0.056	0.5	2	
Barium	1450	U	0.013	< 0.50	20	100	
Cadmium	1450	U	< 0.0010	< 0.010	0.04	1	
Chromium	1450	U	0.0014	< 0.050	0.5	10	
Copper	1450	U	0.0042	< 0.050	2	50	
Mercury	1450	U	0.0017	0.017	0.01	0.2	
Molybdenum	1450	U	0.019	0.19	0.5	10	
Nickel	1450	U	0.0038	< 0.050	0.4	10	
Lead	1450	U	< 0.0010	< 0.010	0.5	10	
Antimony	1450	U	0.0032	0.032	0.06	0.7	
Selenium	1450	U	0.0015	0.015	0.1	0.5	
Zinc	1450	U	0.0055	< 0.50	4	50	
Chloride	1220	U	5.5	55	800	15000	
Fluoride	1220	U	0.15	1.5	10	150	
Sulphate	1220	U	140	1400	1000	20000	
Total Dissolved Solids	1020	N	310	3100	4000	60000	
Phenol Index	1920	U	< 0.030	< 0.30	1	-	
Dissolved Organic Carbon	1610	U	19	190	500	800	

Solid Information	
Dry mass of test portion/kg	0.090
Moisture (%)	25

Waste Acceptance Criteria

Landfill WAC analysis (specifically leaching test results) must not be used for hazardous waste classification purposes. This analysis is only applicable for hazardous waste landfill acceptance and does not give any indication as to whether a waste may be hazardous or non-hazardous.

Report Information

Key

- U UKAS accredited
- M MCERTS and UKAS accredited
- N Unaccredited
- S This analysis has been subcontracted to a UKAS accredited laboratory that is accredited for this analysis
- SN This analysis has been subcontracted to a UKAS accredited laboratory that is not accredited for this analysis
- T This analysis has been subcontracted to an unaccredited laboratory
- I/S Insufficient Sample
- U/S Unsuitable Sample
- N/E not evaluated
- < "less than"
- > "greater than"

Comments or interpretations are beyond the scope of UKAS accreditation

The results relate only to the items tested

Uncertainty of measurement for the determinands tested are available upon request

None of the results in this report have been recovery corrected

All results are expressed on a dry weight basis

The following tests were analysed on samples as received and the results subsequently corrected to a dry weight basis TPH, BTEX, VOCs, SVOCs, PCBs, Phenols

For all other tests the samples were dried at < 37°C prior to analysis

All Asbestos testing is performed at the indicated laboratory

Issue numbers are sequential starting with 1 all subsequent reports are incremented by 1

Sample Deviation Codes

- A - Date of sampling not supplied
- B - Sample age exceeds stability time (sampling to extraction)
- C - Sample not received in appropriate containers
- D - Broken Container
- E - Insufficient Sample (Applies to LOI in Trommel Fines Only)

Sample Retention and Disposal

All soil samples will be retained for a period of 45 days from the date of receipt

All water samples will be retained for 14 days from the date of receipt

Charges may apply to extended sample storage

If you require extended retention of samples, please email your requirements to:

customerservices@chemtest.com