



LEAK DETECTION SYSTEM CONSTRUCTED UNDER EXTENT OF TANK DIA1000mm LAND DRAINAGE LAID IN HERRINGBONE PATTERN @ 3M CTRS LAID TO FALL 1:250 TO EXTERNAL INSPECTION TANK CAPACITY 2.5cuM DRAIN FOOTPRINT OMITTED FOR CLARITY

THE FOLLOWING TECHNICAL SPECIFICATION REGARDING MINIMUM STANDARD OF WORK & FINISH SHOULD BE USED IN THE WORKS DETAILED FOR SPECIFIC AREAS OF DEVELOPMENT.
 FDS S.123, FOR SLATTED LIVESTOCK UNITS, RE-INFORCED CONCRETE TANKS.
 FDS S.101, SHOULD BE USED AS THE MINIMUM SPECIFICATION FOR FRAMEWORK & S102 FOR ROOF AND SIDE CLADDING OF STRUCTURE.
 FDS S.129, SPECIFICATION FOR FARMYARD DRAINAGE, CONCRETE YARDS & ROADS.
 FDS S.144, MINIMUM SPECIFICATION FOR LODGE DRY SDW UNITS.
 ALL WORK TO BE CONDUCTED IN ACCORDANCE WITH DUTY OF SAFE WORKING ENVIRONMENT UNDER THE SAFETY, HEALTH & WELFARE AT WORK ACT 2005.

FLOOR PLAN

FUTURE PLANNED WORKS OUTLINE IN BLUE

EXISTING WORKS IN GREY

PROPOSED WORKS OUTLINED IN GREEN

PROPOSED WORKS TO BE DEMOLISHED SHOWN IN MAGENTA

Weaner Housing
 Existing Floor Area = 1200sq.m
 Demolishment Floor Area = 1390sq.m
 Reinstated & Extended Floor Area = 4517sq.m
 Of which - New Construction = 3127sq.m

Effluent Capacity
 Existing Tanks = 816cu.m
 Freeboard = 162cu.m
 Proposed Tanks = 3692cu.m
 Freeboard = 738cu.m

Scale: 1:150	Date: 03/08/2022
Drawn by: B.England.	Checked by:
Revision:	Drawing No: A3_3272_A
Drawing Title: PROPOSED AIR VENT STACK PROPOSED WEANER HOUSING FLOOR PLAN	

Brian England Draughting Services
 Stoneyacre, Cloughjordan, Co. Tipperary. Telephone: (0505) 42336. Email: england.brian20@mail.com. © COPYRIGHT BRIAN ENGLAND

Client: WOODVILLE PIG FARM LTD. WOODVILLE, BALLYMACKAY, NENAGH, CO. TIPPERARY.