

ODOUR IMPACT ASSESSMENT
EOIN O'BRIEN PIGS

Rp002 2020191 (Eoin O'Brien Pigs)
25 October 2022

PROJECT: AIR QUALITY IMPACT ASSESSMENT

PREPARED FOR: EOIN O'BRIEN
C/O CLW ENVIRONMENTAL PLANNERS
THE MEWS
23 FARNHAM STREET
CAVAN

ATTENTION: PARAIC FAY

REPORT NO.: Rp 002 2020191- ODOUR

Disclaimer

This report is provided for the stated purposes and for the sole use of the named Client. Irwin Carr Ltd accepts responsibility to the Client alone, that the report has been prepared with the skill, care and diligence of a competent engineer, but accepts no responsibility whatsoever to any parties other than the Client. Any such parties rely upon the report at their own risk.

Copyright

The concepts and information contained in this document are the property of Irwin Carr Ltd. Use or copying of this document in whole or in part without the written permission of Irwin Carr Ltd constitutes an infringement of copyright. Information shall not be assigned to a third party without prior consent.

Document Control

Status:	Rev:	Comments	Date:	Author:	Reviewer:
	1.0		30 March 2021	Christy Carr	Shane Carr
Final	2.0		25 October 2022	Christy Carr	Shane Carr






TABLE OF CONTENTS

1	INTRODUCTION.....	4
1.1	Application Description.....	4
1.2	Application History.....	4
2	ASSESSMENT CRITERIA.....	6
2.1	Odour	6
3	AERMOD DISPERSION MODELLING DATA	7
3.1	AERMOD Dispersion Modelling Package Description	7
3.2	Input Parameters	7
3.2.1	<i>Earth Berm</i>	8
3.2.2	<i>Emissions</i>	9
3.2.3	<i>Mitigation</i>	9
3.2.4	<i>Stack Emissions Velocity</i>	11
3.2.5	<i>Slurry Storage</i>	12
3.3	Meteorological Data	13
3.4	Building Downwash.....	14
3.5	Digital Terrain Data	15
4	RESULTS.....	16
4.1	Odour	16
5	CONCLUSIONS	17
APPENDIX A SITE LAYOUT		
APPENDIX B SOURCE AND RECEPTOR LOCATIONS		
APPENDIX C TECHNICAL SPECIFICATION		
APPENDIX D MODELLING RESULTS		

1 INTRODUCTION

Irwin Carr Ltd have been commissioned to undertake air quality dispersion modelling for an existing pig farm at Mogeely, Co. Cork.

The purpose of this report is to quantify the odour levels at the sensitive properties in the vicinity of the pig farm.

The predicted impact can then be compared to an appropriate criterion and graphically illustrated in the form of 'contours of equal concentration' or isopleths which are superimposed on base maps.

1.1 Application Description

The site is currently has the provision for sixteen mechanically ventilated pig sheds which house a total of 19,910 pigs of varying size and type.

In order to accurately predict the odour impact from the site, all 12 sheds (with updated building names) have been included as part of this assessment as well as 3 on site slurry stores, for the purposes of an EPA licence application.

As part of this application, a low protein diet has been included, the associated reductions of which are included in Section 3.2.3 below.

In addition to the low protein diet detailed above, additional mitigation is also incorporated by way of the regular removal of slurry from the sheds. This slurry will be removed from the sheds in line with the Best Available Techniques (BAT) Reference Document and transported to covered slurry tanks located on site.

The reductions associated with this mitigation have been included on all sheds included as part of this assessment.

1.2 Application History

This report is further to an original assessment completed by Irwin Carr, as well as a consultation response from the EPA dated 1 November 2021. The EPA points in relation to odour are addressed in order below:

- a) *The existing licence includes a condition in relation to low protein feeds (condition 5.4). Therefore, the animals in the 'existing' houses should already be on low protein diets and it would not appropriate to incorporate the full reduction into the modelling for the existing houses;*

The reduction in low protein diet is based on the reduction from the baseline odour emission factor. Irrespective of the crude protein level currently being fed to the pigs, if it is sufficiently reduced below the baseline then the full reduction is applicable for the existing sheds.

- b) *As per the EPA's notice of 05 August 2021 and your response of 01 October 2021, ensure all the animal houses and the storage tanks have the same nomenclature/numbering in the Ammonia Impact Assessment Report as the layout plans;*

Shed numbers have been updated as part of this additional assessment.

- c) *Ensure that the number, dimensions (and also nomenclature as mentioned above) of the external storage tanks outlined in the report correspond with the 'Mogeely Slurry Storage Available' document received on 01 October 2021;*

The shed dimensions have also been amended as part of this additional report.

- d) *With regards to point 2 above, update the modelling if necessary, once the type of cover is confirmed;*

It has been confirmed that both tanks will utilise a rigid cover, which has been accounted for in this assessment.

- e) *Provide justification for the meteorological data used with regards to both wind speed and wind direction. Provide the source of the meteorological data, and specifically the wind speed data, for the site of the installation.*

Additional information is provided in Section 3.3 in relation to meteorological data.

- f) *Provide justification for the surface roughness factor used;*

The surface roughness factor has been updated and is based on the dominant land use type around the site- grassland.

- g) *The co-ordinates for House 15 are incorrect as they correspond to a location off-site). Update the report with the correct co-ordinates;*

Co-ordinates have been amended for the updated shed numbers.

- h) *Confirm that the stack heights for all houses correspond to the release heights outlined in the report. If not and taking into account that most of the development works are already complete, confirm whether houses will be retrofitted or amend the modelling to reflect the existing release heights; and*

Stack heights in Table 12 correspond to the release height of each chimney.

- i) *Refer to the guidance document “Odour Impact Screening and Assessment for Intensive Pig Farms”, which will be published by the EPA shortly, before finalising the Air Quality Impact Assessment Report.*

The updated EPA Guidance¹ has been considered as part of this amended report. Updated emission factors for each animal type are provided in Table 4 as well as clarification on the appropriate reductions associate with the relevant mitigation.

In addition, the applicant has also provided additional information in the form of a letter than details how the number of pigs in each shed has been amended, as well as the building references, but the total number of pigs on site remains the same.

¹ *Instruction note for the assessment of odour emissions from Intensive Agriculture pig installations. Environmental Protection Agency, Ireland. Version 05, August 2022.*

2 ASSESSMENT CRITERIA

The proposed target levels and method of assessment is described in this section.

2.1 Odour

The Environmental Protection Agency provide guidelines for dispersion modelling as well as identifying target odour levels at the nearest sensitive locations in the vicinity of operations such as proposed pig and poultry sites.

Table 1 below shows how different types of processes are categorised and the appropriate odour benchmark values.

Table 1: Odour Benchmark levels

Relative Offensiveness of odour	Benchmark level (ou/s)
Most Offensive odours;	
<ul style="list-style-type: none"> • Processes involving decaying animals or fish • Processes involving septic effluent or sludge • Biological landfill odours 	1.5
Moderately Offensive Odours	
<ul style="list-style-type: none"> • Intensive livestock rearing • Fat frying (food processing) • Sugar beet processing • Well aerated green waste composting 	3.0
Less offensive odours;	
<ul style="list-style-type: none"> • Brewery • Confectionery • Coffee roasting • Bakery 	6.0

Generally, odour concentrations should be below C98, 1-Hour $6\text{ou}_E/\text{m}^3$ in order to prevent complaints arising from existing intensive pig facilities in Ireland.

For the purposes of assessing odorous emissions from the proposed extension to the intensive livestock rearing facility, and in the interests of conservatism, the odour target value of C98, 1-Hour $\leq 6\text{ou}/\text{m}^3$ will be adopted at the nearest sensitive receptor.

To put these guidelines into context, an odour threshold of $1\text{ou}/\text{m}^3$ is the level at which an odour is detectable by 50% of screened panelists. The recognition threshold is about 5 times this concentration i.e. $5\text{ou}/\text{m}^3$. Furthermore, odour concentration of between 5 and $10\text{ou}/\text{m}^3$ above background will give rise to a faint odour and concentrations greater than $10\text{ou}/\text{m}^3$ constitutes a distinct odour and are likely to give rise to nuisance complaints.

Odour assessments are commonly compared to the 98th percentile of hourly averages. For a typical meteorological year the dispersion model predicts 8,760 hourly concentrations for each receptor location. The 98th percentile is part of the statistical distribution, where 98% of the results fall below this value and 2% of the results fall above this value.

3 AERMOD DISPERSION MODELLING DATA

The inputs for the dispersion modelling assessment are described in detail in this Section. A surface roughness factor of 0.2 has been used in the Aermom modelling process, and the results in this report reflect the use of this factor. The site layout, including the nearest residential properties, is shown in Appendix A.

3.1 AERMOD Dispersion Modelling Package Description

The AMS.EPA Regulatory Model (AERMOD) is the current US EPA regulatory model used to predict pollutant concentrations from a wide range of sources that are present at typical industrial facilities.

The model accepts hourly meteorological data to define the conditions for plume rise, transport, diffusion and deposition. It estimates the concentration or deposition value for each source and receptor combination for each hour of input meteorology and calculates user-selected short term averages. The model also takes into account the local terrain surrounding the facility. Since most air quality standards are stipulated as averages or percentiles, AERMOD allows further analysis of the results for comparison purposes.

Percentile analysis for emissions is calculated for the maximum averages using the AERMOD-percent post-processing utility. This utility calculates the maximum concentration of a pollutant from all receptors at a specific percentile, for a specific period. Employing the percentile facilitates the omission of unusual short-term meteorological events that may cause elevated pollutant concentrations and hence a more accurate representation of the likely average pollutant concentrations over an averaging period.

The following information was input into the model for the prediction of maximum ground level ambient ammonia concentrations from the pig farm.

3.2 Input Parameters

The site layout map, building plans and elevations were used as a template for all sources, relevant structures and the boundary of the facility. The AERMOD package uses the steady state Gaussian plume equation for a continuous elevated point or line source. Table 2 and 3 below gives general details of the pig houses.

Table 2: Dimensions of Pig Houses

	Dimensions	Total No. of Pigs	Efflux Temp	Emissions
FS1	88.4m x 22.8m x 6.5m	525 x Dry Sows	20 °C	Mechanically Ventilated
FS2	88.7m x 18.8m x 6.5m	225 x Farrowing	20 °C	Mechanically Ventilated
FS3	71.2m x 16.3m x 6.5m	225 x Farrowing	20 °C	Mechanically Ventilated
FS4	71.2m x 18m x 6.5m	525 x Dry Sows	20 °C	Mechanically Ventilated
FS5	36.9m x 15.1m x 6.5m	800 x Weaners	20 °C	Mechanically Ventilated
FS6	36.7m x 16.3m x 6.5m	900 x Weaners	20 °C	Mechanically Ventilated
FS7	41.2m x 18.7m x 6.5m	1,075 x Weaners	20 °C	Mechanically Ventilated
FS8	41.2m x 18.7m x 6.5m	1,075 x Weaners	20 °C	Mechanically Ventilated
FS9	44.6 x 41.5m x 6.5m	2,150 x Weaners	20 °C	Mechanically Ventilated

Table 3: Dimensions of Fattening Sheds

	Dimensions	Total No. of Pigs per Shed	Efflux Temp	Emissions
FS10	110m x 50.1m x 6.5m	2,600 x Growers 3,900 x Fatteners	20 °C	Mechanically Ventilated
FS11	110m x 35.1m x 6.5m	1,360 x Growers 2,040 x Fatteners	20 °C	Mechanically Ventilated
FS12	55m x 43.5m x 6.5m	840 x Growers 1,260 x Fatteners 410 x Maiden Gilts (incl. 10 x Boars)	20 °C	Mechanically Ventilated

It can be seen from the Table above that sheds FS9 – FS12 include both fattener and grower pigs. A recent EU Commission Implementing Decision (CID)² defines production pigs, which will be housed on site, as,

‘typically reared from a live weight of 30 kg to slaughter or first service. This category includes growers, finishers and gilts that have not been serviced.’

This is evidence that production pigs also include grower pigs. Emission factors for grower pigs are provided in SCAIL and they are defined in BREF as ranging between 30-60kg³.

It should be noted that not all animals on site will be at the maximum finishing weight prior to slaughter at the same time. When the sheds are fully stocked they operate on a continuous flow, rather than a batch type production system, thus at any one time there will be pigs in all the weight ranges the animals will range in weight between 30kg – market weight (c. 110-120 kg). It is expected that no more than 60% of the total animal numbers will be ‘fatteners’ (>60kg) at any time and therefore this assessment considers the worst case scenario of 60% fatteners and 40% growers.”

3.2.1 EARTH BERM

It has been confirmed that there is an earth berm located around all of the sheds on site.

This berm is 8m in height and provides a line of site barrier between all of the sheds on site and the nearest sensitive receptors to the site, specifically to the east.

A drawing showing the earth berm is included in Appendix A and it is represented in the AERMOD model by the inclusion of an 8m building surrounding the site. It should be noted that the natural berm and associated landscaping will offer some absorptive capacity which is not reflected in the AERMOD model given that it has been included as a solid building.

² Commission Implementing Decision (EU) 2017/302 of 15 February 2017 establishing best available techniques (BAT) conclusions, under Directive 2010/75/EU of the European Parliament and of the Council, for the intensive rearing of poultry or pigs.

³ JRC Science for Policy Report. Best Available Techniques for the Intensive Rearing of Poultry and Pigs. Industrial Emissions Directive 2010/75/EU (Integrated Pollution Prevention and Control).

3.2.2 EMISSIONS

The rate of production of an emission, such as odour, is best quantified as an emission rate.

To find the emissions from the house, it was necessary to calculate the concentration within the building. The Section below details the emission rates from the sheds.

3.2.3 MITIGATION

The baseline emission factors for pigs have been outlined in Guidance published by the Environmental Protection Agency¹. Section 4.2 of this Guidance document also details the basic principles for reducing odour emissions, namely:

- *Manipulating dietary protein & supplements: Reduction of the protein content in feed (Page 25, Section 4.2.1).*
- *Improved slurry management offered by integrated housing techniques: Frequent removal of slurry and storage in closed tanks (Page 26, Section 4.2.2.)*

Both of these measures are recognised as Best Available Techniques (BAT) and are included in the BAT Reference Document as recommended reduction measures for both odour and ammonia.

The relevant Sections included in the points above also detail the reductions associated with each measure:

- **Low Protein:** For detailed modelling, it would be reasonable to apply a reduction factor of 10% on the basis of a reduction of 1% crude protein in the diet. The maximum reduction factor that can be applied is 30% linked to a reduction of 3% crude protein in the diet.
- **Frequent Removal of Slurry:** For carrying out detailed modelling it would be reasonable to apply a reduction factor of 25% irrespective of the technique being employed (e.g., frequent slurry removal / slurry cooling).

It has been confirmed that the pigs on site will be fed a diet with a crude protein level of 16%. As a result, an odour reduction of 30% has been applied to the sheds on site.

Section 4.2.3 of the EPA Guidance provides advice on mitigation offered by more than one mitigation technique, as is the case with this proposal. Within the Guidance it is noted,

'Until further scientific evidence is available to the contrary, where two mitigation techniques are operated on the same pig rearing installation, the applicant should be limited to:

- *100% of the odour reduction offered by the first mitigation technique; and*
- *no more than 50% of the odour reduction offered by the second mitigation technique'.*

Given that the mitigation associated with the second technique (frequent removal of slurry) is 25%, only 50% of this has been applied, and the Table below takes account of an additional 12.5% reduction.

Table 4: Final Odour Emission Factors accounting for Mitigation

Category of Animal	Baseline Emission Factor (ou/s/animal)	Total Reduction	Levels after Reduction (ou/s/animal)
Dry Sows	21		12.08
Growers	12		6.90
Fatteners/ Maiden Gilts	20	42.5%	11.50
Farrowing	20		11.50
Weaners*	6	25%	4.50

**The full 25% reduction is applied to weaners for the regular removal of slurry, where no reduction has been applied for the incorporation of a low protein diet.*

Table 5 below details the total emission rates per shed, based on the emission factors calculated above.

Table 5: Concentrations per Building

House No.	No. of Pigs	Odour Emission Factor (ou/s per animal)	Total Odour Emission Factor per Animal Type (ou/s)	Total Odour Emission Rate (ou/s per house)
FS1	525 x Dry Sows	12.08	6,339.4	6,339.4
FS2	225 x Farrowing	11.50	2,587.5	2,587.5
FS3	225 x Farrowing	11.50	2,587.5	2,587.5
FS4	525 x Dry Sows	12.08	6,339.4	6,339.4
FS5	800 x Weaners	4.50	3,600	3,600
FS6	900 x Weaners	4.50	4,050	4,050
FS7	1,075 x Weaners	4.50	4,837.5	4,837.5
FS8	1,075 x Weaners	4.50	4,837.5	4,837.5
FS9	2,150 x Weaners	4.50	9,675	9,675
FS10	2,600 x Growers	6.90	17,940	62,790
	3,900 x Fatteners	11.50	44,850	
FS11	1,360 x Growers	6.90	9,384	32,844
	2,040 x Fatteners	11.50	23,460	
FS12	840 x Growers	6.90	5,796	25,001
	1,670 x Fatteners (incl. 400 x Gilts & 10 x Boars)	11.50	19,205	

The total emission rates are set as the pollutant leaving the building each second.

For the purposes of the modelling process, the emission rate per house was divided by the number of emissions points to obtain the emission value for each source.

Table 6 below shows the emission rates coming out of emission point.

Table 6: Emission Rates for each stack

House No.	No of Fans (and type)	Odour per fan (ou/s)
FS1	3 x BD-FF063 6DT	937
	3 x BD-FF063 Zit (S)	1,176
FS2	12 x Skov DA600	216
FS3	4 x BD-FF063 6DT	287
	4 x BD-FF063 Zit (S)	360
FS4	3 x BD-FF063 6DT	937
	3 x BD-FF063 Zit (S)	1,176
FS5	3 X Skov DA600	1,200
FS6	3 x BD-FF063 6DT	599
	3 x BD-FF063 Zit (S)	751
FS7	6 X Skov DA600	806
FS8	6 X Skov DA600	806
FS9	14 x BD-FF063 Zit (S)	691
FS10	24 x BD-FF091	2,616
FS11	16 x BD-FF091	2,053
FS12	12 x BD-FF091	2,083

3.2.4 STACK EMISSIONS VELOCITY

There are four types of fan on the site, Table 7 below shows the ventilation rates for the chosen fan types.

Table 7: Ventilation Rates for fan

Fan Type	Stack Diameter (m)	Cross Sectional Area (m ²)	Exit Velocity (m/s)	Volume Flow (m ³ /s)	Volume Flow (m ³ /hr)
BD-FF063 6DT	0.63	0.312	10.87	3.39	12,200
BD-FF091	0.91	0.651	9.82	6.39	23,000
Skov DA600	0.6	0.283	11.98	3.39	12,200
BD-FF063 Zit (S)	0.63	0.312	13.63	4.25	15,300

*The technical specifications of these fans are provided in Appendix C.

3.2.5 SLURRY STORAGE

The covering of slurry lagoons with rigid covers is considered best practice and is detailed in the BREF Document⁴ as the best available technique in reducing emissions from lagoons.

It is stated within the BREF Document that,

“Purpose-built (rigid) covers are reported to give reductions of at least 80-90% for ammonia and odour emissions associated with manure storage.”

In the interests of conservatism, an 80% reduction has been applied to the standard emission factor for an uncovered lagoon (2.24 ou/m²/yr), resulting in an emission factor of 0.448 ou/m²/yr for lagoons with rigid covers, as shown in Table 8 below.

Table 8: Concentrations per Building

Source Ref.	Details	Area (m ²)	Cover	Emission Factor (ou/m ² /s)	Total Emissions (ou/s)
FS13	Overground Slurry Tank	255	Rigid Cover	0.448	114
FS14	Covered Slurry Tank	380	Rigid Cover	0.448	170
FS15	Covered Slurry Tank	295	Rigid Cover	0.448	132

The emissions above detail the total odour leaving each of the tanks each second.

⁴ JRC Science for Policy Report. Best Available Techniques (BAT) Reference Document for the Intensive Rearing of Poultry and Pigs. Industrial Emission Directive 2010/75/EU (IPPC). 2017. Section 4.11.2.2

3.3 Meteorological Data

For this assessment, five years' worth of meteorological data (2016 – 2020) has been derived from the three-dimensional Weather Research and Forecasting (WRF) mesoscale model. The data has been generated from a nested domain area centered on the Shannon Airport meteorological site at a grid resolution of 4 km.

The annual wind speed at the site was estimated as 6m/s, as shown on the MET Eireann website⁵. Using a ratio of 0.9 – 1.1, the preferable wind speed for the meteorological site is 5.4m/s – 6.6m/s. It can also be seen from the Figure that the average wind speed at Shannon Airport is approx. 5.5m/s, which is within the preferred range of wind speeds for the site.

Given that the average wind speed at Shannon is similar to that at the source location, and also taking into account that both locations are within approx. 10km of the coast, it was deemed representative of the average wind in the vicinity of the site. This allowed for the determination of the predicted overall average impact of emissions from the facility.

The corresponding meteorological datasets for the assessment have been acquired from Lakes Environmental who utilise the WRF model, a mesoscale numerical weather prediction system designed for both atmospheric research and operational forecasting applications to generate a representative, high resolution meteorological dataset suitable for use within AERMOD. The model is used globally to simulate weather conditions by drawing from observations and archived climatological model data and objective analysis to generate gridded meteorological parameters horizontally and vertically for a region.


Lake Environmental then employ the Mesoscale Model Interface Program (MMIF) to convert the prognostic WRF meteorological model output to AERMET pre-processor data input format prior to use within AERMOD.

Surface roughness of the files was updated and is confirmed as grassland, which is the dominant land type around the site.

The associated wind rose plots derived for each individual year are presented in Figure 1 below.

⁵ MET Eireann website available at: [Wind - Met Éireann - The Irish Meteorological Service](#)

Figure 1: Annual Windrose Data- Shannon Airport



3.4 Building Downwash

When one or more buildings in the vicinity of a point source interrupt wind flow, an area of turbulence known as a building wake is created. Pollutants emitted from a relatively low level can be caught in this turbulence, affecting their dispersion. This phenomenon is called building downwash. In order to conduct an analysis of downwash effects of the point sources created to mimic the release of odorous air from the pig farm, the dimensions (including heights) of the pig houses and other existing buildings on-site was obtained from drawings.

3.5 Digital Terrain Data

AERMOD contains a terrain data pre-processor called AERMAP. Receptor and source elevation data from AERMAP output is formatted for direct insertion into an AERMOD control file. The elevation data are used by AERMOD when calculating air pollutant concentrations.

Regulatory dispersion models applicable for simple to complex terrain situations require information about the surrounding terrain. With the assumption that terrain will affect air quality concentrations at individual receptors, AERMAP first determines the base elevation at each receptor and source. For complex terrain situations, AERMOD captures the essential physics of dispersion in complex terrain and therefore needs elevation data that convey the features of the surrounding terrain. In response to this need, AERMAP searches for the terrain height and location that has the greatest influence on dispersion for each individual receptor. This height is referred to as the hill height scale. Both the base elevation and hill height scale data are produced by AERMAP as a file or files which can be directly inserted into an AERMOD input control file.

4 RESULTS

There are ten residential properties in the immediate vicinity of the pig sheds. A brief description of each location is provided below, along with the co-ordinates and approximate distance to the nearest pig shed.

Table 9: Nearest Residential Properties

Location	Description*	ING Grid Co-ordinates	Approx. distance to pig shed (m)
1	Property to the East	198029 076661	630
2	Property to the East	197727 076617	330
3	Property to the East	197717 076519	295
4	Property to the East	197696 076510	270
5	Property to the East	197599 076453	165
6	Property to the South	197455 076260	195
7	Property to the SE	197719 075775	750
8	Property to the SW	197213 076036	415
9	Property to the SW	197192 075988	465
10	Property to the SW	196738 076074	695

*While the property addresses could not be identified, the exact co-ordinates used in the modelling process are provided in the Table above, and all of the properties are shown in the figure in Appendix A.

4.1 Odour

Odour modelling was carried out for each individual year with the results at the nearest sensitive locations presented in Table 10, with the results graphically presented in Appendix B. All results are the odour concentration in (ou/m³).

Table 10: 98th Percentile of the max 1-hr odour levels at nearest residential properties

Location	2016	2017	2018	2019	2020	Average
1	1.21	1.37	1.28	1.02	1.16	1.21
2	3.06	3.48	3.31	2.77	3.13	3.15
3	2.76	3.31	2.91	2.88	2.90	2.95
4	2.91	3.55	3.06	3.16	3.18	3.17
5	4.51	4.97	3.93	4.52	4.38	4.46
6	3.15	3.66	3.31	3.53	3.20	3.37
7	0.47	0.61	0.58	0.56	0.54	0.55
8	2.25	1.04	1.94	1.53	2.21	1.79
9	1.93	0.86	1.52	1.21	1.88	1.48
10	0.69	0.45	0.70	0.43	0.61	0.58

For the site layout, it can be seen from the Table above that there is no exceedance of the 6ou/m³ in each of the 5 years, or when considered as a 5-year average at all of the receptors in the vicinity of the sheds.

5 CONCLUSIONS


An air quality impact assessment has been undertaken for an extension to an existing pig farm at Mogeely, Co. Cork.

The maximum ground level odour concentration is predicted to be primarily confined to the immediate environs of the pig sheds.

Under the site layout, the maximum 98th percentile of 1-hour ground level odour concentration at the worst effected residential property with no interest in the operation of the pig farm, in the vicinity of the site is in accordance with the target limit value for of $\leq 60 \mu\text{E}/\text{m}^3$ when taken as an average of the 5-year period.

Appendix B indicates the predicted dispersion of the odour plume for 2020 for the site.

APPENDIX A SITE LAYOUT



****Note-** The above diagram is not to scale and is for illustrative purposes only. Exact co-ordinates are given in Table 10 above.



The Figure below shows the 8m high earth berm around the pig site.



APPENDIX B SOURCE AND RECEPTOR LOCATIONS

The information below details the AERMOD model inputs, specifically in relation to source locations, building inputs and grid receptor inputs.

Table 11: Building Location

Building Number	Irish Grid Co-ordinates (SW Corner)
FS1	197344 76431
FS2	197337 76454
FS3	197346 76478
FS4	197340 76496
FS5	197302 76472
FS6	197297 76487
FS7	197288 76504
FS8	197280 76525
FS9	197330 76518
FS10	197251 76543
FS11	197234 76591
FS12	197229 76628
FS13	197373 76425
FS14	197394 76422
FS15	197273 76499

Table 12: Source Locations

Building Number	Source	Source Type*	Release Height (m)	Approx. Irish Grid Co-ordinates (to the nearest 1m)	
FS1	1	A	7.1	197348	76443
	2	D	7.1	197361	76448
	3	A	7.1	197375	76452
	4	D	7.1	197388	76457
	5	A	7.1	197400	76461
	6	D	7.1	197413	76465
FS2	1	C	7.1	197336	76463
	2	C	7.1	197342	76465
	3	C	7.1	197348	76467
	4	C	7.1	197353	76469
	5	C	7.1	197359	76471
	6	C	7.1	197365	76473
	7	C	7.1	197370	76474
	8	C	7.1	197376	76477
	9	C	7.1	197381	76479
	10	C	7.1	197387	76480
	11	C	7.1	197401	76482
	12	C	7.1	197414	76486
FS3	1	A	7.1	197350	76484
	2	D	7.1	197360	76487
	3	A	7.1	197368	76491
	4	D	7.1	197376	76493
	5	A	7.1	197384	76496
	6	D	7.1	197392	76499
	7	A	7.1	197399	76501
	8	D	7.1	197407	76504
FS4	1	A	7.1	197344	76506
	2	D	7.1	197353	76510
	3	A	7.1	197362	76513
	4	D	7.1	197373	76516
	5	A	7.1	197387	76521
	6	D	7.1	197397	76524
FS5	1	C	7.1	197303	76480
	2	C	7.1	197315	76484

Building Number	Source	Source Type*	Release Height (m)	Approx. Irish Grid Co-ordinates (to the nearest 1m)	
	3	C	7.1	197326	76488
FS6	1	A	7.1	197299	76492
	2	D	7.1	197311	76496
	3	A	7.1	197323	76501
	4	D	7.1	197297	76498
	5	A	7.1	197309	76502
	6	D	7.1	197320	76506
FS7	1	C	7.1	197293	76511
	2	C	7.1	197305	76515
	3	C	7.1	197318	76520
	4	C	7.1	197290	76518
	5	C	7.1	197303	76523
	6	C	7.1	197315	76527
FS8	1	C	7.1	197285	76532
	2	C	7.1	197298	76536
	3	C	7.1	197311	76541
	4	C	7.1	197282	76539
	5	C	7.1	197295	76544
	6	C	7.1	197309	76548
FS9	1	D	7.1	197332	76530
	2	D	7.1	197337	76531
	3	D	7.1	197343	76533
	4	D	7.1	197348	76535
	5	D	7.1	197353	76536
	6	D	7.1	197357	76538
	7	D	7.1	197362	76539
	8	D	7.1	197324	76548
	9	D	7.1	197329	76550
	10	D	7.1	197336	76552
	11	D	7.1	197341	76554
	12	D	7.1	197347	76556
	13	D	7.1	197352	76557
	14	D	7.1	197357	76559
	1	B	7.4	197260	76553
	2	B	7.4	197263	76554

Building Number	Source	Source Type*	Release Height (m)	Approx. Irish Grid Co-ordinates (to the nearest 1m)		
FS10	3	B	7.4	197287	76562	
	4	B	7.4	197290	76563	
	5	B	7.4	197312	76571	
	6	B	7.4	197315	76572	
	7	B	7.4	197339	76581	
	8	B	7.4	197342	76581	
	9	B	7.4	197254	76571	
	10	B	7.4	197257	76572	
	11	B	7.4	197281	76580	
	12	B	7.4	197284	76581	
	13	B	7.4	197306	76589	
	14	B	7.4	197308	76590	
	15	B	7.4	197333	76599	
	16	B	7.4	197336	76599	
	17	B	7.4	197248	76587	
	18	B	7.4	197251	76588	
	19	B	7.4	197275	76596	
	20	B	7.4	197278	76597	
	21	B	7.4	197300	76605	
	22	B	7.4	197302	76606	
	23	B	7.4	197327	76615	
	24	B	7.4	197329	76615	
	FS11	1	B	7.4	197242	76603
		2	B	7.4	197245	76604
3		B	7.4	197269	76613	
4		B	7.4	197272	76613	
5		B	7.4	197294	76621	
6		B	7.4	197297	76622	
7		B	7.4	197321	76631	
8		B	7.4	197324	76632	
9		B	7.4	197237	76620	
10		B	7.4	197240	76621	
11		B	7.4	197264	76629	
12		B	7.4	197267	76630	
13		B	7.4	197288	76638	

Building Number	Source	Source Type*	Release Height (m)	Approx. Irish Grid Co-ordinates (to the nearest 1m)	
	14	B	7.4	197291	76639
	15	B	7.4	197316	76648
	16	B	7.4	197318	76648
FS12	1	B	7.4	197239	76638
	2	B	7.4	197242	76638
	3	B	7.4	197266	76647
	4	B	7.4	197269	76648
	5	B	7.4	197235	76652
	6	B	7.4	197237	76653
	7	B	7.4	197262	76662
	8	B	7.4	197264	76662
	9	B	7.4	197230	76666
	10	B	7.4	197233	76667
	11	B	7.4	197257	76675
	12	B	7.4	197260	76676

Details of each source type are provided in Table 8 above and summarised below:

- A: BD-FF063 6DT
- B: BD-FF091
- C: Skov DA600
- D: BD-FF063 Zit (S)

Figure 2: Building Inputs of Sheds FS1 – FS12

Building Inputs

Preview

197200 197300 197400

76700

76600

76500

76400

Selected - Re

Building

Active ID: BLD_1

Base Elevation [m]: 30.95 101.54 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Add
Remove
Convert
Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197344.42

Y Coordinate [m]: 76430.87

Tier Parameters

X-Length [m]: 88.43 290.12 [ft]

Y-Length [m]: 22.80 74.80 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

197200 197300 197400

76700

76600

76500

76400

Selected - Re

Building

Active ID: BLD_2

Base Elevation [m]: 31.02 101.77 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Add
Remove
Convert
Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197336.72

Y Coordinate [m]: 76453.85

Tier Parameters

X-Length [m]: 88.70 291.01 [ft]

Y-Length [m]: 18.80 61.68 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_3

Base Elevation [m]: 31.27 102.59 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197345.81

Y Coordinate [m]: 76478.04

Tier Parameters

X-Length [m]: 71.19 233.56 [ft]

Y-Length [m]: 16.27 53.38 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_4

Base Elevation [m]: 31.99 104.95 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197339.56

Y Coordinate [m]: 76496.47

Tier Parameters

X-Length [m]: 71.19 233.56 [ft]

Y-Length [m]: 18.00 59.06 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_5

Base Elevation [m]: 31.96 104.86 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Buttons: Add, Remove, Convert, Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197301.99

Y Coordinate [m]: 76471.61

Tier Parameters

X-Length [m]: 36.93 121.16 [ft]

Y-Length [m]: 15.06 49.41 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_6

Base Elevation [m]: 32.00 104.99 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Buttons: Add, Remove, Convert, Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197296.64

Y Coordinate [m]: 76486.98

Tier Parameters

X-Length [m]: 36.70 120.41 [ft]

Y-Length [m]: 16.29 53.44 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_7

Base Elevation [m]: 32.00 104.99 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197287.79

Y Coordinate [m]: 76503.69

Tier Parameters

X-Length [m]: 41.21 135.20 [ft]

Y-Length [m]: 18.66 61.22 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_8

Base Elevation [m]: 32.05 105.15 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197280.43

Y Coordinate [m]: 76524.92

Tier Parameters

X-Length [m]: 41.21 135.20 [ft]

Y-Length [m]: 18.66 61.22 [ft]

Rotation Angle [deg]: 19.1

Selected - Reference Point X: 197453.06 [m] Y: 76386.38 [m]

Building Inputs

Preview

Building

Active ID: BLD_9

Base Elevation [m]: 32.68 107.22 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197329.64

Y Coordinate [m]: 76517.65

Tier Parameters

X-Length [m]: 44.60 146.33 [ft]

Y-Length [m]: 41.50 136.15 [ft]

Rotation Angle [deg]: 19.1

Building Inputs

Preview

Building

Active ID: BLD_10

Base Elevation [m]: 33.10 108.60 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197250.77

Y Coordinate [m]: 76543.36

Tier Parameters

X-Length [m]: 110.00 360.89 [ft]

Y-Length [m]: 50.10 164.37 [ft]

Rotation Angle [deg]: 19.0

Building Inputs

Preview

197250 197300 197350 197400 197450

767000

766500

766000

765500

765000

764500

764000

763500

Selected - Re

Building

Active ID: BLD_11

Base Elevation [m]: 34.00 111.55 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Add Remove Convert Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197234.46

Y Coordinate [m]: 76590.78

Tier Parameters

X-Length [m]: 110.00 360.89 [ft]

Y-Length [m]: 35.10 115.16 [ft]

Rotation Angle [deg]: 19.0

Building Inputs

Preview

197250 197300 197350 197400 197450

767000

766500

766000

765500

765000

764500

764000

763500

Selected - Re

Building

Active ID: BLD_12

Base Elevation [m]: 34.03 111.65 [ft]

Description (Optional):

Tiers of Current Building

#	Height [m]	Height [ft]
1	6.50	21.33

Add Remove Convert Sloped Roof

Tier

Type: Rectangular

Reference Point (SW Corner)

X Coordinate [m]: 197229.93

Y Coordinate [m]: 76627.53

Tier Parameters

X-Length [m]: 55.00 180.45 [ft]

Y-Length [m]: 43.50 142.72 [ft]

Rotation Angle [deg]: 19.0

It can be seen from the Figures above that the building locations input in the model reflect a rotation angle of approximately 19 degrees.

It should be noted that the slurry tanks included in the assessment to the south of the site do not appear on the preview tab in each of the Figures above, but they are included in the AERMOD model.

Figure 3: Details of Uniform Cartesian Grid

Uniform Cartesian Grid Receptor Network


Network ID: Actions ▾

	X Axis	Y Axis	
SW Coordinates [m]: <input type="radio"/>	<input type="text" value="196577.40"/>	<input type="text" value="76027.45"/>	
Center Coordinates [m]: <input checked="" type="radio"/>	<input type="text" value="197385.40"/>	<input type="text" value="76661.15"/>	<input type="button" value="Source..."/>
No. of Points:	<input type="text" value="21"/>	<input type="text" value="21"/>	
Spacing [m]:	<input type="text" value="80.8"/>	<input type="text" value="63.37"/>	
Length [m]:	<input type="text" value="1616.00"/>	<input type="text" value="1267.40"/>	

Receptors:

Disable Onsite Receptors
 Disable Offsite Receptors

APPENDIX C TECHNICAL SPECIFICATION



2015.04.07 • 604061



3 Technical Data

3.1 DA 600 LPC

Fan type	445091/445092 DA 600 LPC-11	445086/445087 DA 600 LPC-12	445088/445089 DA 600 LPC-13
Electric			
Voltage [V]	230 -10 % / +15%	230 -10 % / +15%	230 -10 % / +15%
Frequency [Hz]	50/60	50/60	50/60
Motor current [A] (for Motor relay)	4.2	4.2	4.2
Power [W]	800	800	800
Adjustment ability	Adjustable	Adjustable	Adjustable
Motor protection	Thermistor	Thermistor	Thermistor
Motor relay	None	None	None
Mechanic			
Cable length [m]	Max. 2m shielded cable	Max. 2m shielded cable	Max. 2m shielded cable
Min. duct diameter [mm]	638	638	638
Blade diameter [mm]	625	625	625
Number of blades [pcs.]	3	3	3
Blade pitch [°]	Periferi 25 Nav 45	Periferi 25 Nav 45	Periferi 25 Nav 45
Fan output			
Revolutions [per minute] (mark)	300-1,100	300-1,200	300-1,300
Air output [m ³ /h] (at -10 Pa)	13,400	14,600	15,800
Air output [m ³ /h] (at -20 Pa)	13,100	14,400	15,500
Air output [m ³ /h] (at -30 Pa)	12,900	14,100	15,200
Air output [m ³ /h] (at -40 Pa)	12,500	13,800	15,100
Air output [m ³ /h] (at -50 Pa)	12,000	13,400	14,700
Air output [m ³ /h] (at -60 Pa)	11,600	13,000	14,400
Power consumption [W] (at -10 Pa)	418	527	645
Specific output [m ³ /kWh] (at -10 Pa)	32,300	27,700	24,500
Specific energy [Watt/1000 m ³ /h] (at -10 Pa)	31	36	41
Pressure stability, change from 0 to -20 Pa [%]	4	3	3
Test authorities	Bygholm AAU/ SKOV A/S	Bygholm AAU/ SKOV A/S	Bygholm AAU/ SKOV A/S
Environment			
Operating temperature	÷ 40 °C to +40 °C (÷40 to 104 °F)		
Start temperature	÷ 40 °C to +50 °C (÷40 to 122 °F)		
Storage temperature	÷ 40 °C to +70 °C (÷40 to 158 °F)		
Ambient humidity, operation	10-95 % RH		



Code no.	Description*
60-47-7902	Fan FF063-6DT 3Ph 50/60Hz 230/400V 2,2/1,25A 0,54kW 12900m ³ /h Rohreinbau f/CL600 ErP2015

*Description adapted to frequency

Valid for the following chimneys
Exhaust air chimney CL 600 gray/brown

Technical data	
Phase:	3
Frequency ¹⁾ :	50/60Hz
Nominal voltage (Y/D):	230/400 V
Nominal current (Y/D):	2,2/1,25 A
Nominal capacity:	0,54 kW
Speed:	930 rpm
Min. ambient temperature:	-40°C
Max. ambient temperature:	+70°C
Acoustic power level:	71 dB(A)
Sound pressure level ²⁾ :	46 dB(A)
Protection class:	IP54
Certificates:	CE, ErP2015
Controllable by:	Frequency converter (w/ all-pole sine filter) / transformer / triac

1) electrical values refer to 50Hz

2) measured at a distance of 7m




Please note:
Picture may deviate from original product


Pressure [Pa]	Volumetric flow rate [m ³ /h]	Specific power [W/(1000m ³ /h)]	Velocity ³⁾ [m/s]
0	12.921	33,4	10,8
10	12.504	35,5	10,5
20	12.075	37,4	10,1
30	11.523	39,9	9,6
40	10.741	44,0	9,0
50	9.713	49,5	8,1
60	7.291	63,9	6,1

3) at tube outlet

Fan characteristics



Dimensions:



CL600: [mm]	
D_i	650
D_a	666
H	Height varies

Schematic

Setpoints for controlled fans

Up to 20 Pa

Setpoint no.	Fan [%] FC / Triac	Capacity [%] FC / Triac	Flap [%] FC / Triac
0	0 / 0	0 / 0	0 / 0
1	59 / 57	15 / 14	42 / 42
2	59 / 57	31 / 29	60 / 60
3	59 / 57	43 / 43	73 / 73
4	59 / 57	57 / 57	100 / 100
5	71 / 70	71 / 71	100 / 100
6	86 / 85	85 / 85	100 / 100
7	100 / 100	100 / 100	100 / 100

Up to 40 Pa

Setpoint no.	Fan [%] FC / Triac	Capacity [%] FC / Triac	Flap [%] FC / Triac
0	0 / 0	0 / 0	0 / 0
1	71 / 70	14 / 14	37 / 38
2	71 / 70	29 / 29	53 / 54
3	71 / 70	43 / 44	65 / 67
4	71 / 70	58 / 57	77 / 77
5	71 / 70	71 / 71	100 / 100
6	86 / 85	85 / 85	100 / 100
7	100 / 100	100 / 100	100 / 100

Code no.	Description*
60-47-8973	Fan EC-Blue FF063-ZIT 1Ph 50/60Hz 200-277V 4,6-3,3A 0,92kW 15600m ³ /h Rohreinbau f/CL600 ErP2015

*Description adapted to frequency

Valid for the following chimneys
Exhaust air chimney CL 600 gray/brown

Technical data	
Phase:	1
Frequency ¹⁾ :	50/60Hz
Nominal voltage:	200-277 V
Nominal current:	4,6-3,3 A
Nominal capacity:	0,92 kW
Speed:	1200 rpm
Min. ambient temperature:	-35°C
Max. ambient temperature:	+55°C
Acoustic power level:	75 dB(A)
Sound pressure level ²⁾ :	50 dB(A)
Protection class:	IP55
Certificates:	CE, UL, ErP2015
Controllable by:	0-10V

1) electrical values refer to 50Hz

2) measured at a distance of 7m




Please note:
Picture may deviate from original product


Pressure [Pa]	Volumetric flow rate [m ³ /h]	Specific power [W/(1000m ³ /h)]	Velocity ³⁾ [m/s]
0	15.610	43,8	13,1
10	15.238	45,9	12,8
20	14.944	47,7	12,5
30	14.547	50,0	12,2
40	14.144	52,8	11,8
50	13.708	55,5	11,5
60	13.191	59,3	11,0
70	12.539	63,8	10,5
80	11.735	69,0	9,8
90	10.150	78,4	8,5
100	7.203	107,9	6,0

3) at tube outlet

Fan characteristics



Dimensions:



CL600: [mm]	
D_i	650
D_a	666
H	Height varies

Schematic

Setpoints for controlled fans

Up to 20 Pa

Setpoint no.	Fan [%]	Capacity [%]	Flap [%]
	EC	EC	EC
0	0	0	0
1	57	13	39
2	57	29	57
3	57	43	72
4	57	57	100
5	71	71	100
6	85	85	100
7	100	100	100

Up to 40 Pa

Setpoint no.	Fan [%]	Capacity [%]	Flap [%]
	EC	EC	EC
0	0	0	0
1	71	13	35
2	71	29	51
3	71	43	64
4	71	57	74
5	71	71	100
6	85	85	100
7	100	100	100

Code no.	Description*
60-47-8991	Fan EC-Blue FF091-ZIT 1Ph 50/60Hz 200-277V 5-3,6A 0,96kW 26000m ³ /h Rohreinbau ErP2015

*Description adapted to frequency

Valid for the following chimneys
Exhaust air chimney BD 920/50-AF gray/brown
Exhaust air chimney BD 920/30-AF gray/brown
Exhaust air chimney BD 920/30-VC gray/brown
Exhaust air chimney CL 920-30-2 gray/black

Technical data	
Phase:	1
Frequency ¹⁾ :	50/60Hz
Nominal voltage:	200-277 V
Nominal current:	5-3,6 A
Nominal capacity:	0,96 kW
Speed:	950 rpm
Min. ambient temperature:	-35°C
Max. ambient temperature:	+40°C
Acoustic power level:	77 dB(A)
Sound pressure level ²⁾ :	52 dB(A)
Protection class:	IP55
Certificates:	CE, UL, ErP2015
Controllable by:	0-10V

1) electrical values refer to 50Hz

2) measured at a distance of 7m




Please note:
Picture may deviate from original product


Pressure [Pa]	Volumetric flow rate [m ³ /h]	Specific power [W/(1000m ³ /h)]	Velocity ³⁾ [m/s]
0	26.044	27,1	10,9
10	25.123	29,2	10,5
20	24.204	31,6	10,1
30	23.286	34,1	9,7
40	22.270	37,0	9,3
50	21.185	40,0	8,9
60	19.920	43,3	8,3
70	18.275	47,8	7,6
80	16.637	52,7	7,0
90	14.841	59,1	6,2
100	12.502	69,8	5,2

3) at tube outlet

Fan characteristics




Dimensions:



Schematic

	Air duct: [mm]	Agroflex / Varioclip: [mm]	CL920-2: [mm]
T	50	30	33
D _i	920	920	920
D _a	1024	984	1004
L	1230	1190	1204
A _{min}	1065	1025	1030
A _{max}	1090	1050	1064
M _{min}	1330	1290	1304
H	Height varies		



Setpoints for controlled fans

Up to 20 Pa

Setpoint no.	Fan [%]	Capacity [%]	Flap [%]
	EC	EC	EC
0	0	0	0
1	57	13	44
2	57	28	61
3	57	43	77
4	57	57	100
5	71	71	100
6	85	85	100
7	100	100	100

Up to 40 Pa

Setpoint no.	Fan [%]	Capacity [%]	Flap [%]
	EC	EC	EC
0	0	0	0
1	71	13	41
2	71	29	57
3	71	43	68
4	71	57	81
5	71	71	100
6	85	85	100
7	100	100	100

APPENDIX D MODELLING RESULTS

PROJECT TITLE:

Eoin O'Brien Pigs

98th Percentile of Max 1-Hour Ground Level Odour Concentration (ou/m³) (2020)

COMMENTS:

SOURCES:

122

RECEPTORS:

451

OUTPUT TYPE:

Concentration

MAX:

31 OU/M3**

MODELER:

Christy Carr

DATE:

25/10/2022

SCALE:


1:9,743

0  0.3 km

IRWIN CARR
CONSULTANTS 

PROJECT NO.:

2020191



OU/M**3

PLOT FILE OF 98.00TH PERCENTILE 1-HR VALUES FOR SOURCE GROUP: ALL
Max: 31 [OU/M**3] at (197203.00, 76661.20)

